

SOUTHEAST METRO STORMWATER AUTHORITY
acting by and through
SEMSWA WATER ACTIVITY ENTERPRISE

RESOLUTION 18-13
Approval of the Grading, Erosion, and Sediment Control Manual, as updated

WHEREAS, the Colorado Department of Public Health and Environment (CDPHE) issues and administers discharge permits and other control mechanisms as provided by the Colorado Water Quality Control Act (25-8-101 et seq., CRS, 1973) and the Federal Water Pollution Control Act, as amended (33 U.S.C. 1251 et seq.; the "Act"); and

WHEREAS, the Southeast Metro Stormwater Authority (SEMSWA) has been authorized to discharge stormwater associated with their Municipal Separate Storm Sewer (MS4) system in accordance with the Colorado Discharge Permit System (CDPS) General Permit No. COR-080021, effective July 1, 2016 (MS4 Permit), specifically for discharges wholly or partly within the Cherry Creek Reservoir drainage basin; and

WHEREAS, in accordance with the MS4 Permit, CDPHE requires SEMSWA to implement stormwater control measures (Programs), of which the Construction Sites Program requires SEMSWA to ensure adequate design, implementation, maintenance, and enforcement related to construction site stormwater runoff; and

WHEREAS, the SEMSWA Board of Directors adopted the SEMSWA Grading, Erosion, and Sediment Control (GESC) Manual as Resolution No. 10-42, to set forth the GESC Permitting Program to meet the Construction Sites Program requirements, for the purposes of ensuring compliance with the MS4 Permit through adequate design, implementation, maintenance, and enforcement of Control Measures (CMs) at construction sites in the City of Centennial; and

WHEREAS, the SEMSWA GESC Manual has been updated to adhere to the Construction Sites Program requirements of the MS4 Permit, to provide more streamlined GESC permitting approaches, and to recognize the evolution of GESC practices and CMs since the original SEMSWA GESC Manual adoption in 2010.

NOW, THEREFORE, BE IT RESOLVED THAT:

1. The Board adopts the SEMSWA GESC Manual, as attached hereto as **Exhibit A**.
2. The Board authorizes the use of the SEMSWA GESC Manual in administering and enforcing the MS4 Permit Construction Sites Program within the boundaries of the City of Centennial.

3. The Board authorizes the Executive Director to make any minor non-substantive modifications to the GESC Manual without prior Board approval.

SOUTHEAST METRO STORMWATER AUTHORITY
acting by and through
SEMSWA WATER ACTIVITY ENTERPRISE

Date: _____

ATTEST:

Secretary

Chairperson

APPROVED AS TO FORM:
Attorney for
Southeast Metro Stormwater Authority

By _____
Edward J. Krisor




GESC MANUAL



May 2018

Grading, Erosion and
Sediment Control
Requirements



The original Grading, Erosion and Sediment Control (GESC) Manual, published in 2005, was an adaptation of the Douglas County GESC Manual, which at the time was a state-of-the-art approach to erosion and sediment control. SEMSWA appreciates the effort and expertise that went in to the development of the Douglas County GESC Manual, and the original 2005 GESC Manual was a very valuable tool to manage SEMSWA's Construction Sites Control program requirements of the State-issued MS4 General Permit.

This 2018 edition of the SEMSWA GESC Manual is a recognition of several critical components in the effort to control sediment and construction waste pollutants from land disturbance sites that could impact our waterways:

- 1. The Denver Metro areas increased utilization of GESC concepts at construction sites, and the technical advances that brings;*
- 2. The construction industry's continuous improvement in the field application of erosion and sediment control measures;*
- 3. The increasing acceptance of GESC principles by the development community to protect the natural resources their development can potentially impact;*
- 4. The expanding knowledge of the development Design Engineer professionals who use their expertise to prepare the GESC Plan/Report for implementation;*
- 5. SEMSWA's acknowledgement of a Contractor's inherent knowledge of what will work at their site, in tandem with refining what erosion, sediment and waste controls will meet requirements in a cost-effective manner; and*
- 6. SEMSWA's development of streamlined permit approaches and recognition of selected land disturbance activities under an acre that do not have the potential to adversely impact drainage patterns, or the drainageway.*

The 2005 GESC Manual told the compelling story of land disturbance impacts on waterways, the need for controls to be in place at a site, and the role of SEMSWA, Developers, Engineers, Contractors and Regulators in GESC compliance, in a reader-friendly format with pictures, graphics, and call-outs. While this comprehensive approach was considered very important in the early days of GESC implementation, it has been over 10 years since SEMSWA started regulating per the GESC Manual. This span of time has seen much formal and informal interaction between SEMSWA and land owners, SEMSWA staff and development Design Engineers, and the SEMSWA Inspectors and Contractors. This collaboration has evolved GESC practices, such that this 2018 GESC Manual can now leave story-telling behind and concentrate on simply stating the GESC requirements at any land disturbance site. This evolution has resulted in a trimmed manual that SEMSWA hopes will provide an easier reference for Design Engineers in the office and Contractors in the field. SEMSWA staff are available to fill in any gaps in knowledge about the GESC back-story and look forward to answering any questions about the procedural content of this 2018 GESC Manual.

CONTENTS

1	The GESC Permit.....	5
1.1	Interpretation	6
1.2	Relationship to Other Standards.....	6
1.3	State Permitting	6
1.4	Federal Permits and Requirements	7
2	GESC Permitting Process.....	7
2.1	Projects that Require a GESC Permit	7
2.2	Who Obtains a GESC Permit?.....	8
2.3	Review and Acceptance	8
3	Types of GESC Permits	9
3.1	Standard GESC Permit.....	9
3.2	Low Impact GESC Permit.....	11
3.3	Single-Family Individual Lot GESC Permit	12
3.4	Annual GESC Permit.....	13
3.5	Low Risk GESC Process	14
4	GESC Permit Policies	14
4.1	Signed GESC Plan and Report	14
4.2	GESC Permit Expiration	14
4.3	GESC Permits with Property or Project Ownership Transfers	15
4.4	Responsibilities for Single-Family Residential Projects.....	15
4.5	GESC Permittee Sells a Portion of the Land/Project Area to a Builder	16
4.6	Review Fees	16
4.7	Consistency with Other Plans	16
4.8	Early Grading Permit Requirements	16
4.9	Permit Fees	16
4.10	Engineering Cost Estimate	16
4.11	Collateral Posting.....	17
4.12	Variances to the GESC Manual.....	18
5	GESC Permit Close-Out	19
5.1	Initial Close-Out	19
5.2	Required Inspections and Maintenance after Initial Close-Out.....	20
5.3	Final Vegetation Acceptance	20
5.4	Removal of Final Stabilization Control Measures	20

5.5	Final Close-Out Inspection	20
6	Enforcement	21
6.1	Non-compliance	21
6.2	SEMSWA Right to Complete GESC Control Measures	21
6.3	Use of Funds by SEMSWA	22
7	Field Policies	22
7.1	Responsibilities of the GESC Manager	22
7.2	Availability of the GESC Manager	22
7.3	Changing the GESC Manager or Alternate	22
7.4	Documents that Shall Remain On Site	23
7.5	Preconstruction Meeting	23
7.6	Topsoil Preservation	23
7.7	Stabilization	23
7.8	Installation of Interim and Final Control Measures	24
8	Required GESC Inspections	24
8.1	GESC Inspections Conducted by Permittee	24
8.2	GESC Inspections Conducted by SEMSWA	24
9	Site Grading Design Guidance and Criteria	25
9.1	Slopes	25
9.2	Stockpiles	25
10	General Construction Practices	25
10.1	Limits of Construction	26
10.2	Street Cleaning	26
10.3	Dust Control	26
10.4	Construction Site Waste Control	26
10.5	Potential Pollutants at a Construction Site	26
10.6	Equipment Maintenance	27
10.7	Spills and Leaks	28
11	Design, Installation, and Maintenance of Control Measures	28
11.1	Use of Control Measures	28
11.2	Check Dam (CD) / Reinforced Check Dam (RCD)	28
11.3	6.3.3 Concrete Washout Area (CWA)/Grout Washout Area (GWA)	30
11.4	Construction Fence (CF)/Construction Markers (CM)	30
11.5	Dewatering as it Relates to Surface Water (DW)	31

11.6	Diversion Ditch (DD).....	31
11.7	Erosion Control Blanket (ECB).....	32
11.8	Grade Differential/Curb Cut Back (GD/CCB)	35
11.9	Grout Mixing Stations (GMS)	35
11.10	Inlet Protection (IP)	36
11.11	Reinforced Rock Berm (RRB)	37
11.12	Sediment Basin (SB).....	37
11.13	Sediment Control Log (SCL)	39
11.14	Sediment Trap (ST)	40
11.15	Seeding and Mulching (SM)	40
11.16	Silt Fence (SF).....	41
11.17	Slope Intercept Ditch (SID)	42
11.18	Stabilized Staging Area (SSA)	43
11.19	6.3.18 Street Sweeping (SS).....	43
11.20	Surface Roughening (SR)	43
11.21	Temporary Slope Drain (TSD)	44
11.22	Temporary Stream Crossing (TSC)	44
11.23	Vehicle Tracking Control (VTC)	45
11.24	Vehicle Tracking Control with Wheel Wash (WW)	46
12	Authorization of the GESC Manual	46
12.1	Amendments and Revisions.....	46
12.2	Enforcement Responsibility	46

List of Appendices:

- A. GESC Contact Information
- B. Early Grading Form Letter
- C. Engineer's Cost Estimates
- D. Example Single-Family Individual Lot GESC Plans
- E. GESC Plan and Report Checklists
- F. GESC Plan Standard Notes and Details
- G. Control Measure Legend and Approval Block
- H. Definitions

This Grading, Erosion and Sediment Control Manual (*GESC Manual*) describes the permitting program adopted by the Southeast Metro Stormwater Authority (SEMSWA) to promote environmentally sound construction practices in the City of Centennial. The GESC Permit Program shall apply to the SEMSWA Permit Implementation Area within the City of Centennial, hereafter referred to as "City."

The development, implementation, and enforcement of the SEMSWA GESC Permit Program is mandated by both the Federal Government and the State of Colorado (State). The Federal Clean Water Act's National Pollutant Discharge Elimination System (NPDES) Stormwater Regulations require that stormwater discharges from certain types of facilities be authorized under discharge permits (40 C.F.R., 122.26). The State of Colorado has assumed the responsibility to authorize these discharges under the Colorado Discharge Permit System (CDPS) and has enacted Regulation 61 of the Colorado Water Quality Control Act (CWQCA) as the regulatory requirement. The City, as a municipality, has been classified by the State as a Municipal Separate Storm Sewer System (MS4). SEMSWA has assumed the City's responsibilities as an MS4 and is authorized to discharge stormwater under the CDPS.

The goal of the GESC Permit Program is to implement effective erosion and sediment control measures or BMPs (Best Management Practices) as a standard for all land disturbance activities to reduce increases in erosion and sedimentation over pre-development conditions. During the relatively short period of time when undeveloped land is converted to urban uses or developed land is redeveloped, a significant amount of sediment can erode from a construction site and be transported to adjacent properties and receiving waters. Erosion caused by land disturbing activities, and the resulting downstream sedimentation, can damage property and degrade the quality of streams and lakes. Sediment is a transport mechanism for many stormwater pollutants. Eroded sediment can impact riparian and aquatic habitat and, since eroded sediments often contain significant phosphorus, this can lead to unwanted algae growth in lakes and reservoirs. SEMSWA is committed to protecting water resources and ensuring that future development continues in an environmentally sound manner.

The **Colorado Water Quality Control Act (CCR 61.8(11) (a) (ii) (D))** requires SEMSWA to: "...develop, implement, and enforce a program to reduce pollutants in any storm water runoff to the MS4 from construction activities that result in a land disturbance of greater than or equal to one acre. Reduction of pollutants in stormwater discharges from construction activity disturbing less than one acre must be included in the program if that construction activity is part of a larger common plan of development or sale that would disturb one acre or more. The program must be developed and implemented to assure adequate design, implementation, and maintenance of control measures at construction sites within the MS4 [SEMSWA] to reduce pollutant discharges and protect water quality. The program must include the development and implementation of, at a minimum:

- An ordinance or other regulatory mechanism to require erosion and sediment controls, as well as sanctions to ensure compliance, to the extent allowable under State or local law;
- Requirements for construction site operators to implement appropriate erosion and sediment controls;
- Requirements for construction site operators to control waste such as discarded building materials, concrete truck washout, chemicals, litter, and sanitary waste at the construction site that may cause adverse impacts to water quality;
- Procedures for site plan review which incorporate consideration of potential water quality impacts;
- Procedures for receipt and consideration of information submitted by the public; and
- Procedures for site inspection and enforcement of control measures.

The GESC Permit Program complies with these requirements.

In addition to the CDPS program requirements, SEMSWA as the MS4, is responsible for complying with **Cherry Creek Reservoir Control Regulation No. 72**, as amended and promulgated by the Water Quality Control Commission (WQCC) pursuant to the CWQCA, Sections 25- 8-202(1)(c) and 25-8-205, *et seq.*, C.R.S. This regulation, affecting approximately 18.6 square miles of Arapahoe County and the City within the Cherry Creek Watershed as well as many other jurisdictions, identifies specific requirements for erosion and sediment control measures on construction sites, including placing limits on the area of land that can be disturbed at any one time. The intent of the regulation is to protect the water quality of Cherry Creek Reservoir.

The GESC Permit Program complies with these requirements.

INTERPRETATION

1.1

In the interpretation and application of the provisions of this *GESC Manual*, the following shall govern: These provisions shall be regarded as the minimum requirements for the protection of the public health, safety, comfort, convenience, prosperity, and welfare of the residents of the City. The *GESC Manual* shall, therefore, be regarded as remedial and shall be liberally construed to further its underlying purposes.

Whenever a provision in these criteria or any provision in any law, ordinance, resolution, rule or regulation of any kind, contain restrictions covering same subject matter, **whichever is more restrictive or imposes higher standards shall govern**. If there is a discrepancy in the interpretation of the *GESC Manual*, the Executive Director shall make the final determination of the intent of the *GESC Manual*.

The *GESC Manual* shall not abrogate or annul any permits or approved drainage reports or construction plans issued before the effective date of this *GESC Manual*.

RELATIONSHIP TO OTHER STANDARDS

1.2

If a special district or other adjacent jurisdiction imposes more stringent criteria, such differences are not considered conflicts. When differences arise, the more stringent requirements shall apply. If Federal or State law imposes stricter criteria, standards or requirements on SEMSWA, such shall be incorporated into SEMSWA's requirements after proper notice and public hearing (s) needed to modify SEMSWA's regulations and standards.

STATE PERMITTING

1.3

The State of Colorado requires separate, additional permits for construction-related activities. The Applicant or the Design Engineer shall contact the Colorado Department of Public Health and Environment, Water Quality Control Division (WQCD) for specific State permitting information for a specific project. Contact information for the WQCD is provided in Appendix A.

Information on some of the State permits that may be applicable is listed in the sections below. This is not to be considered a complete list; therefore, Applicants are advised to contact the State.

STORMWATER MANAGEMENT PLAN

In compliance with the CDPS Stormwater Permit Program, the State requires that construction projects exceeding one (1) acre of disturbance must obtain a Stormwater Construction Permit and develop a Stormwater Management Plan (SWMP).

CONSTRUCTION DEWATERING PERMITS

The State issues a permit for “Discharges Associated with Construction Activities” to manage dewatering discharges from construction projects. The permit establishes water quality standards and control measures for dewatering discharges. Additional permitting from the State Engineer’s Office may be required if it is determined that there is a consumptive water use or loss.

FEDERAL PERMITS AND REQUIREMENTS

Applicants are also responsible for complying with all applicable Federal permits and requirements. This may include, but is not limited to, the Federal Emergency Management Agency (FEMA) map revision process, the United States Army Corps of Engineers (Corps) Section 404 Permit and the United States Fish and Wildlife Service, Endangered Species Act Section 10 and/or Section 7 Permits.

Information on some of the Federal programs and permits that may be applicable are included in the section below (this is not to be considered a complete list; therefore, Applicants are advised to confirm the Federal requirements that may apply).

FEMA MAP REVISIONS

Projects that impact the regulatory floodplain may need to obtain a Conditional Letter of Map Revision (CLOMR) and/or Letter of Map Revision (LOMR) from FEMA. In this case, proper documentation needs to be submitted to FEMA for review and approval.

SECTION 404 PERMITTING

Excavation activity associated with a dredge and/or fill project in “Waters of the United States” (including streams, open water lakes, ponds, wetlands, etc.) may require a Section 404 Permit and/or other permitting. The level of permitting is dependent on the nature and extent of the disturbances within the water body of interest. The Corps should determine if a Nationwide Permit or an Individual Permit is required. Individual Permits will require more detailed information about the project and preparation of exhibits specific to the project site.

2 GESC PERMITTING PROCESS

SEMSWA requires that a GESC Permit be obtained prior to the start of any land-disturbing activities associated with construction within the City in accordance with the GESC Permitting Matrix found on SEMSWA's website, www.SEMSWA.org. *Additionally, any project that the Executive Director determines to have an adverse impact on the public right-of-way, public infrastructure, or adjacent property, with respect to grading, erosion, and sediment control will be required to obtain a GESC Permit.*

PROJECTS THAT REQUIRE A GESC PERMIT

To facilitate project permitting and the inspection process, and to avoid the need for duplicate plan review, approval, and permit issuance, SEMSWA may relinquish control of grading, erosion, sediment, and waste control requirements to a neighboring MS4’s Permit Program if there is an agreement in place with the neighboring entity and if much of the project is within that other jurisdiction’s program. The neighboring entity may assume full jurisdictional control for construction site stormwater runoff control activities, including plan review and approval, permit issuance,

inspections, oversight and enforcement for the entire project, including those areas in the SEMSWA Permit Area, only when a site-specific agreement between the neighboring entity and SEMSWA exists. SEMSWA shall reserve the right to protect its MS4 system when contaminated water flows off the project and into the local storm sewer system per SEMSWA's Illicit Discharge Program, up to and including all remedies available. Neighboring MS4's may relinquish control of the grading, erosion, sediment, and waste control requirements to SEMSWA if most of the project is within SEMSWA's jurisdiction. A specific agreement between the neighboring entity and SEMSWA will be required.

PROJECTS COVERED UNDER OTHER PERMITS

GESC Permits are required for projects meeting the GESC Permitting Matrix criteria, even if a Federal or State agency, or another jurisdiction, has approved the project and issued their permit(s) for the work. The GESC Plan and Report are specific to the GESC Program, and do not meet the requirement for a SWMP.

WHO OBTAINS A GESC PERMIT?

2.2

GESC Permits are signed by both the Project Owner and the Contractor. Prior to issuance of a GESC Permit, the Owner and the Contractor are referred to as "Applicants." After the Permit is issued, both are considered "Permittees" and must comply with the GESC Permitting requirements. The specific contractual relationship between the Owner and Contractor as the Permittees must allow for immediate correction of deficiencies.

A Permittee is defined as "any person(s) who is issued a GESC Permit by SEMSWA." The Permittee shall be legally responsible for compliance with the GESC Permit. If the Applicant is not an individual, an authorized agent of the entity must sign the permit on behalf of the Permittee.

Permittees conducting land-disturbing activities are responsible for meeting all requirements of SEMSWA's GESC Permit Program that are described in detail within the *GESC Manual*. Failure to meet the requirements of the GESC Permit may lead to enforcement action (See Section 6, Enforcement).

REVIEW AND ACCEPTANCE

2.3

SEMSWA will review the GESC Permit Program submittals for general compliance with the criteria contained herein. An acceptance of submitted documents by SEMSWA does not relieve the Owner's Design Engineer or eventual Permittee(s) of responsibility for ensuring that calculations, plans, specifications, and construction comply with the criteria contained herein. Additionally, acceptance by SEMSWA does not alleviate the Design Engineer or Permittee(s) from complying with all other applicable Federal, State, or Local regulations.

AMENDMENTS

SEMSWA allows minor GESC Plan and Report modifications without re-review and approval. The Permittee must update the GESC Plan and Report as necessary to reflect site conditions. All minor modification shall be implemented immediately and recorded on the GESC Plan. SEMSWA expects that the Permittee will need to make minor GESC modifications throughout a project to address changes in site conditions. Minor GESC modifications generally include Control Measure substitutions for other measures that are equivalent in performance and/or are more suitable to specific site conditions.

Major modifications to a GESC Plan, are those involving re-engineering or changes to site hydrology (e.g. increased area tributary to a Control Measure; site conditions beyond the limits of a Control Measure; eliminating a Control Measure; changes to grading, drainage, or design intent). The modifications must be submitted to SEMSWA for

review and acceptance. Control Measures that may be classified as a major modification are indicated with a “box” surrounding the Control Measure acronym, located on the Legend located in Appendix G.

3 TYPES OF GESC PERMITS

SEMSWA has determined there are several ways to manage land disturbance and has determined that the following types of permits will be used. To determine what the appropriate GESC Permit for a project is, refer to the GESC Permitting Matrix found on the SEMSWA website, www.SEMSWA.org.

- Standard GESC Permit
- Low Impact GESC Permit
- Single Family Individual Lot GESC Permit
- Annual GESC Permit
- Low Risk GESC Process

A discussion of each permit type and required plans and reports follow.

3.1 STANDARD GESC PERMIT

A Standard GESC Permit is required for land disturbance activities characterized as conventional development and redevelopment that have varied site conditions that need to be addressed with a complete GESC Permit process. These are more standard development and redevelopment projects with greater than an acre of disturbance, or one or more acres of disturbance as a part of a larger common plan of development. Standard projects may have multiple ownerships, or after development by one owner, will contain multiple lots that can be sold to a new owner(s). In addition, if any of the following conditions are within the described threshold below, the Standard GESC permitting process will be required even if the disturbance is less than one acre:

- If site construction activities result in an increase of redeveloped impervious area that requires a permanent post construction control measure.
- If the site construction activities are within 100 feet of a drainageway and causes a disturbance within the floodplain that requires a floodplain engineering analysis or modification, and results in an impact to the floodplain.
- If the construction site activity alters established drainage patterns and requires a drainage analysis.
- If the construction site activity requires an Engineering Process or a substantially large volume staging of material, significant concrete or grouting work, or considerable waste material storage or generation.
- If SEMSWA determines that the land disturbance activity has the potential to adversely impact drainage patterns, resulting in sedimentation of the stormwater system, or is of a sufficient volume to contribute to a water quality violation.

REPORT REQUIREMENTS

Information relating to GESC required at the site shall be included in a separate GESC Report. See the GESC Report Checklist in Appendix E for information required to be included in a Standard GESC Report.

PLAN REQUIREMENTS

The following requirements shall be adhered to when preparing a Standard GESC Permit Plans and Reports. The GESC Plan and Report requirements are explained in this Section. The GESC Checklists located in Appendix E should be filled out and submitted as an attachment to the GESC Report, to ensure that each of the requirements is addressed.

All Standard GESC Permit Plans shall be prepared on 22" by 34" sheets at a scale of 1-inch to 20-feet up to 1-inch to 200-feet, as appropriate, to clearly show sufficient detail for review. The final GESC Plan submitted for stamped approval may be half size. An Approval Block area shall be reserved for the SEMSWA approval stamp (Appendix G).

The Standard GESC Permit Plan and Report shall be signed and stamped by the Design Engineer. Colorado State Statutes require that the GESC Plans and Report be prepared by or under the responsible charge of, and signed and stamped by, a Professional Engineer registered in the State of Colorado. (See Statutory Requirements in §§ 12-25-101, *et seq.*, C.R.S.) For the purposes of this manual, the Professional Engineer is referred to as the Design Engineer.

COVER SHEET

SEMSWA requires that all GESC submittals are stand-alone documents independent of other site civil construction drawings. Therefore, a separate cover sheet is required for the GESC Permit Program documents.

INITIAL GESC CONTROL MEASURES

This plan sheet shall provide grading, erosion, sediment, and waste controls for the initial clearing, grubbing and grading of a project. These initial control measures shall be installed at the outset of construction, prior to the Preconstruction Meeting and after plan approval. This will ensure that the control measures will be installed prior to any other land-disturbing activities. Initial controls are to be placed on existing grades, but shall be based, as appropriate, on proposed grading operations.

INTERIM GESC CONTROL MEASURES

This plan sheet shows control measures to control grading, erosion, sediment and waste during the grading, site construction, and site re-vegetation process. These control measures shall be based on proposed grades and drainage features, are installed after initial site grading, and as soon as practicable. Some interim controls are installed after construction of site infrastructure (e.g. Inlet Protection Control Measure after inlet construction).

FINAL GESC CONTROL MEASURES

This plan sheet shows controls for completion of the site through the final stabilization phase. Control measures shown in the Final Stabilization GESC Plan shall be installed as one of the last steps in the construction process, such as the final seeding and mulching stabilization control measure.

STANDARD NOTES AND DETAILS

A copy of the GESC Plan Standard Notes and Details has been included in Appendix F and shall be provided with each set of the GESC Plan. This is to make sure the Contractor has all the relevant details provided within the site GESC Permit documents.

REQUIREMENTS FOR STAGED AND PHASED GESC PLANS

Areas of land disturbance equal to 40 acres or greater must not be exposed for more than 30 consecutive days without temporary or permanent stabilization. SEMSWA may allow authorized exemptions to the 40-acre limit for

removal and storage of cut material where geotechnical limitations restrict the use of temporary or permanent stabilization of the stored material (e.g. swelling soils, rock). SEMSWA may allow authorized exemptions to the 40-acre limit when the Owner can demonstrate that the 40-acre limit is physically and/or financially impracticable. For sites granted this exemption, a phasing and earthwork quantities plan shall be submitted to SEMSWA and, following adequate review, approved by SEMSWA prior to the commencement of land disturbance activities. Submittal requirements include: (I) **Phasing Plan/Earthwork Quantity Plan** showing cut and fill volumes and locations for each Phase and project totals. (II) Erosion Control Plan showing specific erosion and sediment controls for each phase.

FEES AND COLLATERAL

Permit fees shall be paid in accordance with the current SEMSWA Fee Schedule, located on the SEMSWA website at www.SEMSWA.org, and collateral shall be submitted, based on the control measures required for site control.

3.2

LOW IMPACT GESC PERMIT

Some land-disturbing activities may have only a minor potential impact on adjacent properties and downstream receiving waters. Low Impact permitted sites are less than one acre of disturbance, do not impact the floodplain, and are short in duration with small footprints that can be controlled with typical construction control measures, materials management, and good housekeeping practices. Low Impact GESC Permit projects do not require engineered construction control measures, such as those control measures that require volume sizing. These projects are typically home improvement projects or small additions to commercial slab-on-grade construction activities that may or may not require a separate City Land Use process, and do not alter established drainage patterns.

Projects that fall under a Low Impact GESC Permit designation use an abbreviated GESC Plan process and may or may not require a GESC Report, typically in the form of a simple narrative.

Low Impact sites have a low level of a complexity such that construction control measures can be presented adequately in a simple sketch plan developed with or without the assistance of SEMSWA. SEMSWA provides specific office hours to assist in the preparation of the Low Impact GESC Plan. This provides an excellent opportunity to discuss the project and make sure all requirements are met.

For sites less than one acre within the Cherry Creek Basin with land disturbance not part of a larger common plan of development, Control Regulation 72 requires the Applicant to submit for approval an Erosion and Sediment Control Plan describing approved construction control measures. SEMSWA shall approve the use of a Low Impact Permit as an abbreviated GESC Permit process that meets Control Regulation 72 requirements for sites under one acre.

Low Impact GESC Permit implementation procedures are contained in a Guidance Document found on the SEMSWA website (www.SEMSWA.org) that provides details about the plan preparation, review and approval, and the issuance, inspection and enforcement components of the permit. They are paraphrased below.

REPORT REQUIREMENTS

No GESC Report is required for the Low Impact GESC Permit, but based on the nature of the disturbance, a narrative may be required. This will be determined during Low Impact Permit plan review.

PLAN REQUIREMENTS

Although a detailed GESC Plan need not be prepared for sites where a Low Impact GESC Permit is appropriate, the following abbreviated GESC Plan shall be prepared and submitted to SEMSWA to provide enough information to determine if a Low Impact GESC Permit is acceptable for the proposed work:

A sketch plan showing:

- All surface water hydrologic features that may affect work area.
- Directional flow arrows indicating grades that will determine stormwater runoff flow paths.
- Erosion, sediment, and waste control measures appropriate to the construction activity.
- Attached details for the designated construction control measures.
- Address roadways, north arrow and location map if possible.

FEES AND COLLATERAL

Permit fees shall be paid in accordance with the current SEMSWA Fee Schedule and collateral shall be submitted if determined necessary, based on the control measure(s) required for site control.

SINGLE-FAMILY INDIVIDUAL LOT GESC PERMIT

3.3

The Single-Family Individual Lot GESC Permit applies only to individual lot residential development. Single-family residential projects are required to obtain a GESC Permit even if they have a City Building Permit. These sites have a low level of complexity, with established drainage patterns, such that SEMSWA's Example Individual Lot Plans (Appendix D) can be used. This permit does not require engineered drawings and does not need to be signed and stamped by a Design Engineer. Applicants requesting a permit for *multiple* single-family lots, or choosing to combine several lots into a group, must obtain a Standard GESC Permit (Section 3.1).

In the Cherry Creek Basin, Control Regulation 72 requires the Applicant to control sediment before it leaves the site using a single or multiple entrapment (perimeter) control measure(s). SEMSWA shall approve the use of the Single-Family Individual Lot GESC Permit Example Lot Plans in Appendix D for erosion and sediment control purposes for single lot land disturbance in the Cherry Creek Basin to meet Control Regulation 72.

Note: Projects involving public improvements for a residential development project must follow the requirements of the Standard GESC Permit. Typical residential development requires a Standard GESC Plan and Permit and will not be issued a Single-Family Residential Individual Lot Permit.

REPORT REQUIREMENTS

No GESC Report is required for the Single-Family Individual Lot GESC Permit; however, based on the nature of the disturbance, a narrative may be required. This will be determined during the Single-Family Individual Lot GESC Plan Review process and may require discussion with the Applicant.

PLAN REQUIREMENTS

In Appendix D, SEMSWA provides example details with Single-family Example lot erosion control plan details with typical drainage patterns. If the Applicant's lot conforms to the general layout and drainage patterns of one of these detailed lot plans, a lot-specific GESC plan shall not be required. If the single-family lot does not conform to one of the example types provided, a specific lot GESC Plan shall be developed and submitted for review and approval.

The Single-Family Individual Example Lot Plans, provided in Appendix D, are the minimum requirements by SEMSWA to control sediment transport from individual lots during single-family lot construction. The Example Lot details provided in Appendix D are provided to avoid the need for a plan review and approval process on each individual lot within a residential development. Use of SEMSWA's Example details of control measures for the permitted activity, however, is required. If alternate methods are going to be used on a residential lot, a specific lot GESC Plan depicting the control measures for that site may be submitted and reviewed on a case-by-case basis.

FEES AND COLLATERAL

Permit fees shall be paid in accordance with the current SEMSWA Fee Schedule and collateral shall be submitted if determined necessary, based on the control measure(s) required for site control.

ANNUAL GESC PERMIT

Land disturbance activities for similar, repetitive, and/or periodic maintenance operations, and dry utility installation projects, are characterized as Annual and are generally short term, frequent in occurrence, use the same or substantially similar design and construction processes, have the same type of waste discharge to manage, and require the same operational construction control measures.

These projects typically are done by public or quasi-public agencies or entities that perform the work with in-house staff or use experienced "short listed" or "on-call" contractors experienced with the requirements of maintenance and installation of public facilities. Projects that fall under an Annual Permit designation use an abbreviated GESC Plan process using SEMSWA-provided Fact Sheets and typical details of control measures installed for the anticipated activities.

For sites under an acre within the Cherry Creek Basin with land disturbance, Control Regulation 72 requires the Applicant to submit for approval of an Erosion and Sediment Control Plan describing approved construction control measures. SEMSWA shall approve the use of the abbreviated Annual GESC Permit Program documents for an Annual GESC Permit as meeting Control Regulation 72 requirements for sites under one acre with land disturbing activities.

The Annual Permit implementation procedures are contained in an Annual Permit Guidance Document on the SEMSWA website (www.SEMSWA.org) that provides details about the Fact Sheet, Permit Special Considerations, and typical details, permit issuance, and inspection and enforcement components of the Annual Permit. They are paraphrased below.

REPORT REQUIREMENTS

No GESC Report is required for an Annual Permit; however, based on the nature of the disturbance, a narrative may be required. This will be determined during discussion with SEMSWA when the Applicant requests an Annual Permit for their construction and/or installation activities.

PLAN REQUIREMENTS

An Annual GESC Permit does not require a GESC Plan to be prepared or stamped by a Professional Engineer.

However, the use of SEMSWA's typical details of control measures for the permitted activity is required. A typical detail has been prepared to assist the Contractor or Applicant with the proper implementation of the appropriate control measure installation. If a standard detail does not exist for the proposed work a specific plan may be required as determined by SEMSWA.

FEES AND COLLATERAL

Permit fees shall be paid in accordance with the current SEMSWA Fee Schedule. No collateral for an Annual Permit is required.

LOW RISK GESC PROCESS

3.5

Some land disturbing activities less than one acre are not expected to contribute sediment to the stormwater system. These projects have a very low potential of causing a water quality impact and/or a violation of a water quality standard and are identified as “Low Risk.” SEMSWA does not issue a Low Risk permit for construction activities that have the potential to adversely impact drainage patterns or result in sedimentation of the stormwater system.

Low Risk construction activities are generally residential in nature, and typical of construction activities a homeowner or handyman service would undertake. Some smaller commercial construction incidental activities may also be considered Low Risk, such as re-skinning a building. The land disturbance is small, and significantly less than one acre; not part of a larger common plan of development; located outside of the floodplain; and would not require any other SEMSWA permit. The activity is typically a one-time project, short in duration, condensed to one activity, and would not have the potential to affect established drainage patterns.

SEMSWA has determined that Low Risk sites can be managed without a formal permit if there is adherence to control measure(s) specified for the activity in SEMSWA-provided Fact Sheets. Failure to comply with the control measures established for the Low Risk activity could result in SEMSWA requiring a GESC Permit to be obtained.

For these types of sites within the Cherry Creek Basin, the SEMSWA Fact Sheet will suffice as an erosion and sediment control plan, describing approved and appropriate construction control measures for the type of Low Risk activity. SEMSWA shall approve the use of the Low Risk Fact Sheet documents as meeting Control Regulation 72 requirements for these condensed sites or projects under one acre with only minor land disturbing activities.

4 GESC PERMIT POLICIES

4

SIGNED GESC PLAN AND REPORT

4.1

The GESC Permit documents will be considered accepted when a completed application and submitted copies of the GESC Plan and Report is approved. Applicants will be notified by SEMSWA when the GESC documents have been signed and are ready to be picked up.

SEMSWA will retain two sets of the signed GESC Plan/Report. The GESC Permit documents are considered valid for two years following the signature date.

GESC PERMIT EXPIRATION

4.2

A GESC Permit is valid for two years from the date the permit is issued. A GESC Permit must stay valid throughout the duration of a project, through final stabilization, and until close-out. Prior to permit expiration, the Permittee shall contact SEMSWA at least thirty (30) days in advance to start the renewal process. Failure to renew the GESC Permit prior to its expiration may result in enforcement, as all sites need to be permitted until the site has met final stabilization requirements and closed out. Renewal fees for the GESC permit shall be in accordance with the current SEMSWA Fee Schedule. All required collateral as appropriate is required to be in place for an active GESC Permit.

GESC PERMITS WITH PROPERTY OR PROJECT OWNERSHIP TRANSFERS

Multi-lot development typically involves the transfer of ownership of portions of the property or project during the life of the project, and they include common areas, which may serve or be impacted by multiple owners. It is important that control measures be in place to ensure that the GESC requirements are maintained on all portions of the original development throughout the life of the project. New Owners or the new Owner's Agent are responsible for obtaining a permit for any disturbed areas and should reference the GESC Permitting Matrix on SEMSWA's website to determine Permit and Plans required. The SEMSWA Fee Schedule lists permitting fees associated with property or project transfers for a GESC Permit.

When a discrete portion of a development project is sold to a new Owner, the new Owner shall be required to obtain a GESC Permit for that portion of the property or project. A GESC Plan and Report for the property or project may exist and may provide the necessary control measure requirements. The new Owner may be required to provide new collateral in accordance with the GESC Permit requirements. This includes the situation when a GESC Permit is transferred from a Developer to a Homebuilder. The Developer must ensure the common areas are still permitted since they serve the entire site. These include the streets and rights-of-way, the common open space areas, drainage tracts and easements, stormwater detention and water quality facilities, and other areas that are not associated with the individual lots that are now in new ownership.

The original GESC Permit documents for the development may be adjusted throughout the life of the subdivision build-out to reflect only those improvements that are necessary. The cost estimate and collateral may be reduced, upon approval, accordingly throughout the project at the request of the Permittee.

The Permittee is responsible for all GESC requirements including subcontractors, utility providers and trades. The Permittee may be required to revise GESC documents to reflect any new or revised permitted area(s) and must notify SEMSWA of the updated plan/ownership/construction limits.

If a different Contractor replaces the Contractor that is identified on the GESC Permit, the GESC Permit shall be transferred to the new Contractor. The transfer shall require a new GESC Permit, payment of a transfer/permit fee, and new collateral. Failure to transfer the GESC Permit to the new responsible Contractor or Permittee may result in enforcement.

RESPONSIBILITIES FOR SINGLE-FAMILY RESIDENTIAL PROJECTS

When individual lots are sold from a Permittee to a homeowner, the Permittee is responsible for notifying the new Owner of the single-family individual lot of the need to maintain the temporary erosion and sediment control measures on the site until the lot is final landscaped or re-vegetated in accordance with SEMSWA's GESC requirements.

If the Permittee is not the one responsible for landscaping any portion of the lot, then once the property is transferred to a homeowner, the homeowner shall be responsible for the erosion and sediment control of the property. The Builder is responsible for ensuring temporary erosion control measures are designed to function for a minimum of 90 days after the transfer of ownership to the homeowner. SEMSWA requires through its regulations that homeowners prevent the erosion and transport of sediment from their property. Homeowners are required to provide permanent stabilization of their lot, through such measures as sod, established seeded vegetation, rock, landscaping or other permanent measures of stabilization per the City Land Development Code. Homeowners are

required to maintain temporary erosion control measures on their property, until permanent measures are installed and functioning.

GESC PERMITTEE SELLS A PORTION OF THE LAND/PROJECT AREA TO A BUILDER

4.5

When a Permittee sells a portion of their land/project area, the Permittee must remove that area from their GESC plan and notify SEMSWA of the updated plan, ownership, and construction limits. When individual lots are sold off to multiple owners, the lot owners will be required to obtain separate GESC permits for their lots and provide the required collateral to guarantee compliance with the GESC requirements. A separate GESC Plan may be required for these lots.

REVIEW FEES

4.6

Review fees are submitted with the initial GESC Permit submittal package. Review fees for a GESC Plan and Report are specified in the current SEMSWA Fee Schedule and based on area of land disturbance.

CONSISTENCY WITH OTHER PLANS

4.7

The GESC Plan shall be consistent with approved plans such as drainage reports and construction drawings. The GESC Plan shall be submitted along with other related SEMSWA and City plans and permit applications. The Applicant may be required to obtain other permits as part of the project to facilitate development, including right-of-way access, construction of public improvement(s), and activities in the floodplain. These other related plans and permits may not reflect all requirements for development in the City. The Applicant should verify plans and permits required from the City specific to their development.

EARLY GRADING PERMIT REQUIREMENTS

4.8

To obtain the approval to perform early grading on a site before having approved Construction Documents, the project must have received favorable recommendation from the City Planning Commission or if the project is not heard by the Planning Commission, approval by the City Council. In the event the plan is not required to go to either the Planning Commission or the City Council and will be administratively approved, the City Planning Director must approve early grading. The GESC Report and Plan must be complete and approvable, the applicant must provide a Hold Harmless Letter, pay permit fees, and provide for collateral to be allowed early grading approval (see Appendix B for an example). At the appropriate time, the GESC Permit for the site will be issued.

PERMIT FEES

4.9

Permit Fees are to be paid prior to the GESC Permit issuance. Permit fees are identified in the current SEMSWA Fee Schedule, available through SEMSWA's website, www.SEMSWA.org.

ENGINEERING COST ESTIMATE

4.10

Applicants are required to provide an engineer's cost estimate (ECE) associated with implementing the GESC control measures. An example of the ECE is provided in Appendix C and provides unit cost information that shall be used to generate the cost estimate. The ECE will quantify the collateral that will secure appropriate GESC control measures.

The collateral to secure GESC control measures will be held by SEMSWA until the Final Close-Out Acceptance. There may be a reduction in collateral between the Initial Close-Out and Final Close-Out upon request and approval.

SEMSWA may waive/reduce the ECE-based collateral amount for governmental entities constructing public projects.

For projects that will be phased, the ECE must be separated and sub-totaled for each phase of the project on the ECE calculation spreadsheet.

4.11

COLLATERAL POSTING

Collateral may be retained, based on the control measures required for site control, and for site final stabilization.

SEMSWA requires collateral, as follows:

Permit	Collateral Required
Standard	Yes
Low Impact	Case-by-case basis*
Annual	No
Single Family	Case-by case basis*
Government Partner Agencies**	Yes, 10% of ECE or other agreed upon amount.

*Low Impact projects may require collateral depending on size, scope, and control measures required.

** SEMSWA may allow reduced collateral from governmental entities based on an executed written agreement addressing GESC requirements, control measure implementation and final stabilization.

The conditions under which the GESC collateral is held by SEMSWA is separate from any other security relating to the project site's Subdivision Improvements Agreement (SIA), Public Improvement Agreement (PIA), or any other agreements or permits relating to the site. GESC collateral will be retained and released separately per the *GESC Manual* requirements.

AMOUNT OF COLLATERAL

The amount of collateral for a GESC Permit is based on cost estimates for installing and maintaining the GESC control measures required during construction, and for the site's final stabilization. A copy of the worksheets to be used for preparing the ECE for erosion and sediment control measures during construction, and for the site's final stabilization, is included in Appendix C.

FORMS OF COLLATERAL

SEMSWA accepts two forms of financial collateral:

- Irrevocable Letter of Credit from a Colorado financial institution in a form acceptable to SEMSWA. The Letter of Credit template is available on the website, www.SEMSWA.org.
- Cash Escrow. An example of a cash escrow agreement is available upon request.

The conditions of each form of collateral shall allow the collateral to be held by SEMSWA for a minimum of three (3) years. The three-year period should allow for completion of all GESC and other Agreement requirements, including two growing seasons to allow time for re-vegetation to reach the required coverage for Final Stabilization and GESC Permit close-out.

EXPIRATION OF COLLATERAL

If the construction of the project and/or stabilization process takes longer than three (3) years, the Permittee may extend the posted Letter of Credit for one (1) year a minimum of thirty (30) days prior to the expiration date. This extension must be requested by the Permittee. Failure to extend the collateral, prior to the thirty (30) day deadline on an active site, may result in enforcement and/or SEMSWA drawing upon the collateral to ensure permit conditions are met. An additional fee charged by the Permittee's financial institution may apply to extend the letter of credit.

The Permittee shall maintain the collateral amount required for the GESC control measures in full force and effect until Final Close-out approval of the GESC Permit, unless otherwise approved by SEMSWA.

RELEASE AND REDUCTION OF COLLATERAL

It is recognized by SEMSWA, that during the interim period between Initial Close-Out and Final Close-Out, conditions of the site may warrant alterations to the required final stabilization control measures. If the final stabilization control measures collateral amount is less than the interim measures, the Permittee may request a reduction in collateral consistent with the reduced control measure amount as outlined in the ECE.

Once Final Close-out Acceptance for the site has been granted, the Final Close-Out form will be approved by SEMSWA and collateral for the project will be released.

At any time, the Permittee may request a reduction in GESC collateral. The decision to reduce collateral is at the discretion of SEMSWA.

VARIANCES TO THE GESC MANUAL

4.12

No variance to the GESC Permit Program requirements as contained in the *GESC Manual* will be considered that would result in a non-compliance with SEMSWA's MS4 Permit. Outlined below is the process of submitting a variance request and appealing a denied request for a variance from these standards.

VARIANCE CRITERIA

A variance shall be granted only upon the finding that the requested variance from the requirements of the GESC Permit Program will not impair the public health, safety, and welfare of the residents of the City and that the intent and purposes of the GESC Permit Program have been met. In ruling upon a variance, SEMSWA shall also consider the impacts the proposed alternative criteria would have on construction and maintenance requirements and cost.

VARIANCE AND APPEAL PROCEDURES

Step 1. Applicant submits a written request for a variance from the GESC Permit Program to SEMSWA with the variance request form found on the website at www.SESMWA.org. At a minimum, the variance request must include the following information:

1. Identification of the criteria sought to be waived or varied;
2. Identification and detailed description of the alternative to the GESC Permit Program criteria; and
3. Justification of the variance request.

Step 2. SEMSWA is responsible for reviewing the variance request and deciding approval or denial. If the requested variance impacts other SEMSWA Program areas, the request shall be referred to the Technical Review Committee

(TRC), consisting of SEMSWA Technical management staff. TRC reviews the request and recommends either approval or denial. Upon the determination of a variance request, SEMSWA will notify the Applicant of the determination.

Step 3. If the variance request is denied, the Applicant may appeal the decision by submitting a written appeal to the Executive Director.

Step 4. Within six (6) working days of receiving the appeal request, SEMSWA shall respond to the Applicant by setting a date, time and location for a meeting to allow the Applicant to present their appeal. The meeting date shall occur within twelve (12) working days from the date SEMSWA received the appeal.

Step 5. Within three (3) working days of the appeal meeting, SEMSWA shall render a written decision either approving or denying the variance request. SEMSWA's decision shall be provided to the Applicant within five (5) working days from the date of the appeal meeting.

Step 6. If the Executive Director upholds the denial of the variance request, the Applicant may appeal the decision to the SEMSWA Board. To do so, the Applicant shall submit to the Director a written request to appeal. Within six (6) working days of receiving the request for an appeal, the Director shall notify the Applicant of the date, time and location of the public hearing at which the SEMSWA Board will consider the variance.

Step 7. The public hearing provides the Applicant and SEMSWA staff an opportunity to present information relative to the variance request. The SEMSWA Board will evaluate the variance application and all presented information at the hearing and shall approve, conditionally approve or deny the variance. The SEMSWA Board shall base its decision on the information presented in consideration of the applicable GESC Permit Program requirements.

BURDEN OF PROOF

In all stages of appeal, the Applicant bears the burden of proof to establish that a variance from the GESC Permit Program is justified.

5 GESC PERMIT CLOSE-OUT

5.1 INITIAL CLOSE-OUT

Initial Close-Out may be requested when all disturbed areas are stabilized in accordance with SEMSWA criteria. The Permittee will request an Initial Close-out inspection from the SEMSWA Inspector.

Prior to the Initial Close-Out Inspection, the following must be completed:

- Clean all streets, sidewalks and flowlines of sediment with a street sweeper. **WASHING OF STREETS, SIDEWALKS AND FLOWLINES IS IN DIRECT VIOLATION OF SEMSWA CRITERIA.**
- Clean all inlets, trickle channels and all other drainage features.
- Remove construction erosion and sediment controls (per the approved GESC Plan) and install/maintain final stabilization erosion and sediment control measures per the SEMSWA-approved GESC Plan.

Once all items are completed, the Permittee shall call SEMSWA and schedule an Initial Close-Out Acceptance Inspection. In addition to the SEMSWA Inspector, a representative of the Permittee shall attend the Initial Close-Out Inspection.

The Permittee shall complete the Close-Out Form located on SEMSWA's website, www.SEMSWA.org. Any corrections noted during the inspection shall be made to the site as requested by the SEMSWA Inspector, and when completed, a re-inspection can be scheduled with SEMSWA.

Once the Close-Out Form has been provided to SEMSWA, and the acceptance inspection is approved, SEMSWA shall grant Initial Close-Out.

REQUIRED INSPECTIONS AND MAINTENANCE AFTER INITIAL CLOSE-OUT

5.2

The Permittee shall undertake the following inspections and maintenance operations after Initial Close-Out:

- Seeded and mulched areas shall be inspected as necessary to ensure growth of vegetation by the Permittee for a period of two (2) growing seasons (Spring and Fall); following initial seeding, noxious weeds shall be controlled.
- Reseeding and mulching shall be undertaken as necessary after the two (2) growing seasons for any areas failing to meet the required coverage, or as requested by the SEMSWA Inspector.
- Final stabilization control measures shall remain in good working order at all times. Failure to do so may result in enforcement.
- SEMSWA may approve alternative final stabilization criteria for specific operations or field conditions.

FINAL VEGETATION ACCEPTANCE

5.3

The SEMSWA Inspector will confirm on the Close-Out Form that vegetation has met the required coverage of 70% of the pre-construction condition, and that noxious weeds have been controlled. When the required coverage has been met, the SEMSWA Inspector will issue acceptance of the vegetation and give the Permittee instructions to remove remaining final stabilization control measures.

If the required vegetation coverage is not met, repairs or corrections shall be made by the Permittee and a follow-up Vegetation Acceptance Inspection can be scheduled once the vegetation meets the required coverage.

REMOVAL OF FINAL STABILIZATION CONTROL MEASURES

5.4

After obtaining written acceptance of the vegetation coverage from SEMSWA, the remaining final stabilization control measures shall be removed and properly disposed. The site shall be cleaned up and any areas disturbed as a result of control measure removal shall be seeded and mulched, or otherwise final stabilized.

FINAL CLOSE-OUT INSPECTION

5.5

Prior to Final Close-Out inspection the following must be done:

- Clean all streets, sidewalks and flowlines of sediment with a street sweeper. **WASHING OF STREETS, SIDEWALKS AND FLOWLINES IS IN DIRECT VIOLATION OF SEMSWA CRITERIA.**
- Clean all inlets, trickle channels and all other drainage features.
- Remove all controls at the site.
- Maintain all stormwater infrastructure to ensure proper functionality of the stormwater system.

The Final Close-out Inspection shall then be scheduled between SEMSWA and the Permittee. The SEMSWA Inspector will check the removal of control measures, confirm that the final stabilization vegetation has been maintained as appropriate, and either accept the site as final, or stipulate the corrections that must be made. In the rare instance

when corrections are substantial, the SEMSWA Inspector may require that follow-up inspections be scheduled with SEMSWA until the site is final stabilized.

6 ENFORCEMENT

Failure to comply with any term, condition, limit, deadline or other provision of the GESC Permit Program, the GESC Permit, or failure to obtain a GESC Permit or keep an active GESC Permit or Plan/Report, shall constitute a violation of the SEMSWA GESC Regulation. Discharge of any pollutant offsite, including sediment, is a violation and subject to enforcement.

Per SEMSWA's Enforcement Resolution(s), as amended, in addition to any other legal or equitable remedies that SEMSWA may have for GESC violations, SEMSWA may at its discretion use any of, but not limited to, the following enforcement: withhold issuance or extensions of permits; issue re-inspection fees and/or compliance assurance enforcement fees; issue Stop Work Order; issue Notice of Violation; revoke permit; initiate Compensatory Action; conduct Abatement; withhold inspections; or refuse to issue any other necessary approvals until such violation has been corrected and the Permittee has taken the necessary action to ensure compliance with the GESC Permit and GESC Permit Program requirements.

NONCOMPLIANCE

In the event the Permittee is not meeting the requirements of the GESC Permit Program, GESC Plan/Report, and/or GESC Standard Notes and Details, and is therefore in noncompliance, remedies will be available to SEMSWA in accordance with the remedies contained herein, other legal or equitable remedies, and/or any SEMSWA Resolution(s) or Policies containing provisions for providing remedies for enforcement against defaults or violations. The following list identifies actions that constitute noncompliance; however, noncompliance actions are not limited to the list below. SEMSWA's Enforcement Response Plan, found on SEMSWA's website at www.SEMSWA.org, explains what constitutes noncompliance and the tools used to enforce on violations and details the escalation procedures for sites requiring enforcement.

- Failure to obtain a GESC Permit or starting work before a GESC Permit is issued.
- Permittee fails to construct the improvements in substantial compliance with the GESC Plan and the other requirements of the GESC Permit;
- Permittee fails to repair, replace, and/or maintain a control measure that causes a discharge of pollutants offsite when a verbal request has been made to immediately correct the deficiency;
- Permittee fails to correct any noncompliance specified on an Inspection Form or in any written notice of noncompliance within the time frame specified;
- Permittee otherwise breaches or fails to comply with any obligation of the GESC Permit and/or GESC Permit Program;
- Permittee become insolvent, files a voluntary petition of bankruptcy, is adjudicated as bankrupt pursuant to an involuntary petition in bankruptcy, or a receiver is appointed for the Permittee;
- Permittee fails to maintain in full force and effect a Letter of Credit to secure collateral in the amounts specified above or in the GESC Permit. Notice of defaults as to any phase of GESC must be given prior to expiration of the warranty period for such phase of the SIA, PIA or other agreement, as hereinafter provided.
- Permittee fails to submit a cut sheet of any alternative erosion or sediment control measure installed onsite in the time frame specified.

Additional noncompliance actions may be determined at the Executive Director's discretion based on an assessment of the action in relation to a violation of the *GESC Manual*, GESC Permit, and/or GESC Permit Program.

SEMSWA RIGHT TO COMPLETE GESC CONTROL MEASURES

6.2

SEMSWA shall have the right to complete the GESC control measures to correct any GESC Permit default, either itself or by contract with a third party or by assignment of its rights to a successor who has acquired the subdivision/project by purchase, foreclosure, or otherwise.

SEMSWA shall be entitled to: (a) make a draw on the Letter of Credit or cash collateral for the amount reasonably determined by SEMSWA to be necessary to correct the default in a manner consistent with the approved GESC Plan up to the face amount of the Letter of Credit or cash collateral; and (b) sue the Permittee for recovery of any amount necessary to correct the default over and above the amount available under the Letter of Credit.

USE OF FUNDS BY SEMSWA

6.3

Any funds in the possession of SEMSWA or obtained by SEMSWA may be used to pay the costs of site control and/or stabilization and to pay the reasonable costs and expenses of SEMSWA in connection with the GESC Permit default by Permittee(s), including reasonable attorneys' fees.

7 FIELD POLICIES

7

RESPONSIBILITIES OF THE GESC MANAGER

7.1

As the Permittee's focus shifts from preparing the GESC Plan and Report and applying for the GESC Permit, to constructing the project, the first task is to select a site GESC Manager. The GESC Manager is the Permittee contact person with SEMSWA for all matters pertaining to the GESC Plan and Permit and shall respond to requests made by SEMSWA staff and have any deficiencies in the work corrected. The GESC Manager may be an employee of the Owner or Contractor and shall have the authority to act on behalf of the Permittee, including committing funds, to ensure that the site remains in compliance with the GESC Permit. In all matters, the Permittee shall remain the legally responsible party.

An Alternate GESC Manager who can serve in the same capacity as the GESC Manager shall also be selected. The GESC Manager shall inform the Alternate GESC Manager of any absences, provide the Alternate the status of the GESC Plan implementation, and ensure that the Alternate GESC Manager assumes the GESC Manager's responsibilities during any absence. The GESC Manager and Alternate GESC Manager shall be named at the onsite Preconstruction Meeting.

AVAILABILITY OF THE GESC MANAGER

7.2

The GESC Manager shall be on site as necessary to ensure the GESC requirements are being implemented and shall provide SEMSWA with a contact number. The contact number will ensure that the GESC Manager can be contacted and provide adequate communication about the site. In the event the GESC Manager (or Alternate GESC Manager) cannot be reached within 24 hours, and a GESC issue is urgent, a violation may be assessed.

7.3

CHANGING THE GESC MANAGER OR ALTERNATE

Notification shall be provided to SEMSWA if the GESC Manager or Alternate change. A field meeting with the SEMSWA Inspector and new GESC Manager or Alternate should be scheduled prior to the next scheduled inspection to discuss site conditions and responsibilities of the GESC Manager.

7.4 DOCUMENTS THAT SHALL REMAIN ON SITE

A copy of the Approved GESC Plan/Report, GESC Plan - Standard Notes and Details, and GESC Permit shall be made available at the SEMSWA Inspector's request.

7.5 PRECONSTRUCTION MEETING

An onsite Preconstruction Meeting is required prior to GESC Permit issuance. This is the opportunity for the SEMSWA Inspector to verify that initial sediment, erosion, and waste control measures are in place and the site is ready for construction activity and the GESC Permit application can be approved and the Permit issued. In addition to the SEMSWA Inspector and the GESC Manager, the following representatives should attend:

- **General Contractor.**
- **Owner or Owner's Representative** (the General Contractor may **NOT** be the owner's representative).
- **Alternate GESC Manager** (may be the same as the Owner or General Contractor Representative).
- **Grading Sub-Contractor**, if different than the General Contractor.

If the SEMSWA Inspector determines that significant modifications or corrections to the initial GESC control measures are necessary, the SEMSWA Inspector will inform the GESC Manager that such corrections shall be made, and that a follow-up inspection shall be scheduled with SEMSWA. At no time can construction activities be initiated until appropriate control measures are in place. Acceptance of the corrected control measures by the SEMSWA Inspector shall take place prior to the issuance of the GESC Permit.

The Permittee shall not start site grading activities prior to the GESC Permit being issued or the issuance of the Hold Harmless letter in the case of early grading activities.

7.6 TOPSOIL PRESERVATION

Topsoil stripping and stockpiling of disturbed area soils is a critical component in establishing the required vegetative coverage for final stabilization. Re-spreading of the former in-situ topsoil in areas to be vegetated shall be a mandatory practice and specified in all GESC Plans.

7.7 STABILIZATION

All areas disturbed by construction, and soil stockpiles, shall be stabilized as soon as possible to reduce the duration of soil exposure to runoff events and the potential for erosion. All disturbed areas which are either final graded or will remain inactive for a period of more than thirty (30) days, shall be required to be stabilized within fourteen (14) days of the completion of the grading activities. Reworking the disturbed area within the thirty (30) days for the sole purpose of avoiding the requirement to stabilize the exposed area shall not be considered an acceptable practice. Acceptable stabilization control measures are as follows.

- Surface roughening **and** Mulching,
- Seeding and Mulching (acceptable if area will remain dormant for more than six (6) months; temporary seed mix is acceptable), or
- Erosion Control Blanket.

For temporary stabilization (i.e. areas that will be reworked), SEMSWA requires one of the above. All stabilization measures must be maintained.

As soon as possible after construction in drainageways, or after removal of a temporary stream crossing, all disturbed areas shall be top-soiled, seeded and mulched, and, unless otherwise approved, protected with Erosion Control Blanket.

INSTALLATION OF INTERIM AND FINAL CONTROL MEASURES

7.8

It is the responsibility of the GESC Manager to ensure that Interim control measures and subsequent Final control measures are installed at the earliest opportunity. Some control measures have specific time requirements for installation that are identified on the GESC Plan - Standard Notes and Details; these time requirements shall be adhered to.

For control measures where a specific time frame is not given, the controls shall be installed as soon as construction of the infrastructure is substantially complete or when grading activities have produced grades close to the final grade. In these cases, it is up to the discretion of the SEMSWA Inspector to make the final determination of Interim and Final control measure installation time frames.

8 REQUIRED GESC INSPECTIONS

8

GESC INSPECTIONS CONDUCTED BY PERMITTEE

8.1

During the construction phase, erosion, sediment, and waste controls must be inspected regularly by the site GESC Manager to ensure that the control measures are adequately installed, maintained and functioning as intended. Sites with a State Stormwater Permit must have a self-documented inspection conducted of site control measures to ensure installation and maintenance is per the site's GESC Plan-Standard Notes and Details once per calendar week. For control measures not included in SEMSWA's Standard Notes and Details, the GESC Manager must inspect per the manufacturer's recommendations for installation, inspection, and maintenance frequency. Sites that are inactive with no construction activity on site must have a documented inspection conducted monthly by the site GESC Manager.

For areas within the Cherry Creek Basin, the GESC Manager must inspect BMPs at the following times and intervals at a minimum:

- After installation of any Construction BMP;
- After any runoff event; and
- At least every 14 days.

For sites where construction activities are completed but final stabilization has not been achieved due to a vegetative cover that has been planted but has not become established, the Permittee may reduce the inspection frequency to once per month.

The GESC Manager shall provide Inspection Reports to the SEMSWA Inspector upon request.

GESC INSPECTIONS CONDUCTED BY SEMSWA

8.2

During the construction and final stabilization phase, erosion, sediment and waste controls will be inspected regularly by a SEMSWA Inspector. SEMSWA Inspectors will consider the overall effectiveness of the controls and will generally check for proper installation and maintenance of the controls. It remains the responsibility of the Permittee/GESC Manager to ensure that the site remains in compliance with all GESC requirements.

9 SITE GRADING DESIGN GUIDANCE AND CRITERIA

This section provides design guidance and criteria for developing a proposed grading plan for a site. Although the existing topography and planned uses of development sites and individual lots are unique, several principles apply when designing permanent land surface grading.

SLOPES

The topography of a site may be steep existing slopes that are to be preserved or cut or fill slopes created during the grading process. In either case, the measures in this section shall be taken to protect slopes from erosion.

On steep or sloping sites, or flat sites where more variation in grade is desired, the proposed grading plan may incorporate graded slopes and/or retaining walls. Preferred slopes are 4:1 or flatter, designed with variation and shaping as appropriate, possibly utilizing a Landscape Architect. Slopes between 3:1 and 4:1 are problematic; these slopes require stabilization with Erosion Control Blanket. Slopes steeper than 3:1 are highly discouraged, will require additional permanent measures to withstand erosion, and may require a variance (Section 4.12).

STOCKPILES

During design, earthwork balance and timing of construction will determine the necessity of stockpiling. If stockpiling is anticipated, it must be noted on the GESC Plan.

Stockpiling of material on construction sites or undeveloped lots shall be allowed only as a temporary condition and must be within approved construction limits. Stockpile types and locations may be reviewed and approved by the SEMSWA Inspector. The following criteria apply to all stockpiles:

- Side slopes of stockpiles not being actively worked must be flatter than 3:1. Appropriate control measures to control erosion of the slopes must be used.
- Soils that will be stockpiled for an extended period must be stabilized. If soil is to be stockpiled for more than 30-days and not actively worked, it shall be seeded and mulched within 14-days of stockpiling. If material is removed from the stockpile periodically throughout the life of the stockpile, appropriate control measures must be provided to address the disturbance caused by the removal operations.

10 GENERAL CONSTRUCTION PRACTICES

The Permittee and Contractor working in the City have the responsibility to review, understand, and comply with the GESC Plan Standard Notes and Details. Several of SEMSWA's requirements pertaining to general construction practices are highlighted in the following sections. Noncompliance with these construction practices is not acceptable, will be a violation of the GESC Permit, and can be enforced upon by the SEMSWA Inspector.

LIMITS OF CONSTRUCTION

No work, storage of equipment, or stockpiling, shall be allowed outside of the approved Limits of Construction. The Limits of Construction must be complied with and are enforceable by the SEMSWA Inspector.

STREET CLEANING

10.2

Throughout the life of a project, streets used for egress shall be kept clean and free of sediment that can be tracked. In the event of accidental tracking of mud or dirt on streets, the mud and/or dirt shall be cleaned immediately using a vacuum-type street sweeper, a brush-type street sweeper with dust control, or manually using shovels and brooms.

Any damage to the street from mechanical methods of street cleaning shall be repaired at the Permittee expense.

Streets can only be cleaned with water if all wash water is captured and prevented from entering the storm sewer system.

Tracking of sediment from a construction site is not acceptable, is a violation of the GESC Permit, and can be enforced by the SEMSWA Inspector.

DUST CONTROL

10.3

The GESC Manager shall be responsible for dust control on the site. Disturbed areas not yet ready to be seeded, landscaped, paved, or otherwise stabilized, shall be watered, sprayed with a tackifier, mulched (without seed) or ripped as necessary to preclude visible dust emissions.

Dust that leaves the site in any amount that can be considered a safety issue is not acceptable, is a violation of the GESC Permit, and can be enforced upon.

CONSTRUCTION SITE WASTE CONTROL

10.4

Many potential pollutants other than sediment are associated with construction site activities. These pollutants include, but are not limited to, pesticides; fertilizers used for vegetative stabilization; petrochemicals; construction chemicals such as concrete products, sealers, and paints; wash water associated with these products; trash; paper; wood; garbage; detergents and solvents; and sanitary wastes. These wastes are described in Section 10.5.

Responsible handling and adequate disposal facilities shall be utilized for solid waste, including excess asphalt, concrete, wood, rebar and other construction wastes produced during construction.

Washing of equipment and machinery shall not be allowed on site, is a violation of the GESC Permit, and can be enforced upon.

Appropriately store, cover, and/or isolate all onsite potential construction-associated waste pollutants to prevent runoff of pollutants and contamination of ground water. The GESC Manager is responsible for both the management and cleanup of potential construction waste. Outdoor storage of bulk liquids is required to have secondary containment or equivalent protective measures in place. Outdoor storage or any of the above items shall not be stored within the floodplain, is a violation of the GESC Permit, and can be enforced upon.

POTENTIAL POLLUTANTS AT A CONSTRUCTION SITE

10.5

Pollutant sources onsite must be identified and controlled using structural and/or non-structural controls to the Maximum Extent Practicable (MEP) as determined by SEMSWA. Detailed descriptions of structural control measures for pollution control are given in Section 11. Though not an exhaustive list, the following are examples of common pollutant sources found on construction sites. Failure to control any of these pollutant sources, or other potential pollutants is unacceptable, is a violation of the GESC Permit, and can be enforced by the SEMSWA Inspector.

PESTICIDES

Insecticides, fungicides, rodenticides, and herbicides are used on construction sites to reduce maintenance and fire hazards associated with weeds and woody plants. Rodenticides are also used to control rodents attracted to construction sites. Common insecticides employed include synthetic, relatively water-insoluble chlorinated hydrocarbons, organophosphates, carbamates, and pyrethrins.

PETROLEUM PRODUCTS

Petroleum products used during construction activities include fuels and lubricants for vehicles, for power tools, and for general equipment maintenance. Specific petroleum pollutants include gasoline, diesel oil, kerosene, lubricating oils, and grease. Asphalt paving also can be particularly harmful since it releases various oils for a considerable time after application. Additionally, many of these pollutants adhere to soil particles that can leave the site in runoff and pollute receiving waters.

NUTRIENTS

Fertilizers are used on construction sites when re-vegetating graded disturbed areas. Fertilizers contain nitrogen and phosphorus, which in large doses can adversely affect surface waters, causing eutrophication.

SOLID WASTES

Solid wastes on construction sites are generated from trees and shrubs removed during land clearing and structure installation. Other wastes include wood and paper from packaging and building materials, scrap metals, sanitary wastes, rubber, plastic and glass, and masonry and asphalt products. Common trash, including food containers, cigarette packages, leftover food, and aluminum foil also contribute to solid wastes at the construction site.

CONSTRUCTION CHEMICALS

Chemical pollutants, such as paints, acids for cleaning masonry surfaces, cleaning solvents, asphalt products, soil additives used for stabilization, sanitary wastes, and concrete curing compounds, may also be used on construction sites and carried in runoff.

SEDIMENT

Sediments are soils or other surficial materials transported or deposited by the action of wind, water, ice, or gravity, and often as a product of erosion. Sediments from construction sites can erode from land disturbed by the construction activities during a rainfall event.

EQUIPMENT MAINTENANCE

10.6

Equipment maintenance is to be conducted in the designated location within the Limits of Construction. Maintenance should not be conducted within 50 feet of a conveyance swale, drainageway, and/or storm sewer inlets.

SPILLS AND LEAKS

10.7

Spills and leaks onsite must be cleaned up using dry methods whenever possible. If water or other liquid methods are used, the wash water must be collected and disposed of properly. Spilled substances and any associated cleaning residue must be prevented from reaching receiving waters and/or entering the storm sewer system.

Effective spill control is required to be implemented on construction sites. Onsite personnel must be trained on both spill prevention and spill response measures.

11 DESIGN, INSTALLATION, AND MAINTENANCE OF CONTROL MEASURES

11

This section identifies several temporary control measures accepted for use in the City to control erosion and sediment runoff from construction sites. This section of the *GESC Manual* provides the design parameters to be specified for each control measure on the GESC Plan and the accompanying GESC Plan – Standard Notes and Details, criteria for sizing control measures, and required maintenance for each control measure.

USE OF CONTROL MEASURES

11.1

The GESC Plan submitted to SEMSWA for approval and subsequently provided to the Contractor with the final construction drawings shall include a set of the GESC Plan - Standard Notes and Details. If there is a conflict between the design, installation, and/or maintenance of a control measure in the GESC Manual and the Standard Notes and Details, the SEMSWA Inspector will determine the appropriate reference to use.

SEMSWA recognizes that there will be new advances in the development of erosion and sediment control measures that may prove effective, or even out-perform controls currently accepted. SEMSWA may allow the installation of alternative erosion and sediment control measures other than the GESC Plan Standard Notes and Details. If alternative erosion and sediment control measures will be used, a cut sheet must be submitted to the SEMSWA Inspector.

SEMSWA reserves the right to reject any control measure proposed or conditionally implemented. If the control measure does not perform with sufficient effectiveness, it would be considered a failed control measure by SEMSWA. In the case of a failed alternate control measure, one or more of SEMSWA's standard control measures shall replace the failed control measure, at the Permittee's expense.

Standard SEMSWA GESC control measures are listed here in alphabetical order for easy reference.

CHECK DAM (CD) / REINFORCED CHECK DAM (RCD)

11.2

The purpose of the Check Dam (CD) is to trap sediment in the backwater zone upstream of the check and, when used in series, to reduce flow velocities. CDs are used only for construction activities within a drainageway. CDs are not to be used to capture sediment transport from any activity near the stream. Once sediment is in the stream from a construction activity, it is a violation of the GESC Permit, and can be enforced upon. Therefore, appropriate control measures shall be used upland to keep sediment from entering the drainageway. The State does not recognize the

use of any control measure within drainageways. Any control measure placed within a drainageway must have the appropriate permit from the Corps.

A Reinforced Check Dam (RCD) is a rock dam contained within a twisted wire gabion, designed to withstand overtopping, that is placed in a major drainageway. Like a check, the purpose of the reinforced check is to trap sediment in the backwater zone upstream of the check. The reinforcement increases the ability of the rock dam to withstand the larger overtopping flows of major drainageways.

If disturbance to a drainageway is significant, such that excessive amounts of sediment may be transported downstream, a CD, reinforced or non-reinforced, shall be installed immediately downstream of the disturbed area in the drainageway. If several areas of disturbance are in close proximity, one CD at the downstream end of the construction may be appropriate. In general, CDs will be used infrequently at typical construction sites since control measures shall be configured to control erosion and trap sediment outside of the limits of drainageways; CDs are only to be used for specialized, permitted stream channel work.

DESIGN

Design parameters to be specified on the GESC plan include the following items:

- Type of check dam (check dam or reinforced check dam).
- Length (L) dimension.
- Crest length (CL) dimension.
- Depth (D) dimension.

The type of check is based on the drainage area upstream of the CD. An RCD shall be used for drainage areas greater than 130 acres. A non-reinforced CD may be used for drainage areas less than 130 acres or as approved by SEMSWA. A Reinforced Rock Berm (RRB) may be used as a check dam for drainage areas less than 20 acres (see Section 11.11).

Dimensions are to be specified to ensure that the check conforms to the existing drainageway cross section shape and provides adequate overtopping capacity.

INSTALLATION AND MAINTENANCE

Key Installation and Maintenance Requirements of CD and RCD:

- Riprap utilized for CDs shall be sized to withstand overtopping and to fit the drainageway and shall be sized per UDFCD criteria.
- Minimum size riprap shall be VL.
- Riprap pad shall be trenched into the channel banks to adequately anchor with the center of the check dam lower to allow for overtopping at the crest.
- Sediment accumulated upstream of the CD shall be removed when the sediment depth upstream of the check dam is within approximately 1/2 of the height of the crest.
- Gabions shall have galvanized twisted wire netting with a maximum opening dimension of 4 1/2" and an appropriate gauge to withstand anticipated flows. Wire hog rings at 4" spacing or other approved means shall be used at all gabion seams and to secure each gabion to the adjacent gabion.
- The GESC Manager shall inspect the CD and/or RCD and maintain in good operating condition.

CONCRETE WASHOUT AREA (CWA)/GROUT WASHOUT AREA (GWA)

11.3

A concrete and/or grout washout area is a contained area to isolate concrete truck and grout washout operations. A Concrete Washout Area (CWA) shall be provided when concrete work is performed. A Grout Washout Area (GWA) shall be provided when grout work is performed.

DESIGN

- If there is a potential for high ground water, the CWA/GWA must have an impervious liner. For portable concrete washouts, sizing of the portable container should be per the manufacturer recommendations.
- The CWA/GWA shall be located a minimum of 50 feet from storm drain inlets, open conveyance channels, drainage facilities and waterways.

INSTALLATION AND MAINTENANCE

Key Installation and Maintenance Requirements for CWA:

- A sign shall be placed at each washout area to clearly indicate the location of the CWA/GWA to operators of concrete trucks and pump rigs.
- Excavated material may be utilized in perimeter berm construction.
- If there is a potential for high ground water, the CWA/GWA must have an impervious liner.
- The CWA/GWA shall be repaired, enlarged, and/ or cleaned out as necessary to maintain capacity for wasted concrete.
- As needed during construction and at the end of construction, all concrete or grout waste shall be removed from the site and disposed of at an approved waste site.
- The GESC Manager shall inspect washout areas and maintain in good operating condition.

CONSTRUCTION FENCE (CF)/CONSTRUCTION MARKERS (CM)

11.4

Construction Fence (CF) consists of orange plastic fencing or other SEMSWA-accepted material attached to support posts and is used to delineate Limits of Construction and to control access to the construction site. When construction within a drainageway is unavoidable, the Design Engineer shall delineate construction limits that restrict activities to the smallest area possible. CF or Construction Markers (CM) shall be indicated on the GESC Plan within the drainageway corridor to indicate the allowable limits of disturbance. In the same manner, CF or CM shall be shown on the GESC Plan throughout the site to identify all Limits of Construction, except in the case of single-family individual lot home construction (Section 3.3).

DESIGN

Design parameters to be specified on the GESC Plan include the following items:

- Location of construction fence or line of markers.
- Length (L) in lineal feet of construction fence or line of markers.

CF or CM shall be shown throughout the site to identify the Limits of Construction. CF or an appropriate alternative method of delineating the project limit shall be required along all drainageways and sensitive resources.

INSTALLATION AND MAINTENANCE

Key Installation and Maintenance Requirements for CF/CM:

- CM consisting of painted or flagged lath at approximately 100-foot spacing may be used to delineate the Limits of Construction, if approved by SEMSWA.
- Steel tee posts shall be utilized for support of construction fence as appropriate to site conditions.
- The GESC Manager shall inspect CF/CM and maintain in good operating condition.

11.5

DEWATERING AS IT RELATES TO SURFACE WATER (DW)

Dewatering controls typically consist of a gravel filter provided on the suction end of a pump to reduce the pumping of sediment, and a riprap pad at the discharge end of the pump for erosion protection. DW may require a sediment basin or filter bag large enough to provide for settling before the water is discharged onto the ground for infiltration or to a temporary settling basin.

Dewatering of groundwater operations is covered by State permits. The Permittee is responsible for obtaining and complying with State-issued permits.

DESIGN

Design parameters to be specified on the GESC Plan include the following items:

- The location of all proposed DW operations.
- The recommended size of the dewatering pump. The size shall be determined to provide sufficient capacity for the proposed pumping rates and may be modified by the Contractor if necessary.
- In addition, SEMSWA may require a Water Control Plan if site conditions warrant.

INSTALLATION AND MAINTENANCE

Key Installation and Maintenance Requirements for DW:

- All DW shall be in accordance with the requirements of any state permits.
- DW operations shall use one or more of the dewatering sumps shown in the GESC Plan - Standard Notes and Details or other means approved by SEMSWA to reduce the pumping of sediment and shall provide a temporary basin for settling pumped discharges prior to release.
- The discharge point shall be to a stabilized area.
- The discharge end of the line shall be staked to prevent movement from the stabilized discharge point.
- Maintenance shall occur per manufacturer's specification for dewatering bags, and replaced when full or ruptured
- Sediment shall be removed from sediment basins when volume is reduced by 50%.
- The GESC Manager shall inspect dewatering systems and perform any necessary repairs or maintenance as necessary.

11.6

DIVERSION DITCH (DD)

A Diversion Ditch (DD) is a small earthen channel used to divert and convey runoff, generally to a Sediment Basin, Check Dam, or Reinforced Rock Berm. Depending on slope, the DD may need to be lined with one of the following: Erosion Control Blanket, plastic (for temporary installations only), PVC, or riprap.

A temporary DD may be necessary at upslope and downslope perimeters, at the top of steep slopes, and downstream of slope drains. DD shall be sized and stabilized according to the criteria below.

DESIGN

Design parameters to be specified on the GESC Plan include the following items:

- Lining of DD (earth, Erosion Control Blanket, riprap, or plastic).
- Length of each type of ditch.
- Depth (D) and width (W) dimensions and slope.
- Location.
- In addition, if the ditch lining is Erosion Control Blanket or riprap, the type of Erosion Control Blanket and size of riprap (D50) needs to be specified.
- Lining type is based on slope of the ditch: unlined- slope equal to or less than 0.5%; ECB lined- slope 0.5%-3%; riprap lined—slope 3%-33%; plastic lined- slope 3%-33%. Dimensions shall be specified to ensure that the ditch adequately conveys runoff from a 2-year return period event for site conditions expected during the operation of the control measure. Ditches or drainageways conveying a 2-year flow rate exceeding 10 cfs shall require specific calculations and a design analysis by the Design Engineer.
- Runoff rate.

INSTALLATION AND MAINTENANCE

Key Installation and Maintenance Requirements:

- In locations where construction traffic must cross a DD, the GESC Manager shall install a temporary culvert that conveys the same flow as the ditch.
- If a DD fills in with sediment, the DD must be maintained to ensure a 2-year flow capacity.
- The GESC Manager shall inspect all DDs and shall ensure they are maintained in good operating condition.

EROSION CONTROL BLANKET (ECB)

11.7

Erosion Control Blanket is a fibrous blanket of straw, jute, excelsior, or coconut material trenched in and staked down over prepared soil. The blanket reduces both wind and water erosion.

ECB shall be required for any disturbed channel banks and all slopes steeper than 3:1. An ECB may be used for lining of a Diversion Ditch, or for temporary stabilization under a downspout (See Appendix D, Page 4). The Design Engineer shall indicate approximate limits of ECB on the GESC Plan.

DESIGN

Parameters to be specified on the GESC Plan include the following items:

- Type of blanket (straw, straw-coconut, coconut, or excelsior).
- Type of blanket shall be based on the shear stress associated with the design flow, as discussed below. Dimensions shall be specified to ensure that the blanket provides protection.
- Area (A) in square yards for each type of blanket.
- Dimensions or location information.

All ECB shall have double sided netting. All ECB and netting should be made of 100% natural and biodegradable material and shall have a minimum product life of 2-years for channel bank applications and 12-month product life for slope applications.

ECB shall be specified based on the judgment of the Design Engineer, but at a minimum, blanket in drainageways shall be sized for the shear stress from a 2-year return period event for site conditions expected during the operation of the matting. Table 6-1 provides the maximum shear stress and velocity, based on unvegetated channel conditions, for allowable types of ECB.

A double-net straw or excelsior blanket shall be used for all slopes steeper than 3:1, outside of drainageways. Concave slope areas that may concentrate sheet flows as well as all other drainage channels (up to the top of the banks) shall require a double-net 70% straw / 30% coconut, double-net 100% coconut, or double-net 100% excelsior blanket based on the shear stress and velocity of the new or disturbed channel. The shear stresses and velocities shown in Figure 6-1 shall be considered the maximum allowable values. Channels where velocities and stresses exceed those shown in Figure 6-1 shall require specific calculations and a design analysis by the Design Engineer.

Shear stress and velocity in ditches and drainageways may be calculated based on the following formulas:

Shear stress (lbs/sf) = $62.4 * D * S$, where:

D (ft) = maximum flow depth for the design (2-yr) storm event;

S (ft/ft) = drainageway slope;

Velocity (ft/sec) = Q/A , where: Q (cfs) = flow rate for the (2-yr) storm event;

A (sf) = cross-sectional area.

Table 6-1 Erosion Control Blanket Type

TYPE	COCONUT CONTENT	STRAW CONTENT	MIN. WEIGHT (lbs/sy)	MANNING'S N VALUE (varies with depth as shown)	ALLOWABLE MAX. SHEAR STRESS (lbs/sf)	ALLOWABLE MAX. VELOCITY (fps)
STRAW	0%	100%	0.5	0.018 for $D \geq 2.0'$ 0.050 for $D \leq 0.5'$	Not allowed in drainage ways or diversion ditches	
STRAW- COCONUT	30% MIN.	70% MAX.	0.5	0.018 for $D \geq 2.0'$ 0.050 for $D \leq 0.5'$	1.75	5.0
COCONUT	100%	0%	0.5	0.018 for $D \geq 2.0'$ 0.050 for $D \leq 0.5'$	2.25	5.0
EXCELSIOR	NA	NA	0.7	0.028 for $D \geq 2.0'$ 0.066 for $D \leq 0.5'$	2.00	5.0

For depths between 0.5 and 2.0-feet, the solution will be iterative, continuing until the depth corresponding to the Manning's N value is within 0.25-feet of the calculated depth. The maximum drainageway shear stress and velocity calculated using the above equations shall be less than the values indicated in Figure 6-1 for the type of blanket specified. This criterion is for temporary ditches and permanent channels designed to be grass-lined. For permanent channels, the types of ECB shown shall be considered to comprise temporary erosion control only until vegetation can be established. The ECB shown herein shall be fabricated from 100 percent natural or biodegradable materials. ECB, as discussed in this section, is to be provided for temporary stabilization of permanent drainageways or roadside ditches that have been designed to be stable with grass or vegetative lining. The ECB is to provide erosion protection until the vegetation is established, and it is therefore an important component of an effective GESC Plan.

Figure 6-1. Erosion Control Blanket Design Criteria

		Shear Stress, lbs/sf										
		0.25	0.50	0.75	1.00	1.25	1.50	1.75	2.00	2.25	>2.25	
Velocity, fps	1	All four types of ECB allowed				All but 100% straw allowed		Excelsior 100% and coconut allowed		100% coconut allowed		
	2											
	3											
	4											
	5											
	>5	Outside allowable range										

INSTALLATION AND MAINTENANCE

Key Installation and Maintenance Requirements:

- All ECB shall be double-sided netting and be made of 100% natural and biodegradable material; no plastic or other synthetic material, even if photodegradable, shall be allowed.
- Unless otherwise approved by SEMSWA, in areas where ECB is shown on the plans, the GESC Manager shall place topsoil and perform final grading, surface preparation, and seeding below the blanket in accordance with the GESC Plan Standard Notes and Details, Seeding and Mulching. Subgrade shall be smooth and moist prior to ECB installation and the ECB shall be in full contact with the subgrade; no gaps or voids shall exist under the ECB. Sufficient stakes will be used to keep blanket in contact with the soil to facilitate vegetation growth.
- Staking spacing dimensions on center shall be based on expected sheer velocities.
- Perimeter anchor trench shall be used at the outside perimeter of all ECB areas.
- Follow all manufacture installation specifications.
- Depending on location, 2 x 4 wedge stakes may be required to be removed prior to Final Close-out.
- The GESC Manager shall inspect ECB and maintain in good operating condition.

A Grade Differential/Curb Cut Back (GD/CCB) control measure is a temporary sediment trap formed by excavation behind the curb/sidewalk/roadway. This control measure's purpose is to intercept sediment-laden runoff from the site during construction and retain sediment on the lot. The hardscape (sidewalk, curb, or roadway) acts as a barrier to retain the stormwater long enough for the sediment to drop out before it leaves the site.

DESIGN

Design parameters to be specified on the GESC Plan include the following items:

- Location of the GD/CCB.
- Length (L) of the GD/CCB.
- Generally, the maximum allowable tributary drainage area per 50 lineal feet of GD/CCB is approximately 5,000 sq ft depending on the slope. Longer and steeper slopes require additional measures. When installed as perimeter control, it should be installed in a way that will not produce concentrated flows.
- Excavate soil from behind the curb, sidewalk, or roadway 3-4 inches down from the top of the hardscape and bring the soil back 3-4 feet from the hardscape. The depth and length of the excavated area may be increased if more sediment storage is needed or if the tributary area is greater than 50 lineal feet per 5,000 sq ft.
- Do not use in areas with 3:1 slopes or greater, or areas with concentrated flow.

INSTALLATION AND MAINTENANCE

Key Installation and Maintenance Requirements:

- The excavated area must be cleaned regularly as site conditions or rain events cause sediment deposition in the excavated area. Inspect this control measure to ensure the excavated area is at a minimum of 3-4 inches in depth and has a width of at a minimum of 3-4 feet.
- Remove accumulated sediment when berms or off-set cut reaches 1/3 capacity. Do not allow sediment to overflow onto curb or sidewalk.
- Do not store construction material within the GD/CCB excavated area.
- The GESC Manager shall inspect GD/CCB and maintain in good operating condition.

A Grout/Mortar Mixing Station (GMS) area is a contained area to isolate grout/mortar mixing operations. A GMS control measure shall be provided when masonry work of any size or dimension is to be performed.

DESIGN

Design parameters to be specified on the GESC Plan include the following items:

- A note that the location of all proposed GMS operations will be determined in the field. The GESC Manager shall locate the GMS a minimum of 50 feet from storm drain inlets, open conveyance channels, drainage facilities and waterways.
- The proposed containment device shall be a minimum of 8" in height; earthen berm, concrete block enclosure, wood frame securely fastened around entire perimeter, or other approved method.

- A minimum 10 mil plastic liner covering entire mixing area shall be securely fastened to the raised containment device.

INSTALLATION AND MAINTENANCE

Key Installation and Maintenance Requirements:

- Area large enough to provide adequate containment off all mixing operations.
- Excavated material may be utilized in perimeter berm construction.
- All materials to be stored adjacent to the GMS shall be on pallets and be covered.
- All grout/mortar washout shall be contained in an approved CWA/GWA.
- At the end of construction, the liner and all grout/mortar waste residue shall be removed from the site and disposed of at an approved waste disposal site.
- The GESC Manager shall inspect the GMS and maintain in good operating condition.

INLET PROTECTION (IP)

11.10

Inlet Protection (IP) consists of a small reinforced rock berm and cinder block frame placed in front of (but not completely blocking) a curb inlet or around an area inlet to reduce sediment in runoff entering the storm sewer system. At some point during a significant storm event, the SEMSWA Inspector may request that IP within the Right-of-Way be removed to allow for safe passage by vehicles. In this instance, sufficient time will be given to replace the IP that has been removed for safety reasons.

Storm sewer inlets on a site shall be provided with IP control measure. The GESC Plan shall specify whether the control measure is an area, sump, or continuous grade IP to be used in a particular location. The continuous grade curb sock IP is intended to trap sediment upstream of an inlet on a continuous grade street without causing any bypass of flow around the inlet. Sump and area IP is also designed to maintain inlet capacity after runoff flows over the wire-enclosed rock.

DESIGN

IP shall be shown on the GESC Plan at all street and area inlets. The GESC Plan shall indicate the type of IP, either sump or continuous grade for curb-opening inlets, or area IP. Determining the length of the reinforced rock berm to fit the inlet is the responsibility of the GESC Manager, as is providing temporary IP in accordance with the GESC Plan Standard Notes and Details.

INSTALLATION AND MAINTENANCE

Key Installation and Maintenance Requirements:

- Interim configuration of IP in streets (before paving) shall be installed immediately after pouring of the inlet and the concrete has taken initial set.
- IP (after paving) shall be installed immediately after paving is placed.
- Wire mesh shall be twisted into a mesh with a maximum opening of 1.0-inch (commonly termed "Chicken Wire").
- Wire mesh shall be secured with wire ties at approximately 6-inch centers along all joints and at approximately 2-inch centers on ends of berm.

- Crushed rock shall be fractured face (all sides) and shall comply with gradation shown on the GESC Plan Standard Notes and Details (1-1/2" minus). Recycled concrete may not be used.
- The top of reinforced rock berm shall allow for overtopping into the inlet.
- No gaps shall exist between sections of reinforced rock berms or cinder block frames.
- Tubular markers shall be placed on each end of IP located on streets where public access can occur.
- Reinforced rock berm or cinder block ends shall be placed tightly against curb face.
- IP is to remain in place until the upstream disturbed area is stabilized and grass cover approved, unless SEMSWA approves earlier removal of IP.
- Maintain IP when there is evidence of significant sediment buildup.
- Replace IP if removed for public/vehicle safety during a significant storm event, as approved by SEMSWA.
- The GESC Manager shall inspect IP and ensure it is maintained in good operating condition. More frequent inspections and repairs may be necessary during winter plowing conditions.

11.11

REINFORCED ROCK BERM (RRB)

A Reinforced Rock Berm (RRB) consists of a linear mass of gravel enclosed in wire mesh to form a porous filter, able to withstand overtopping. The berm is heavy and stable and promotes sediment deposition on its upstream side. Culvert inlets on a site shall be provided with an RRB.

DESIGN

Design parameters to be specified on the GESC Plan include the following items:

- Length (L) dimensions.
- Depth (D) dimensions.
- Location.
- If used in a Diversion Ditch or small drainageway, dimensions are to be specified to ensure that the RRB fits the drainageway cross section shape and provides adequate overtopping capacity. Multiple RRBs may be used as a Check Dam across swales and small drainageways for up to 20 acres of upstream drainage area.

INSTALLATION AND MAINTENANCE

Key Installation and Maintenance Requirements:

- Crushed rock shall be fractured face (all sides) and shall comply with gradation shown in the GESC Plan - Standard Notes and Details (1-1/2" minus). Recycled concrete may not be used.
- Wire mesh shall be wire twisted into a mesh with a maximum opening of 1.0-inch ("Chicken Wire").
- Wire mesh shall be secured wire ties at approximately 6-inch centers along all joints and at approximately 2-inch centers on ends of berm.
- Sediment accumulated upstream of RRB shall be removed when the sediment depth upstream of filter is 50% of the height or if the rock becomes further clogged.
- The GESC Manager shall inspect RRB and ensure it is maintained in good operating condition.

11.12

SEDIMENT BASIN (SB)

A Sediment Basin (SB) is an impoundment that captures sediment-laden runoff and releases it slowly, providing prolonged settling times to capture coarse and fine-grained soil particles. Runoff from disturbed drainage areas

exceeding one (1) acre shall be treated in a SB. Runoff from disturbed areas less than 1.0 acre may be treated in a Sediment Trap.

DESIGN

Design parameters shall be specified on the GESC Plan and include the following items:

- Location.
- Outlet release design based on Table 6-2 below.
- The SB design shown on the GESC Plan - Standard Notes and Details provided in Appendix F shall be used for any disturbed drainage area greater than 1.0 acre. The standard SB is appropriate for use for disturbed drainage areas up to 15 acres. For drainage areas greater than 15 acres, a UDFCD *Volume 3* design must be prepared. For those areas greater than 15 acres, calculations should be included within the report.
- The SB discharge point must be to a stabilized area that does not drain back into a disturbed area.

Sizing information for the SB design (based on providing a minimum initial storage volume equal to 1,800 cubic feet per upstream acre) shall be determined from Table 6-2. As shown on the GESC Plan - Standard Notes and Detail sheets, the standard SB features a pipe outlet drilled with a single column of orifice holes. The hole diameter shown in Table 6-2 will drain the upper 1.5 feet of the SB in about 40 hours.

Table 6-2. Sizing Information for Standard Sediment Basin

Upstream Drainage Area (rounded to nearest acre), (ac)	Basin Bottom Width (W), (ft)	Spillway Crest Length (CL), (ft)	Hole Diameter (HD), (in)
1	16	2.0	7/16
2	22	4.0	5/8
3	27	6.0	3/4
4	31	8.0	7/8
5	35	10.0	1.0
6	38	12.0	1 1/8
7	41	14.0	1 1/4
8	44	16.0	1 1/4
9	47	18.0	1 3/8
10	49	20.0	1 3/8
11	52	22.0	1 1/2
12	54	24.0	1 1/2
13	56	26.0	1 5/8
14	59	28.0	1 5/8
15	61	30.0	1 3/4

Outlet facilities for extended detention basins that provide a drain time of 40-hours may be used as the SB outlet, with proper outlet control measures in place.

INSTALLATION AND MAINTENANCE

Key Installation and Maintenance Requirements:

- A gravel pack of rock around the pipe outlet shall be provided. The rock needs to be sized appropriately to not clog the outlet.
- Sediment accumulated within the SB shall be removed when the design storage volume is no more than 1/3 filled with sediment.
- The SB volume shall be maintained to the design intent and kept in a maintained condition until vegetation in upstream watershed is fully established and accepted.
- Trash and debris shall be removed from the SB to prevent clogging at the outlet.
- The GESC Manager shall inspect the SB control measure and shall ensure it is maintained in good operating condition.

11.13

SEDIMENT CONTROL LOG (SCL)

A Sediment Control Log (SCL) consists of a cylindrical bundle of excelsior, straw, or coconut material designed to form a semi-porous filter, able to withstand overtopping.

DESIGN

Design parameters to be specified on the GESC Plan shall include the following items:

- Location of the SCL.
- Length (L) of the SCL.
- Generally, the maximum allowable tributary drainage area per 50 lineal feet of SCL, installed along the contour, is approximately 5,000 sq ft depending on the slope. Longer and steeper slopes require additional measures. This recommendation only applies to SCL installed along the contour. When installed for other uses, such as perimeter control, it should be installed in a way that will not produce concentrated flows. For example, a "J-hook" installation may be appropriate to force runoff to pond and evaporate or infiltrate in multiple areas, rather than concentrate and cause erosive conditions parallel to the SCL.
- SCL shall not be used across swales or drainageways.
- In most cases, SCL shall be located on the contour. SCL may be shown running up or down slight slopes.

INSTALLATION AND MAINTENANCE

SCL shall be staked into the ground to promote sediment deposition on its upstream side and a reduction in flow velocities.

Key Installation and Maintenance Requirements:

- The SCL shall be trenched into the ground per manufacturer instructions.
- SCL shall be maintained when upstream sediment reaches 50%.
- The GESC Manager shall inspect and ensure SCL is maintained in good operating condition.

SEDIMENT TRAP (ST)

11.14

A Sediment Trap (ST) consists of a riprap berm with a small upstream basin that acts to trap coarse sediment particles. It may be used for upstream disturbed areas less than 1.0 acre. Runoff from disturbed areas exceeding 1.0 acre shall be treated in a Sediment Basin.

DESIGN

Design parameters shall be specified on the GESC Plan and include the following items:

- Location, length (L) and width (W) dimensions. A ST may be used for upstream disturbed areas less than 1.0 acre. ST dimensions shall be specified to provide a storage volume equal to 1,800 cubic feet per upstream acre.
- ST designed in series shall require a specific calculation and a design analysis by the Design Engineer.
- Overtopping must occur on stabilized surfaces, to include well vegetated areas, riprap, or pavement.

INSTALLATION AND MAINTENANCE

Key Installation and Maintenance Requirements:

- The top of the earthen berm shall allow for overtopping at the crest.
- The ends of the riprap outlet structure shall be higher than the center of the outlet structure to allow for overtopping at the crest.
- Sediment accumulated within in the ST shall be removed when volume is reduced by approximately 50%.
- The GESC Manager shall inspect the ST and ensure it is maintained in good operating condition.

SEEDING AND MULCHING (SM)

11.15

Seeding and Mulching (SM) consists of drill seeding disturbed areas with the approved SEMSWA seed mix and crimping in straw mulch to provide immediate protection against water and wind erosion and, as the grass cover becomes established, to provide long-term stabilization of exposed soils.

For permanent stabilization (i.e. final grading is completed), SEMSWA requires that the disturbed area be permanently seeded and mulched. If the time of year does not allow for seeding operations to be effective, the Permittee may be granted an extension on the seeding requirement, however; mulching of the area will be required. The Permittee will be required to seed and mulch the disturbed area by the date that is provided by the SEMSWA Inspector on the inspection report.

DESIGN

Design parameters to be specified on the GESC Plan include the following items:

- Area (A) in acres to be SM.
- Type of seed mix.

All projects include a seed mix recommendation provided by a Landscape Architect with sufficient knowledge of the project. If a Landscape Architect does not provide a seed mix, then SEMSWA's standard seed mix shall be specified. The main requirements include the following:

- Existing topsoil shall be stripped to a depth of six inches (unless otherwise approved) from areas to be disturbed. The stripped topsoil shall be stockpiled during grading operations, then replaced to a depth of at least six inches in all areas to be seeded. If quantities of on-site topsoil are inadequate to provide a replaced depth of six inches, the Permittee/Contractor will have to import topsoil or condition the soil as approved by SEMSWA. All disturbed areas are to be ripped prior to placing topsoil. Topsoil shall be thoroughly loosened prior to seeding to a depth of at least six inches.
- Seeding shall be accomplished using a drill seeder at a depth of seeding not less than 1/4-inch and not more than 3/4-inch and at the rates specified in the GESC Plan - Standard Notes and Details. In small areas that are impossible to drill seed, the Permittee/Contractor, with SEMSWA's prior approval, may hand broadcast seed at twice the drilled rate, lightly rake to cover the seed, and crimp mulch. Information on seed types in SEMSWA's standard seed mixes is provided in Appendix F.
- Straw mulch shall be applied at a rate of 4,000-pounds per acre and mechanically crimped into the soil and tackified where needed. In places where straw mulch cannot be mechanically crimped due to site constraints, Hydraulic mulch may be considered, with approval from SEMSWA.

INSTALLATION AND MAINTENANCE

Key Installation and Maintenance Requirements:

- All areas to be seeded and mulched shall have native topsoil or appropriately conditioned soil spread to a depth of at least 6-inches (loose depth).
- All disturbed areas shall be loosened (tilled) to a depth of 6-inches prior to spreading topsoil.
- The top 6-inches of the seed bed shall be generally free of rocks, woody debris and soil clods.
- Stockpiles and areas that are being temporarily seeded do not require topsoil prior to seeding and mulching.
- Seed shall be applied using a mechanical drill to a depth of not less than 1/4-inch and not more than 3/4-inch. Row spacing shall be no more than 6-inches. Material used for mulch shall consist of long-stemmed straw. At least 50-percent of the straw, by weight, shall be 10-inches or more in length. Mulch shall be applied and mechanically anchored to a depth of at least 2-inches. Mulch shall be applied at a rate of 4,000-pounds of straw per acre.
- Copies of seed tickets shall be provided to the SEMSWA Inspector, upon request.
- Temporary Irrigation is highly encouraged to assist with growth of vegetation.
- Seeded and mulched areas shall be inspected for required coverage monthly, until the site reaches final acceptance. Repairs and re-seeding and mulching shall be undertaken for any areas failing to meet the required coverage until final acceptance. Required coverage is defined as 70% of the existing/preconstruction condition, free of eroded areas, and free from infestation of noxious weeds.

11.16

SILT FENCE (SF)

Silt Fence (SF) is a temporary sediment barrier constructed of woven fabric stretched across supporting posts. The bottom edge of the fabric is placed in an anchor trench that is backfilled with compacted soil.

DESIGN

Design parameters to be specified on the GESC Plan include the following items:

- Location of SF.
- Length (L) in linear feet of SF.

- SF works most effectively when placed relatively level, on the contour, to capture and filter approaching sheet flow. It is not suited for concentrated flow or for large upstream drainage areas. The following criteria shall apply to the use of SF:
 - SF shall not be used across swales or drainageways.
 - SF shall be located on the contour. SF may be shown running up or down slight slopes.
 - The average upslope length of the area draining to an individual section of SF shall not exceed 100 disturbed feet and the total area draining to a section of SF shall not exceed 10,000 square feet of disturbed area.
 - SF located at the toe of a slope should be placed a minimum of five feet offset from the toe to allow for maintenance activities.
 - SF used to protect the drainageway from upland construction activities shall be wire-backed.

INSTALLATION AND MAINTENANCE

Key Installation and Maintenance Requirements:

- The bottom portion of the SF shall be trenched in and compacted per the GESC Plan - Standard Notes and Detail. SF installation machines that use trenching or slicing may be utilized to install SF.
- Sediment accumulated upstream of SF shall be removed when the upstream sediment reaches 25%.
- SF near the roadway is the responsibility of the Permittee/Contractor to maintain, even if damaged from public snow removal operations.
- The GESC Manager shall inspect SF and ensure it is maintained in good operating condition.

SLOPE INTERCEPT DITCH (SID)

11.17

A Slope Intercept Ditch (SID) is a small earth channel with accompanying earthen berm cut in on the contour used to check stormwater surface flows from leaving a construction site and to prevent run-on of stormwater surface flows from undisturbed areas contiguous with the construction site.

DESIGN

Design parameters to be specified on the GESC Plan include the following items:

- Location and length of each SID.
- May be used in place of Silt Fence and Sediment Control Logs, as appropriate.

INSTALLATION AND MAINTENANCE

Key Installation and Maintenance Requirements:

- Material cut out of the SID should form a compacted berm adjacent to, on the construction side of the SID.
- Minimum SID depth shall be 10 inches.
- Compacted berm from SID spoils shall be a minimum 10 inches in height.
- Sediment accumulated in the SID shall be removed when half-full. Sediment shall be placed on and compacted with the adjacent berm.
- The GESC Manager shall inspect all SID and shall ensure they are maintained in good operating condition.

STABILIZED STAGING AREA (SSA)

A Stabilized Staging Area (SSA) consists of stripping topsoil and spreading a layer of angular granular material in the area to be used for a trailer, parking, storage, unloading and loading.

An SSA shall be provided near the main access point and ideally connected to the Vehicle Tracking Control.

DESIGN

Design parameters to be specified on the GESC Plan include the following:

- Location of SSA.
- Approximate area (A) in square yards of the SSA.

Gravel or road base may be used for the SSA. Recycled asphalt shall not be used. Recycled concrete may be used upon SEMSWA approval.

INSTALLATION AND MAINTENANCE

Key Installation and Maintenance Requirements:

- SSA shall be large enough to contain parking, storage, and unloading and loading operations.
- SSA shall consist of a minimum thickness of 3 inches of angular granular material.
- The GESC Manager shall inspect the SSA and ensure it is maintained in good operating condition.

STREET SWEEPING (SS)

Street Sweeping consists of cleaning mud and other debris which is tracked onto impervious surface at a construction site. Street sweeping shall be used for incidental tracking and is not to be used as a perimeter control measure or as the sole control measure. Removing all tracked mud from the streets reduces or eliminates sediment transport to downstream structures and receiving water.

Any damage from sweeping public streets may require repair to the street and shall be paid for by the Permittee.

DESIGN

No design is required for SS.

INSTALLATION AND MAINTENANCE

Key Installation and Maintenance Requirements:

- Any mud tracked onto the street shall be cleaned using a vacuum-type street sweeper, a brush-type street sweeper with dust control, or manually using shovels and brooms.
- Ensure all appropriate permits for sweeping public streets are obtained.
- Streets shall not be washed with water at any time unless all water is contained and collected.
- The GESC Manager shall inspect streets and ensure they are free of dirt and debris.

SURFACE ROUGHENING (SR)

Surface Roughening (SR) consists of creating a series of grooves or furrows on the contour in all disturbed, graded areas to trap rainfall and reduce the formation of rill and gully erosion. This is an effective control measure that can be used to control runoff for areas of the site and provides a layered control measure approach, or treatment train approach to limit runoff and sediment transport.

DESIGN

Since SR is to be performed for all disturbed, graded areas on a site, the location of SR does not need to be indicated on the plan.

INSTALLATION AND MAINTENANCE

Key Installation and Maintenance Requirements:

- Disturbed surfaces shall be roughened using ripping or tilling equipment on the contour or tracking up and down a slope using equipment treads.
- The GESC Manager shall inspect SR and shall ensure it is maintained in good operating condition.

TEMPORARY SLOPE DRAIN (TSD)

11.21

A Temporary Slope Drain (TSD) is a small culvert, plastic rundown or riprap rundown to convey runoff down a slope or channel bank to reduce the occurrence of rill and gully erosion.

A TSD shall be used to convey runoff down a channel bank or slope to the bottom of a drainageway. When a ditch, constructed to convey runoff, intersects a slope or channel bank, a TSD, consisting of pipe, plastic, or riprap, shall be required to convey diverted water from the DD down the slope or channel bank.

DESIGN

Design parameters to be specified on the GESC Plan include the following items:

- Type of TSD (pipe, riprap lined, or plastic lined).
- Location and length (L) in linear feet.
- “D” dimension and “D50” size.
- Dimensions are to be specified to ensure that the TSD provides capacity equal to a 2-year return period event for site conditions expected during the operation of the slope drain.

INSTALLATION AND MAINTENANCE

Key Installation and Maintenance Requirements:

- An energy dissipater shall be placed at the outfall of the TSD.
- The GESC Manager shall inspect the TSD and ensure it is maintained in good operating condition.

TEMPORARY STREAM CROSSING (TSC)

11.22

A Temporary Stream Crossing (TSC) consists of culverts covered with rock to allow construction equipment to cross a stream. Excavation of the existing channel and disturbance is to be kept to a minimum.

Crossing drainageways with construction equipment requires a TSC. Appropriate control measures shall still be used to keep sediment from entering the drainageway. Any control measure placed within a drainageway must have the appropriate permits from the Corps and SEMSWA. In addition, SEMSWA may require a Water Control Plan.

DESIGN

Design parameters to be specified on the GESC Plan include the following items:

- Location of TSC.
- Length (L), height (Y), overtopping depth (H), diameter (D) and number of culverts.

The type of TSC is based on the presence of baseflow and the shape of the channel. If there is any baseflow present, or the channel is relatively deep and narrow, a culvert crossing shall be used. For temporary culvert crossings, the Design Engineer shall specify pipe class, minimum cover, etc. to ensure that the culverts will bear the loads associated with the type of vehicles that may use the crossing. The structural capacity of the crossing may require specific calculations and a design analysis by the Design Engineer.

INSTALLATION AND MAINTENANCE

Key Installation and Maintenance Requirements:

- Sediment accumulated upstream of TSC shall be removed when the sediment depth upstream of crossing is 50% or greater of the culvert opening.
- The GESC Manager shall inspect TSC and ensure it is maintained in good operating condition.

11.23

VEHICLE TRACKING CONTROL (VTC)

Vehicle Tracking Control (VTC) consists of a crushed rock pad that is 12 inches thick at all exit points for a site. VTC is intended to strip mud from tires prior to vehicles and equipment leaving the construction site.

VTC shall be provided at all exit points at the site. The number of access points at a construction site shall be minimized.

DESIGN

Design parameters to be specified on the GESC Plan include the following:

- Location of all VTCs.

INSTALLATION AND MAINTENANCE

Key Installation and Maintenance Requirements:

- VTC shall be installed at every access point from the construction site.
- VTC shall consist of hard, dense, durable stone, angular in shape and resistant to weathering. Rounded stone or boulders will not be acceptable. The stones shall not be smaller than 3- inches in size.
- Curb ramps of any type are not allowed in the curb section.
- VTC must be maintained whenever tracking is evident, or at the discretion of the SEMSWA Inspector.
- The GESC Manager shall inspect the VTC and ensure it is maintained in good operating condition.

VEHICLE TRACKING CONTROL WITH WHEEL WASH (WW)

11.24

Vehicle Tracking Control with Wheel Wash (WW) does not need to be specified. It shall be used if specifically required by the SEMSWA Inspector. Typically, if vehicle tracking onto public streets is a repetitive violation, a WW will be required by the SEMSWA Inspector.

DESIGN

No design is required.

INSTALLATION AND MAINTENANCE

WW consists of a gravel and riprap pad at the main exit point for the site with an adjacent wash water/sediment trap. If SEMSWA requires a Contractor to implement this control measure, each wheel of all vehicles coming into contact with dirt or mud shall be cleaned using a high-pressure washer prior to the vehicle leaving the site.

12 AUTHORIZATION OF THE GESC MANUAL

12

The *GESC Manual* is authorized and approved by the SEMSWA Board of Directors.

AMENDMENTS AND REVISIONS

12.1

These GESC criteria and associated policies may be amended and revised as new technology is developed and experience is gained. The SEMSWA Board, following the recommendations of the Executive Director, may consider such amendments and revisions. Minor revisions that do not affect policy may be made without action of the Board.

ENFORCEMENT RESPONSIBILITY

12.2

The SEMSWA Board, acting through the Executive Director, shall enforce the provisions of the *GESC Manual*.

Appendix A: GESC Contact Information

(Information is subject to change)

SEMSWA

Maintenance & Inspections Division

Phone: 303-858-8844

Fax: 303-267-9550

Email: dolsen@semswa.org

Web: www.SEMSWA.org

City of Centennial

Community Development

13133 East Arapahoe Road

Centennial, Colorado 80111

Phone: 303-754-3308

Fax: 720-488-0933

Web: www.centennialco.gov

Other

Colorado Department of Public Health and
Environment

Water Quality Control Division

Phone: 303-692-3500

Web: www.colorado.gov/cdphe

U.S. Army Corps of Engineers, Omaha District
Tri-Lakes Project Office

Phone: 303-979-4120

Fax: 303-979-0602

United States Department of the Interior
Fish and Wildlife Division

Phone: 303-326-7400

Urban Drainage and Flood Control District

Phone: 303-455-6277

Fax: 303-455-7880

Web: www.udfcd.org

Federal Emergency Management Agency
Region VIII

Phone: 303-235-4800

Fax: 303-235-4976

Web: www.fema.gov

Cherry Creek Basin Water Quality Authority

Phone: 303-779-4525

Fax: 303-773-2050

Web: www.cherrycreekbasin.org

Arapahoe County Weed Control Specialist
Arapahoe County Government - Public Works
and Development

Phone: 720-874-6500

Fax: 303-794-3201

Web: www.co.arapahoe.co.us

SEMSWA GESC Permit Program

**HOLD HARMLESS LETTER
FOR
EARLY START OF GRADING**

Manager, Land Development Review Services
Southeast Metro Stormwater Authority (SEMSWA)
7437 South Fairplay Street
Centennial, CO 80112-4486

Subject: Early Start (Grading Only) for:

☐ Planning Commission Approval

Project No: _____

☐ City Council Approval

Project Name: _____

☐ City Planning Director Approval

To Whom It May Concern,

We are requesting an early start on implementing the Grading, Erosion and Sediment Control (GESC) Plan(s) for the project. The Construction Drawings, Phase III Drainage Report, and/or other technical documents have not yet been approved by SEMSWA, the City of Centennial, or Arapahoe County, as applicable. In order to start this work, we understand that the GESC Plan(s) must be complete, submitted to SEMSWA for review, and approved by SEMSWA, the GESC Permit complete, submitted, and approved, and the collateral posted.

We further understand that any work that occurs under this Early Grading Hold Harmless Letter will be at the risk of the owner. Specifically, any changes required for the GESC Plan(s) or GESC Permit resulting from approved Construction Drawings, or other applicable documents, will be the responsibility of the owner. We acknowledge that SEMSWA will not be held responsible for those changes. We shall be responsible for all the costs associated with any changes that may be required by SEMSWA under the GESC Plan(s), Report and/or Permit. SEMSWA shall not be responsible for any costs.

I have read the SEMSWA GESC Manual, specifically the GESC Permit Policies, and understand that the owner assumes all of the risk of completing grading prior to approval of development plans for a site. Approval of the GESC Plan(s) and Report does not imply approval of other engineering concepts or documents associated with a submittal. Prior to the issuance of the approved GESC Permit, we will submit the required collateral for the revegetation/stabilization of the site and/or all of the erosion and sediment control measures that are required to be installed per the GESC Plan for the development site.

Sincerely,

(Owner's Name, Title, and Signature)

Date: _____

SEMSWA GESC Permit

Engineer's Cost Estimate Spreadsheet for Final Control Measures

Note: Final Control Measures (CM) shall be added together for the Cost Estimate

Project Name: _____ Date: _____

CM No.	Control Measures	ID	Unit	Installation Unit Cost	Final Quantity	Final Cost
1	Check Dam	CD	LF	\$ 24.00		\$ -
2	Compost Blanket	CB	SF	\$ 0.36		\$ -
3	Compost Filter Berm	CFB	LF	\$ 2.00		\$ -
4	Concrete Washout Area	CWA	EA	\$ 100.00		\$ -
5	Construction Fence	CF	LF	\$ 2.00		\$ -
6	Construction Markers	CM	LF	\$ 0.20		\$ -
7	Dewatering	DW	EA	\$ 600.00		\$ -
8	Diversion Ditch	DD	LF	\$ 1.60		\$ -
9	Erosion Control Blanket	ECB	SY	\$ 5.00		\$ -
10	Inlet Protection	IP	EA	\$ 200.00		\$ -
11	Reinforced Check Dam	RCD	LF	\$ 36.00		\$ -
12	Reinforced Rock Berm	RRB	LF	\$ 9.00		\$ -
13	RRB for Culvert Protection	RRC	LF	\$ 9.00		\$ -
14	Sediment Basin	SB	AC	\$ 1,000.00		\$ -
15	Sediment Control Log	SCL	LF	\$ 2.00		\$ -
16	Sediment Trap	ST	EA	\$ 600.00		\$ -
17	Seeding & Mulching (Less than 10 Acres)	SM	AC	\$ 2,500.00		\$ -
	(Greater than 10 Acres)	SM	AC	\$ 1,500.00		\$ -
18	Silt Fence	SF	LF	\$ 2.00		\$ -
19	Stabilized Staging Area	SSA	SY	\$ 2.00		\$ -
20	Surface Roughening	SR	AC	\$ 600.00		\$ -
21	Temporary Slope Drain	TSD	LF	\$ 30.00		\$ -
22	Temporary Stream Crossing	TSC	EA	\$ 1,000.00		\$ -
23	Terracing	TER		\$ -		\$ -
24	Vehicle Tracking Control	VTC	EA	\$ 1,000.00		\$ -
25	VTC with Wheel Wash	WW	EA	\$ 1,500.00		\$ -
26	Mobilization (required on all projects)	MB	LS	\$ 5,000.00	1	\$ 5,000.00
27	Pond Maintenance/Sediment Removal (Based on area tributary to the pond)	PM	AC	\$ 1,000.00		\$ -
28	Street Maintenance (Based on lane miles of streets within project and frontage)	SM	LM	\$ 500.00		\$ -
29	Other: _____			\$ -		\$ -
Total Cost of Final Control Measures						\$ 5,000.00


SEMSWA GESC Permit

Engineer's Cost Estimate Spreadsheet for Initial and Interim Control Measures

Note: *Initial* and *Interim* Control Measures (CM) shall be added together for the Cost Estimate

Project Name: _____ Date: _____


CM No.	Control Measures	ID	Unit	Installation Unit Cost	Initial/Interim Quantity	Initial/Interim Cost
1	Check Dam	CD	LF	\$ 24.00		\$ -
2	Compost Blanket	CB	SF	\$ 0.36		\$ -
3	Compost Filter Berm	CFB	LF	\$ 2.00		\$ -
4	Concrete Washout Area	CWA	EA	\$ 100.00		\$ -
5	Construction Fence	CF	LF	\$ 2.00		\$ -
6	Construction Markers	CM	LF	\$ 0.20		\$ -
7	Dewatering	DW	EA	\$ 600.00		\$ -
8	Diversion Ditch	DD	LF	\$ 1.60		\$ -
9	Erosion Control Blanket	ECB	SY	\$ 5.00		\$ -
10	Inlet Protection	IP	EA	\$ 200.00		\$ -
11	Reinforced Check Dam	RCD	LF	\$ 36.00		\$ -
12	Reinforced Rock Berm	RRB	LF	\$ 9.00		\$ -
13	RRB for Culvert Protection	RRC	LF	\$ 9.00		\$ -
14	Sediment Basin	SB	AC	\$ 1,000.00		\$ -
15	Sediment Control Log	SCL	LF	\$ 2.00		\$ -
16	Sediment Trap	ST	EA	\$ 600.00		\$ -
17	Seeding & Mulching (Less than 10 Acres)	SM	AC	\$ 2,500.00		\$ -
	(Greater than 10 Acres)	SM	AC	\$ 1,500.00		\$ -
18	Silt Fence	SF	LF	\$ 2.00		\$ -
19	Stabilized Staging Area	SSA	SY	\$ 2.00		\$ -
20	Surface Roughening	SR	AC	\$ 600.00		\$ -
21	Temporary Slope Drain	TSD	LF	\$ 30.00		\$ -
22	Temporary Stream Crossing	TSC	EA	\$ 1,000.00		\$ -
23	Terracing	TER		\$ -		\$ -
24	Vehicle Tracking Control	VTC	EA	\$ 1,000.00		\$ -
25	VTC with Wheel Wash	WW	EA	\$ 1,500.00		\$ -
26	Mobilization (required on all projects)	MB	LS	\$ 5,000.00	1	\$ 5,000.00
27	Pond Maintenance/Sediment Removal (Based on area tributary to the pond)	PM	AC	\$ 1,000.00		\$ -
28	Street Maintenance (Based on lane miles of streets within project and frontage)	SM	LM	\$ 500.00		\$ -
29	Other: _____			\$ -		\$ -
Total Cost of Initial & Interim Control Measures						\$ 5,000.00




— x — SILT FENCE / SEDIMENT CONTROL LOG

← DIRECTION OF SURFACE WATER RUNOFF

EROSION CONTROL BLANKET






— x — SILT FENCE / SEDIMENT CONTROL LOG
 ← DIRECTION OF SURFACE WATER RUNOFF


NOTE: THIS PLAN MAY BE USED WHEN ONLY A PART OF THE LOT IS DISTURBED.

COMMON DRAINAGE SWALE AND DOWNSPOUT PROTECTION DETAIL (BETWEEN HOUSES)



NOTE: DETAIL MUST BE IMPLEMENTED WHEN DOWNSPOUTS ARE INSTALLED ON HOUSE(S)

EXAMPLE: DOWNSPOUT PROTECTION DETAIL



Appendix E: SEMSWA DRAWING AND REPORT CHECKLIST FOR STANDARD GESC PERMITS

A. DRAWINGS

I. COVER SHEET

- ☐ yes ☐ no 1. Project Name.
☐ yes ☐ no 2. Project address (if applicable) shall include zip code or location/intersection
☐ yes ☐ no 3. Owner address (shall include zip code).
☐ yes ☐ no 4. Design firm's name and address (shall include zip code).
☐ yes ☐ no 5. Plan sheet index.
☐ yes ☐ no 6. SEMSWA Case Number in the lower left hand corner.
☐ yes ☐ no 7. The following note:

"This *Grading, Erosion and Sediment Control (GESC)* document has been placed in the SEMSWA file for this project and appears to fulfill the latest version of the *SEMSWA Grading, Erosion and Sediment Control Manual*. Additional grading, erosion and sediment control measures may be required of the owner or his/her agents, due to unforeseen erosion problems or if the submitted plan does not function as intended. The requirements of this GESC document shall run with the land and be the obligation of the land owner, or his/her designated representative(s) until such time as the plan is properly completed, modified or voided."

- ☐ yes ☐ no 8. GESC Drawing Design Engineer's signature block with name, date, and Professional Engineer registration number. Signature block shall include the following certification statement:

"I hereby attest that this Grading, Erosion, and Sediment Control (GESC) document for (*name of subdivision/development*) has been prepared by me or under my direct supervision, and to the best of my knowledge and ability has been prepared in accordance with the latest version of the SEMSWA GESC Manual. The signature and stamp affixed hereon certifies that this GESC document was prepared in accordance with the required regulations and criteria; however, the stamp and signature does not certify or guarantee future performance of the execution of the plan by the Contractor. The Contractor is responsible for executing the construction work according to the information set forth in the plan and in accordance with all applicable requirements."

Registered Professional Engineer _____
 State of Colorado No. _____
 Affix Seal w/date

- ☐ yes ☐ no 9. Landowner/authorized agent acknowledging GESC review and the acceptance of GESC responsibility. Signature block shall include the following certification statement:

"I hereby certify that the Grading, Erosion, and Sediment Control measures for (*Name of Subdivision/Development/address*) shall be constructed according to the design presented in this document. I understand that additional erosion control, sediment control and water quality enhancing measures may be required of the owner and his or her agents due to unforeseen pollutant discharges or if the submitted plan does not function as intended. The requirements of the plan shall be the obligation of the land owner and/or his successors or heirs; until such time as the plan is properly completed, modified or voided."

Owner or Authorized Agent _____
 Authorized Signature _____ Date _____

- ___ yes ___ no 10. SEMSWA Approval Block (see Appendix G)
- ___ yes ___ no 11. General Location Map at a Scale of 1-inch to 1000 feet to 8000 feet indicating:
- General vicinity of the site location
 - Major roadway names
 - North arrow and scale

II. GESC DRAWING INDEX SHEET

For projects that require multiple plan-view sheets to adequately show the project area (based on the specified scale ranges), a single plan-view sheet shall be provided at a scale appropriate to show the entire site on one sheet. Areas of coverage of the multiple blow-up sheets are to be indicated as rectangles on the index sheet.

III. INITIAL GESC DRAWING

This plan sheet shall provide grading, erosion and sediment controls for the initial clearing, grubbing and grading of a project. At a minimum, it shall contain:

- ___ yes ___ no 1. Property lines.
- ___ yes ___ no 2. Existing and proposed easements.
- ___ yes ___ no 3. Existing topography at one or two foot contour intervals, extending a minimum of 100 feet beyond the property line.
- ___ yes ___ no 4. Location of any existing structures or hydrologic features within the mapping.
- ___ yes ___ no 5. Flow arrows.
- ___ yes ___ no 6. Floodplain delineation.
- ___ yes ___ no 6. USGS Benchmark used for project (must be NAVD 88)
- ___ yes ___ no 7. Limits of construction encompassing all areas of work access points, storage and staging areas, borrow areas, stockpiles, and utility tie-in locations in on-site and off-site locations. Stream corridors and other resource areas to be preserved and all other areas outside the limits of construction shall be lightly shaded to clearly show area not to be disturbed.
- ___ yes ___ no 8. Location of stockpiles, including topsoil, imported aggregates, and excess material.
- ___ yes ___ no 9. Location of storage and staging areas for equipment, fuel lubricant, chemical (and other materials) and waste storage.
- ___ yes ___ no 10. Location of borrow or disposal areas.
- ___ yes ___ no 11. Location of temporary roads, including haul roads.
- ___ yes ___ no 12. Location, map symbol, and letter callouts of all initial erosion and sediment Control Measures.
- ___ yes ___ no 13. Location, map symbol, and letter callouts of Vehicle Tracking Control(s) (VTC).
- ___ yes ___ no 14. Location, map symbol, and letter callouts of Concrete Washout Area(s) (CWA).
- ___ yes ___ no 15. Location, map symbol, and letter callouts of dedicated asphalt and concrete batch plants.
- ___ yes ___ no 16. Locations of other areas or operations where spills can occur.
- ___ yes ___ no 17. Location, map symbol, and letter callouts for any anticipated Dewatering (DW) activities. Note: Dewatering of groundwater is covered by state permits. The Permittee is responsible for obtaining and complying with State-issued permits.
- ___ yes ___ no 18. Information to be specified for each Control Measure, such as type and dimensions as called for in the Standard Notes and Details.

___ yes ___ no

19. The following notes:

- APPROPRIATE CONTROL MEASURES MUST BE IMPLEMENTED PRIOR TO THE START OF ACTIVITY, MUST CONTROL POTENTIAL POLLUTANTS DURING EACH PHASE OF CONSTRUCTION, AND MUST BE CONTINUED THROUGH FINAL STABILIZATION. APPROPRIATE STRUCTURAL CONTROL MEASURES MUST BE MAINTAINED IN OPERATIONAL CONDITION.
- SEE SEMSWA STANDARD NOTES AND DETAILS (SHEET 1 OF 4) FOR LEGEND OF CONTROL MEASURE NAMES AND SYMBOLS.
- ANY CONTROL MEASURES SHOWN THAT REQUIRE GRADING, (E.G. SEDIMENT BASINS, SEDIMENT TRAPS, CONCRETE WASH-OUT AREAS, ETC...), SHALL NOT BE PLACED UNTIL AFTER THE PRE-CONSTRUCTION MEETING AND ISSUANCE OF THE GESC PERMIT, BUT MUST BE FULLY FUNCTIONAL PRIOR TO ANY LARGE SCALE GRADING. THE INITIAL PLAN ILLUSTRATES EXISTING CONDITIONS. NO PROPOSED INFRASTRUCTURE IS SHOWN.

___ yes ___ no

19. Other information as may be required by SEMSWA.

IV. INTERIM GESC DRAWING

This plan sheet shows Control Measures to control grading, erosion and sediment during the initial over lot grading, site construction and site re-vegetation process. The Interim GESC Plan shall show all the information included on the Initial GESC Plan, as noted below. At a minimum, it shall contain the following information:

- | | |
|----------------|---|
| ___ yes ___ no | 1. Existing topography at one or two foot contour intervals extending a minimum of 100 feet beyond the property line, as shown on Initial GESC Plan. These contours shall be screened. |
| ___ yes ___ no | 2. Location of all existing erosion and sediment control measures on site, as shown on the INITIAL GESC Plan Sheet. These control measures shall be screened. Dimension information for initial stage Control Measures shall not be shown. |
| ___ yes ___ no | 3. Items 1, 2, and 4 through 18 from the Initial GESC Plan (Section III of this checklist). |
| ___ yes ___ no | 4. Proposed topography at one or two foot contour intervals, showing elevations, dimensions, locations, and slope of all proposed grading with flow arrows. |
| ___ yes ___ no | 5. Outlines of cut and fill areas. |
| ___ yes ___ no | 6. Location of all interim erosion and sediment controls designed in conjunction with the proposed site topography, but also considering the controls designed in the Initial GESC Plan. |
| ___ yes ___ no | 7. Locations of all buildings, floodplain delineation, drainage features and facilities, paved areas, retaining walls, cribbing, water quality facilities, or other permanent features to be constructed in connection with, or as a part of, the proposed work, per approved plat or land use plan (e.g. Final Development Plan), or other improvement plan. |
| ___ yes ___ no | 8. The following notes: <ul style="list-style-type: none"> • APPROPRIATE CONTROL MEASURES MUST BE IMPLEMENTED PRIOR TO THE START OF ACTIVITY, MUST CONTROL POTENTIAL POLLUTANTS DURING EACH PHASE OF CONSTRUCTION, AND MUST BE CONTINUED THROUGH FINAL STABILIZATION. APPROPRIATE STRUCTURAL CONTROL MEASURES MUST BE MAINTAINED IN OPERATIONAL CONDITION. • SEE SEMSWA STANDARD NOTES AND DETAILS (SHEET 1 OF 4) FOR LEGEND OF NAMES AND SYMBOLS. • SHADED CONTROL MEASURES WERE INSTALLED IN THE INITIAL STAGE AND SHALL BE LEFT IN PLACE IN THE INTERIM STAGE UNLESS OTHERWISE NOTED. • CONTROL MEASURES, INCLUDING SEEDING AND MULCHING OF DISTURBED AREAS, MUST BE COMPLETED WITHIN 14 DAYS IF THE AREAS WILL REMAIN UNDISTURBED FOR A PERIOD GREATER THAN 30 DAYS. • ALL PROPOSED SLOPES ON THIS PLAN HAVE A MAXIMUM SLOPE OF 4:1. ANY SLOPES BETWEEN 3:1 AND 4:1 WILL REQUIRE THE USE OF EROSION CONTROL BLANKETS OR FLEXIBLE GROWTH MEDIUM, AS APPROVED BY SEMSWA INSPECTOR. • SEE CONSTRUCTION PLANS FOR DETAILS OF PERMANENT DRAINAGE FACILITIES SUCH AS DETENTION FACILITIES, WATER QUALITY FACILITIES, CULVERTS, STORM DRAINS, AND INLET AND OUTLET PROTECTION. • IF SITE RUNOFF ENTERS THE POST-CONSTRUCTION PERMANENT CONTROL MEASURE(S), SEDIMENT CONTAMINATION OF THE MATERIALS MAY RESULT IN THE POST-CONSTRUCTION PERMANENT CONTROL MEASURE(S) HAVING TO BE RECONSTRUCTED IN ITS ENTIRETY. (WHERE APPLICABLE) REMOVAL OF SEDIMENT BASIN ON SITE SHALL ONLY OCCUR AFTER ALL AREAS TRIBUTARY TO THE SEDIMENT BASIN HAVE BEEN STABILIZED. REMOVAL MUST BE APPROVED BY SEMSWA. |

- ___ yes ___ no 9. Summary of cut and fill volumes. If export occurs, note location where export will likely be transported to.
- ___ yes ___ no 10. Other information or data as may be required by SEMSWA.

V. FINAL GESC DRAWING

This plan sheet shows controls for final completion of the site. The Final GESC Plan shall include all information shown on the Initial and Interim Plans, as noted below. At a minimum, this plan sheet shall contain the following information:

- ___ yes ___ no 1. Existing topography in areas of proposed contours need not be shown.
- ___ yes ___ no 2. Existing Initial and Interim Control Measures shall be shown, **(screened)**.
Dimension information shall not be shown.
- ___ yes ___ no 3. Directional flow arrows on all drainage features.
- ___ yes ___ no 4. Show Floodplain delineation.
- ___ yes ___ no 4. Any Initial or Interim Control Measures that are to be removed and any resulting disturbed areas to be stabilized.
- ___ yes ___ no 5. Location of all Final erosion and sediment Control Measures (including seeding and mulching of any areas not stabilized in the Interim Plan), permanent landscaping, and any Control Measures necessary to minimize the movement of sediment off site until permanent vegetation can be established.
- ___ yes ___ no 6. Show area of buildings, pavement, sod and permanent landscaping (define types) per approved plat or land use plan (e.g. Final Development Plan), or other improvement plan.
- ___ yes ___ no 7. Show seeding and mulching(SM) (or erosion control blanket where applicable) everywhere, except buildings, pavement areas, and permanent landscaped areas.
- ___ yes ___ no 8. Show other Control Measures considered by the Design Engineer to be appropriate.
- ___ yes ___ no 9. Show the Control Measures to be removed at the end of construction, for example:
- Indicate dewatering (DW) to be removed.
 - Indicate temporary stream crossing (TSC) to be removed.
 - Indicate stabilized staging area (SSA) to be removed.
 - Indicate vehicle tracking control (VTC) to be removed.

___ yes ___ no

10. The following notes:

- APPROPRIATE CONTROL MEASURES MUST BE IMPLEMENTED PRIOR TO THE START OF ACTIVITY, MUST CONTROL POTENTIAL POLLUTANTS DURING EACH PHASE OF CONSTRUCTION, AND MUST BE CONTINUED THROUGH FINAL STABILIZATION. APPROPRIATE STRUCTURAL CONTROL MEASURES MUST BE MAINTAINED IN OPERATIONAL CONDITION.
- SEE SEMSWA STANDARD NOTES AND DETAILS (SHEET 1 OF 4) FOR LEGEND OF CONTROL MEASURE NAMES AND SYMBOLS.
- SHADED CONTROL MEASURES WERE INSTALLED IN INITIAL OR INTERIM GESC PLAN AND, UNLESS OTHERWISE INDICATED, SHALL BE LEFT IN PLACE UNTIL APPROVED BY SEMSWA.
- ALL INTERIM CONTROL MEASURES, INCLUDING SEEDING AND MULCHING OF DISTURBED AREAS, MUST BE COMPLETED WITHIN 14 DAYS IF THE AREAS WILL REMAIN UNDISTURBED FOR A PERIOD GREATER THAN 30 DAYS.
- ALL PROPOSED SLOPES ON THIS PLAN HAVE A MAXIMUM SLOPE OF 4:1. ANY SLOPES BETWEEN 3:1 AND 4:1 WILL REQUIRE THE USE OF EROSION CONTROL BLANKETS OR FLEXIBLE GROWTH MEDIUM, AS APPROVED BY SEMSWA INSPECTOR.
- SEE CONSTRUCTION PLANS FOR DETAILS OF PERMANENT DRAINAGE FACILITIES SUCH AS DETENTION FACILITIES, WATER QUALITY FACILITIES, CULVERTS, STORM DRAINS, AND OUTLET PROTECTION.
- ACCEPTANCE OF THE POST-CONSTRUCTION PERMANENT CONTROL MEASURES WILL NOT OCCUR UNTIL ALL TRIBUTARY AREAS TO THE PERMANENT CONTROL MEASURES ARE FINAL STABILIZED.

___ yes ___ no

11. Other information or data as may be required by SEMSWA.

VI. GESC PLAN STANDARD NOTES AND DETAILS

A copy of the GESC Drawing Standard Notes and Details (included in Appendix F) shall be bound into each set of GESC Documents.

VII. GESC DRAWING AND REPORT CHECKLIST

A copy of this GESC Drawing and Report Checklist must be completely filled out, signed by the designer, and submitted with the GESC Report.

B. REPORT REQUIREMENTS FOR STANDARD GESC PERMITS

The report shall contain the following information:

<input type="checkbox"/> yes <input type="checkbox"/> no	1.	<u>Name, address (include zip code), telephone number of the applicant, and the SEMSWA Case Number</u> - The name, address, SEMSWA Case Number, and telephone number of the Professional Engineer preparing (or supervising the preparation of) the GESC Plan shall also be included, if different from the applicant.
<input type="checkbox"/> yes <input type="checkbox"/> no	2.	<u>Project description</u> - A brief description of the nature and purpose of the land-disturbing activity, the total area of the site, the area of disturbance involved, and project location including township, range, section and quarter-section, or the latitude and longitude, of the approximate center of the project.
<input type="checkbox"/> yes <input type="checkbox"/> no	3.	<u>Existing site conditions</u> – A description of the existing topography, vegetation, and drainage; a description of any wetlands on the site; and any other unique features of the property. Pictures of existing vegetation are encouraged.
<input type="checkbox"/> yes <input type="checkbox"/> no	4.	<u>Adjacent areas</u> - A description of neighboring areas such as streams, lakes, Floodplain, residential areas, roads, etc., which might be affected by the land disturbance.
<input type="checkbox"/> yes <input type="checkbox"/> no	5.	<u>Soils</u> – A brief description of the soils on the site including information on soil type and names, mapping unit, erodibility, permeability, hydrologic soil group, depth, texture, and soil structure (This information may be obtained from the soil report for the site, from adjacent sites if acceptable to SEMSWA, or the applicable Soil Survey prepared by the Natural Resources Conservation Service (NRCS)).
<input type="checkbox"/> yes <input type="checkbox"/> no	6.	<u>Areas and Volumes</u> - An estimate of the quantity (in cubic yards) of excavation and fill involved (attempting to achieve an earthwork balance), haul road information, and the surface area (in acres) of the proposed disturbance.


___ yes ___ no	7.	<p><u>Erosion and sediment control measures</u> - A description of the methods presented in the GESC Manual that will be used to control erosion and sediment on the site. These descriptions should describe how Control Measures would address specific site conditions and clarify anything that cannot be clearly shown on the Plans. Control Measures must be selected, designed, installed, implemented, and maintained to provide control of all potential pollutants, such as but not limited to sediment, construction site waste, trash, discarded building materials, concrete truck washout, chemicals, sanitary waste, and contaminated soils in discharges to the MS4. At a minimum pollutant sources associated with the following activities (if part of the applicable construction activity) must be addressed:</p> <ul style="list-style-type: none"> • Land disturbance and storage of soils • Vehicle tracking • Loading and unloading operations • Outdoor storage of construction site materials, building materials, fertilizers, and chemicals • Bulk storage of materials • Vehicle and equipment maintenance and fueling • Significant dust or particulate generating processes • Routine maintenance activities involving fertilizers, pesticides, detergents, fuels, solvents, and oils • Concrete truck/equipment washing, including the concrete truck chute and associated fixtures and equipment • Dedicated asphalt and concrete batch plants. • Other areas or operations where spills can occur. • Other non-stormwater discharges including construction dewatering not covered under the Construction Dewatering Discharges general permit and wash water that may contribute pollutants to the MS4.
___ yes ___ no	8.	<u>Permanent stabilization</u> - A brief description, including applicable specifications, of how the site will be stabilized after construction is completed.
___ yes ___ no	9.	<u>Stormwater management considerations</u> – Explain how stormwater runoff from and through the site will be handled during construction.
___ yes ___ no	10.	<u>Maintenance</u> – Any special maintenance requirements over and above what is identified in the standard notes and details.
___ yes ___ no	11.	<u>Calculations</u> – Any calculations made for the design of such items as sediment basins, diversion ditches, and/or erosion control matting selection.
___ yes ___ no	12.	<u>Other information or data</u> - As may be required by SEMSWA.
___ yes ___ no	13.	<p>The following note above Certification Statements on Signature Page –</p> <p>“This <i>Grading, Erosion and Sediment Control (GESC)</i> document has been placed in the SEMSWA file for this project and appears to fulfill the latest version of the <i>SEMSWA Grading, Erosion and Sediment Control Manual</i>. Additional grading, erosion and sediment control measures may be required of the owner or his/her agents, due to unforeseen erosion problems or if the submitted plan does not function as intended. The requirements of this GESC document shall run with the land and be the obligation of the land owner, or his/her designated representative(s) until such time as the plan is properly completed, modified or voided.”</p>

<p>___ yes ___ no</p>	<p>14.</p>	<p><u>Signature Page</u> – For landowner/authorized agent acknowledging the review and acceptance of responsibility, and for the professional engineer acknowledging responsibility for the preparation of the GESC plan, the Certification Statements are as follows:</p> <p>“I hereby certify that the Grading, Erosion, and Sediment Control measures for (Name of Subdivision/Development/address) shall be constructed according to the design presented in this document. I understand that additional erosion control, sediment control and water quality enhancing measures may be required of the owner and his or her agents due to unforeseen pollutant discharges or if the submitted plan does not function as intended. The requirements of the plan shall be the obligation of the land owner and/or his successors or heirs; until such time as the plan is properly completed, modified or voided.”</p>
<p>___ yes ___ no</p>	<p>15.</p>	<p><u>Engineer's Cost Estimate for installation and maintenance of controls</u> – An Engineer's Cost Estimate, as a standalone document for erosion and sediment control, including anticipated maintenance during the construction phase, shall be submitted with the GESC documents. This will be reviewed by SEMSWA staff and used as a basis for collateral. A copy of a spreadsheet to be used for preparing the Engineer's Cost Estimate for erosion and sediment control are included in Appendix C of the GESC Manual. An electronic copy of the spreadsheet is available from the SEMSWA website.</p> <p><u>Unit costs used to develop probable erosion and sediment control costs shall be those shown in the spreadsheet and shall not be modified.</u></p>

GRADING, EROSION, AND SEDIMENT CONTROL (GESC) GENERAL NOTES

- THE SOUTHEAST METRO STORMWATER AUTHORITY (SEMSWA) LAND DEVELOPMENT REVIEW MANAGER SIGNATURE AFFIXED TO THIS DOCUMENT INDICATES SEMSWA HAS REVIEWED THE DOCUMENT AND FOUND IT IN GENERAL COMPLIANCE WITH CENTENNIAL'S LAND DEVELOPMENT CODE AND/OR THE GRADING, EROSION AND SEDIMENT CONTROL (GESC) MANUAL. THE LAND DEVELOPMENT REVIEW MANAGER THROUGH ACCEPTANCE OF THIS DOCUMENT, ASSUMES NO RESPONSIBILITY (OTHER THAN AS STATED ABOVE) FOR THE COMPLETENESS AND/OR ACCURACY OF THESE DOCUMENTS.
- THE ADEQUACY OF THIS GESC PLAN LIES WITH THE ORIGINAL DESIGN ENGINEER. CHANGES TO DESIGN INTENT THAT MEET THE DEFINITION OF MAJOR MODIFICATIONS MUST GO THROUGH ORIGINAL DESIGN ENGINEER.
- THE GESC PLAN SHALL BE CONSIDERED VALID FOR TWO (2) YEARS FROM THE DATE OF ACCEPTANCE BY SEMSWA. AFTER WHICH TIME THE PLAN SHALL BE VOID AND WILL BE SUBJECT TO RE-REVIEW AND RE-ACCEPTANCE BY SEMSWA. PLANS MUST CONFORM TO CURRENT REQUIREMENTS.
- ALL MATERIALS AND WORKMANSHIP SHALL BE SUBJECT TO INSPECTION BY SEMSWA'S INSPECTION DIVISION. SEMSWA RESERVES THE RIGHT TO ACCEPT OR REJECT ANY MATERIALS AND WORKMANSHIP THAT DOES NOT CONFORM TO THE GESC MANUAL, GESC PLAN OR GESC PERMIT.
- THE PLACEMENT OF EROSION AND SEDIMENT CONTROL MEASURES SHALL BE IN ACCORDANCE WITH THE ACCEPTED GESC PLAN AND THE SEMSWA GESC MANUAL.
- ANY VARIATION IN MATERIAL, TYPE OR LOCATION OF EROSION AND SEDIMENT CONTROL MEASURES FROM THE SEMSWA - ACCEPTED GESC PLAN WILL REQUIRE APPROVAL FROM AN ACCOUNTABLE REPRESENTATIVE OF SEMSWA.
- UPON RECEIVING THE APPROVED, SIGNED AND STAMPED GESC PLANS AND REPORT, THE CONTRACTOR MAY INSTALL THE NON-EARTH DISTURBING INITIAL-STAGE EROSION AND SEDIMENT CONTROL MEASURES INDICATED ON THE ACCEPTED GESC PLAN.
- AFTER INSTALLATION OF THE INITIAL-STAGE EROSION AND SEDIMENT CONTROL MEASURES, THE PERMITTEE SHALL CALL THE INSPECTION DIVISION TO SCHEDULE A PRECONSTRUCTION MEETING AT THE PROJECT SITE. THE REQUEST SHALL BE MADE NO LESS THAN 24 HOURS PRIOR TO THE REQUESTED MEETING TIME. NO CONSTRUCTION ACTIVITIES SHALL BE PLANNED WITHIN 24 HOURS AFTER THE PRECONSTRUCTION MEETING.
- IN ADDITION TO THE SEMSWA INSPECTOR AND GESC MANAGER, THE FOLLOWING REPRESENTATIVES SHOULD ATTEND: GENERAL CONTRACTOR, OWNER, OR OWNER'S REPRESENTATIVE AND GRADING SUBCONTRACTOR. IF ANY OF THE REQUIRED PARTICIPANTS FAIL TO ATTEND THE PRECONSTRUCTION MEETING, OR IF THE INSTALLATION OF THE INITIAL CONTROL MEASURES ARE NOT APPROVED BY THE SEMSWA INSPECTOR, THE APPLICANT WILL HAVE TO PAY A REINSPECTION FEE, ADDRESS ANY PROBLEMS WITH CONSTRUCTION, EVALUATION, AND CALL TO RESCHEDULE THE MEETING, WITH A CORRESPONDING DELAY IN THE START OF CONSTRUCTION.
- CONSTRUCTION SHALL NOT BEGIN UNTIL THE SEMSWA INSPECTOR APPROVES THE INSTALLATION OF THE INITIAL CONTROL MEASURES AND THE APPROVED GESC PERMIT HAS BEEN ISSUED BY SEMSWA AND IS IN-HAND ON THE SITE. THE COMPLETED PERMIT WILL GENERALLY BE FIELD ISSUED OR ISSUED VIA EMAIL AFTER THE INSTALLATION OF THE INITIAL CONTROL MEASURES ARE APPROVED.
- THE GESC MANAGER SHALL STRICTLY ADHERE TO THE SEMSWA APPROVED LIMITS OF CONSTRUCTION AT ALL TIMES. THE SEMSWA INSPECTION DIVISION MUST APPROVE ANY CHANGES TO THE LIMITS OF CONSTRUCTION AND, AT THE DISCRETION OF THE INSPECTION DIVISION, ADDITIONAL EROSION/SEDIMENT CONTROLS MAY BE REQUIRED IN ANY ADDITIONAL AREAS OF CONSTRUCTION/ DISTURBANCE ARE NEEDED.
- THE MAXIMUM AREA OF CONSTRUCTION SHALL BE LIMITED TO 40 ACRES (70 ACRES IF APPROVED FOR SOIL MITIGATION OPERATIONS) TO REDUCE THE AMOUNT OF LAND DISTURBED AT ANY ONE TIME. LARGER SITES SHALL BE DIVIDED INTO PHASES THAT ARE EACH 40 (OR 70) ACRES OR LESS IN SIZE. THESE PROJECTS SHALL CONTROL GRADING ACTIVITIES IN ACCORDANCE WITH THE ACCEPTED GESC PLAN. CONTROL MEASURE INSTALLATION AND APPROVAL BY SEMSWA AT THE START AND COMPLETION OF EACH PHASE SHALL BE CONDUCTED IN ACCORDANCE WITH THE PROCEDURES OUTLINED IN THE GESC MANUAL.
- NATURAL VEGETATION SHALL BE RETAINED AND PROTECTED WHEREVER POSSIBLE. EXPOSURE OF SOIL TO EROSION BY REMOVAL OR DISTURBANCE OF VEGETATION SHALL BE LIMITED TO THE AREA REQUIRED FOR IMMEDIATE CONSTRUCTION OPERATIONS.
- THE GESC PERMIT SHALL BE VALID FOR A PERIOD OF TWO (2) YEARS.
- A COPY OF THE GESC PERMIT AND APPROVED GESC PLANS SHALL BE ON SITE OR MADE AVAILABLE UPON REQUEST.
- THE GESC MANAGER SHALL BE RESPONSIBLE PARTY FOR ENSURING THAT THE SITE REMAINS IN COMPLIANCE WITH THE GESC PERMIT AND SHALL BE THE PERMITTEE'S CONTACT PERSON WITH SEMSWA FOR ALL MATTERS PERTAINING TO THE GESC PERMIT. THE GESC MANAGER SHALL BE ON THE SITE AS NECESSARY TO ENSURE THE GESC REQUIREMENTS ARE BEING IMPLEMENTED, AND (ALONG WITH THE SEMSWA INSPECTOR) SHALL PROVIDE SEMSWA WITH A 24-HOUR EMERGENCY CONTACT NUMBER. IN THE EVENT THAT THE CONTRACTOR'S GESC MANAGER IS NOT ON SITE AND CANNOT BE REACHED DURING A 24-HOUR PERIOD, THE GESC MANAGER SHALL BE CONTACTED. IF NEITHER THE GESC MANAGER NOR ALTERNATE GESC MANAGER CAN BE CONTACTED DURING ANY VIOLATION, WITHIN 24 HOURS, VIOLATION MAY BE ISSUED TO THE PERMITTEE(S).
- ALL CONSTRUCTION TRAFFIC MUST EXIT THE SITE THROUGH THE SEMSWA-APPROVED ACCESS POINT. A VEHICLE TRACKING CONTROL PAD IS REQUIRED ON ALL EXIT POINTS ON THE SITE. ADDITIONAL STABILIZED CONSTRUCTION ENTRANCES MAY BE ADDED WITH AUTHORIZATION FROM THE SEMSWA INSPECTION DIVISION.
- THE GESC MANAGER IS RESPONSIBLE FOR CLEANUP OF SEDIMENT OR CONSTRUCTION DEBRIS TRACKED OUT TO ADJACENT PAVED AREAS. PAVED AREAS INCLUDING STREETS ARE TO BE KEPT CLEAN THROUGHOUT BUILD-OUT AND SHALL BE CLEANED, WITH A STREET SWEEPER OR SIMILAR DEVICE, AT FIRST NOTICE OF ACCIDENTAL TRACKING OF AT THE DISCRETION OF THE SEMSWA GESC INSPECTOR. STREET WASHING IS NOT ALLOWED. SEMSWA RESERVES THE RIGHT TO REQUIRE ADDITIONAL MEASURES TO ENSURE AREA STREETS ARE KEPT FREE OF SEDIMENT AND/OR CONSTRUCTION DEBRIS.
- APPROVED EROSION AND SEDIMENT CONTROL MEASURES SHALL BE MAINTAINED AND KEPT IN GOOD REPAIR FOR THE DURATION OF THIS PROJECT. AT A MINIMUM, THE GESC MANAGER SHALL INSPECT ALL CONTROL MEASURES IN ACCORDANCE WITH THE GESC MANUAL AND GESC MANUAL. ALL NECESSARY MAINTENANCE AND REPAIR ACTIVITIES SHALL BE COMPLETED WITHIN 48 HOURS. ACCUMULATED SEDIMENT AND CONSTRUCTION DEBRIS SHALL BE REMOVED AND PROPERLY DISPOSED.
- STRAW BALES ARE NOT A SEMSWA GESC-ACCEPTED SEDIMENT CONTROL MEASURE.
- TOPSOIL SHALL BE STRIPPED AND STOCKPILED IN THE LOCATION SHOWN ON THE ACCEPTED GESC PLAN. THE TOPSOIL STOCKPILES(S) SHALL FOLLOW ALL STOCKPILING CRITERIA DESCRIBED IN THE GESC MANUAL. TOPSOIL SHALL BE REPLACED AT A MINIMUM DEPTH OF 6 INCHES. IF A MINIMUM DEPTH OF 6 INCHES CAN NOT BE OBTAINED, ADDITIONAL TOPSOIL AND/OR APPROVED SOIL AMENDMENTS WILL BE REQUIRED TO BE PLACED PRIOR TO SEEDING AND MULCHING.
- THE ACCEPTED GESC PLAN MAY REQUIRE CHANGES OR ALTERATIONS AFTER APPROVAL TO MEET CHANGING SITE OR PROJECT CONDITIONS OR TO ADDRESS INEFFICIENCIES IN DESIGN OR INSTALLATION. THE GESC MANAGER SHALL OBTAIN PRIOR APPROVAL FOR MAJOR MODIFICATIONS FROM THE DESIGN ENGINEER AND SEMSWA FOR ANY PROPOSED CHANGES.
- LINING OF TEMPORARY SWALES AND DITCHES SHALL BE IN ACCORDANCE WITH THE GESC MANUAL.
- ANY SETTLEMENT OR SOIL ACCUMULATIONS BEYOND THE LIMITS OF CONSTRUCTION DUE TO GRADING OR EROSION SHALL BE REPAIRED IMMEDIATELY BY THE GESC MANAGER. THE GESC MANAGER SHALL BE HELD RESPONSIBLE FOR OBTAINING ACCESS RIGHTS TO ADJACENT PROPERTY, IF NEEDED, AND REMEDIATING ANY ADVERSE IMPACTS TO ADJACENT WATERWAYS, WETLANDS, PROPERTIES, ETC. RESULTING FROM WORK DONE AS PART OF THIS PROJECT.
- A WATER SOURCE SHALL BE AVAILABLE ON SITE DURING EARTHWORK OPERATIONS AND UTILIZED AS REQUIRED TO MINIMIZE DUST FROM EARTHWORK EQUIPMENT AND WIND.
- SOILS THAT WILL BE STOCKPILED FOR MORE THAN THIRTY (30) DAYS SHALL BE SEEDED AND MULCHED WITHIN FOURTEEN (14) DAYS OF STOCKPILE CONSTRUCTION. NO STOCKPILES SHALL BE PLACED WITHIN ONE HUNDRED (100) FEET OF A DRAINAGE WAY UNLESS APPROVED BY SEMSWA.
- ALL CHEMICAL OR HAZARDOUS MATERIAL SPILLS WHICH MAY ENTER WATERS OF THE STATE OF COLORADO, WHICH INCLUDE BUT ARE NOT LIMITED TO, SURFACE WATER, GROUND WATER AND DRY GULLIES OR STORM SEWER LEADING TO SURFACE WATER, SHALL BE IMMEDIATELY REPORTED TO THE COPE (PDS 25-8-60), AND SEMSWA. RELEASES OF PETROLEUM PRODUCTS AND CERTAIN HAZARDOUS SUBSTANCES LISTED UNDER THE FEDERAL CLEAN WATER ACT (40 CFR PART 118) MUST BE REPORTED TO THE NATIONAL RESPONSE CENTER AS WELL AS THE COPE. CONTACT INFORMATION FOR COPE, SEMSWA AND THE NATIONAL RESPONSE CENTER CAN BE FOUND IN APPENDIX A. LIFE THAT POSE AN IMMEDIATE RISK TO HUMAN HEALTH SHALL BE REPORTED TO 911. FAILURE TO REPORT AND CLEAN UP ANY SPILL SHALL RESULT IN ISSUANCE OF A STOP WORK ORDER. TO REPORT SPILLS TO SEMSWA CALL 303-688-8844.
- ALL WORK ON SITE SHALL STAY A MINIMUM OF ONE HUNDRED (100) FEET AWAY FROM ANY DRAINAGE WAY, WETLAND, ETC. UNLESS OTHERWISE NOTED ON AN ACCEPTED SEMSWA GESC PLAN.
- THE USE OF REBAR, STEEL STAKES OR STEEL FENCE POSTS FOR STAKING OR SUPPORT OF ANY EROSION OR SEDIMENT CONTROL MEASURE IS PROHIBITED (EXCEPT STEEL TEE-POSTS FOR USE IN SUPPORTING CONSTRUCTION FENCE).
- THE CLEANING OF CONCRETE DELIVERY TRUCK CHUTES IS RESTRICTED TO APPROVED CONCRETE WASH OUT LOCATIONS ON THE JOB SITE. THE DISCHARGE OF WATER CONTAINING WASTE CONCRETE TO THE STORM SEWER SYSTEM IS PROHIBITED. ALL CONCRETE WASTE SHALL BE PROPERLY CLEANED UP AND DISPOSED AT AN APPROPRIATE LOCATION.
- ALL PERMANENT INSTALLATIONS OF PIPES FOR STORM SEWERS, SLOPE DRAINS, AND CULVERTS, TOGETHER WITH RIPRAP APRONS OR OTHER INLET AND OUTLET PROTECTION, REQUIRE INSPECTION BY SEMSWA (SEPARATE FROM GESC INSPECTIONS).
- ALL DISTURBED AREAS SHALL BE STABILIZED IN ACCORDANCE WITH THE GESC MANUAL WITHIN 14 DAYS OF SUBSTANTIAL COMPLETION OF GRADING, INCLUDING AREAS TO REMAIN DOMINANT FOR LONGER THAN 30 DAYS, WHOEVER IS LESS, THIS MAY REQUIRE MULTIPLE MOBILIZATIONS FOR SEEDING AND MULCHING.
- HYDRAULIC SEEDING IS NOT AN ACCEPTABLE METHOD OF SEEDING WITHIN THE SEMSWA SERVICE AREA.
- HYDRO-MULCH MAY BE USED FOR LIMITED APPLICATIONS AS APPROVED BY SEMSWA.
- UTILITY LINE INSTALLATION SHALL COMPLY WITH THE FOLLOWING CRITERIA:
 - ALL UTILITY WORK WITHIN A CITY OF CENTENNIAL RIGHT-OF-WAY SHALL BE REQUIRED TO OBTAIN A CITY OF CENTENNIAL RIGHT-OF-WAY USE AND CONSTRUCTION PERMIT IN ACCORDANCE WITH THE APPROPRIATE STANDARDS.
 - PROVIDE ADEQUATE EROSION AND SEDIMENT CONTROLS.
 - AT THE END OF A WORK DAY, NO TRENCH SHALL BE LEFT OPEN AND BACKFILL MUST BE COMPLETED TO GRADE.
 - WHERE CONSISTENT WITH SAFETY AND SPACE CONSIDERATIONS, EXCAVATED MATERIAL IS TO BE PLACED ON THE UPDRAIN SIDE OF TRENCHES.
 - AT NO TIME SHALL EXCAVATED MATERIAL BE PLACED ON THE STREET.
 - TRENCH Dewatering DEVICES MUST DISCHARGE IN A MANNER THAT WILL NOT EFFECT STREAMS, WETLANDS, DRAINAGE SYSTEMS, OR OFF-SITE PROPERTY. DISCHARGE FROM TRENCH SHALL BE FREE OF ANY SEDIMENT. A RIPRAP PAD SHALL BE INSTALLED AT THE DISCHARGE END OF THE HOSE TO PREVENT EROSION.
 - STORM SEWER INLET PROTECTION SHALL BE PROVIDED WHENEVER SOIL EROSION FROM THE EXCAVATED AREA HAS POTENTIAL OF ENTERING THE STORM DRAINAGE SYSTEM.
 - ALL DISTURBED AREAS SHALL BE DRILL SEEDED AND CRIMP MULCHED WITHIN FIVE DAYS AFTER UTILITY INSTALLATION IS COMPLETED.
 - ALL OTHER APPLICABLE CRITERIA AS OUTLINED IN THE GESC MANUAL.
- ALL SINGLE-FAMILY RESIDENTIAL DEVELOPMENT PROJECTS SHALL COMPLY WITH THE GESC CRITERIA AS PRESENTED IN THE GESC MANUAL.
- NO RECYCLED ASPHALT SHALL BE USED AS A CONTROL MEASURE. RECYCLED CONCRETE MUST BE APPROVED BY SEMSWA.
- SEMSWA MAY ALLOW THE INSTALLATION OF ALTERNATIVE CONTROL MEASURES OTHER THAN THE GESC PLAN STANDARD NOTES AND DETAILS. IF ALTERNATIVE EROSION AND SEDIMENT CONTROL MEASURES WILL BE USED, OUT SHEETS MUST BE SUBMITTED TO THE SEMSWA INSPECTOR.
- IF YOU ARE EXPORTING EXCESS DIRT WITHIN THE SEMSWA SERVICE AREA YOU WILL BE REQUIRED TO OBTAIN A GESC PERMIT FOR THE SECONDARY SITE.

DETAIL NO.	SHEET NO.	LEGEND
1	1	CBC CUT BACK CURB
2	1	CD CHECK DAM
3	1	CWA CONCRETE WASHOUT AREA
4	1	CF CONSTRUCTION FENCE
5	1	CM CONSTRUCTION MARKERS
6	1	CS CURB SOCK
7	1	DW DEWATERING
8	2	DD DIVERSION DITCH
9	2	ECB EROSION CONTROL BLANKET
10	2	GMS GROUT MIXING STATION
11	2	IP INLET PROTECTION
12	2	RCD REINFORCED CHECK DAM
13	2	RRB REINFORCED CURB BERM
14	2	RRR RRB FOR CULVERT PROTECTION
15	2	SB SEDIMENT BASIN
16	3	SCL SEDIMENT CONTROL LOG
17	3	ST SEDIMENT TRAP
18	3	SM SEEDING AND MULCHING
19	3	SF SILT FENCE
20	3	SID SLOPE INTERCEPT DITCH
21	3	SSA STABILIZED STAGING AREA
22	4	SR SURFACE ROUGHENING
23	4	TSR TEMPORARY SLOPE DRAIN
24	4	TSC TEMPORARY STREAM CROSSING
25	4	VTC VEHICLE TRACKING CONTROL
26	4	WW VTC WITH WHEEL WASH
		LOC ROCK AND RIPRAP GRADATIONS
		*EG MAY MEET MAJOR MODIFICATION REQUIREMENTS



- CONCRETE WASHOUT AREA INSTALLATION NOTES**
- SEE PLAN VIEW FOR LOCATIONS OF CONCRETE WASHOUT AREA.
 - THE CONCRETE WASHOUT AREA SHALL BE INSTALLED PRIOR TO ANY CONCRETE PLACEMENT ON SITE.
 - VEHICLE TRACKING CONTROL (VTC) (DETAIL 24) IS REQUIRED AT THE ACCESS POINT. THE VTC CAN BE REMOVED AT THE DISCRETION OF THE SEMSWA INSPECTOR.
 - SIGNS SHALL BE PLACED AT THE WASHOUT AREA, AND MAY BE ELSEWHERE AS NECESSARY TO CLEARLY INDICATE THE LOCATION OF THE CONCRETE WASHOUT AREA TO OPERATORS OF CONCRETE TRUCKS AND PUMP TRUCKS.
 - EXCAVATED MATERIAL MAY BE UTILIZED IN PERIMETER BERM CONSTRUCTION.
 - CONCRETE WASHOUT MUST BE LINED IN AREAS WITH HIGH GROUNDWATER. LINERS MUST BE 30 MIL OR GREATER.
- CONCRETE WASHOUT AREA MAINTENANCE NOTES**
- THE CONCRETE WASHOUT AREA SHALL BE REPAIRED AND ENLARGED OR CLEANED OUT AS NECESSARY TO MAINTAIN CAPACITY FOR WASTED CONCRETE.
 - AS NEEDED DURING CONSTRUCTION, AND AT THE END OF CONSTRUCTION, ALL CONCRETE SHALL BE REMOVED FROM THE SITE AND DISPOSED OF AT AN APPROVED WASTE SITE.
 - WHEN THE CONCRETE WASHOUT AREA IS REMOVED, THE DISTURBED AREA SHALL BE DRILL SEEDED AND CRIMP MULCHED OR OTHERWISE STABILIZED IN A MANNER APPROVED BY SEMSWA.
 - INSPECT WEEKLY, DURING AND AFTER ANY STORM EVENT.

GENERAL NOTE:
USE OF PROPRIETARY CONCRETE WASHOUT SYSTEM MAY BE CONSIDERED IF APPROVED BY SEMSWA INSPECTOR PRIOR TO USE.




ROCK AND RIPRAP GRADATIONS

D50 MEDIAN STONE SIZE (INCHES)	% OF MATERIAL SMALLER THAN TYPICAL SIZE	TYPICAL STONE EQUIVALENT DIAMETER (INCHES)	TYPICAL STONE WEIGHT (POUNDS)
6	70 - 100 50 - 70 35 - 50 2 - 10	12 9 6 2	85 35 10 0.4
9	70 - 100 50 - 70 35 - 50 2 - 10	15 12 9 3	160 85 35 1.3
12	70 - 100 50 - 70 35 - 50 2 - 10	21 18 12 4	440 275 120 5
18	100 50 - 70 35 - 50 2 - 10	30 24 18 6	1280 650 275 10
24	100 50 - 70 35 - 50 2 - 10	42 33 24 9	3500 1700 650 35

TABLE 2. RIPRAP BEDDING

SIEVE SIZE	MASS PERCENT PASSING SQUARE MESH SIEVES
	CLASS A
3"	100
1 1/2"	20 - 90
NO. 4	0 - 20
NO. 200	0 - 3

MATCHES SPECIFICATIONS FOR COPT CLASS A FILTER MATERIAL AND LIFTED TYPE 1 BEDDING. ALL ROCK SHALL BE FRACTURED FACE. ALL SIDES.



LENGTH (L) OF DISTURBED AREA PERPENDICULAR TO CURB	AREA PER FT. OF DISTURBED LENGTH	DEPTH OF CURB (D)	REQUIRED STORAGE VOLUME	REQUIRED MIN. WIDTH (W) OF CURB OUT
(FT)	(FT ²)	(IN)	(FT ³ /ACRE) (FT ³ /FT ²)	(FT)
20	20	6	0.50 1800	0.0413 1.7
30	30	6	0.50 1800	0.0413 2.5
40	40	6	0.50 1800	0.0413 2.3
50	50	6	0.50 1800	0.0413 4.1
60	60	6	0.50 1800	0.0413 5.0
70	70	6	0.50 1800	0.0413 5.9
80	80	6	0.50 1800	0.0413 6.6
90	90	6	0.50 1800	0.0413 7.4
100	100	6	0.50 1800	0.0413 8.3

1. FROM DOUGLAS COUNTY, GRADING, EROSION, AND SEDIMENT CONTROL MANUAL, SEDIMENT TRAP STORAGE VOLUME REQUIREMENT.

DESCRIPTION AND PURPOSE

- A TEMPORARY SEDIMENT BARRIER AND TRAP FORMED BY EXCAVATION BEHIND CURB OR SIDEWALK TO RETAIN SEDIMENT ON SITE DURING CONSTRUCTION.

SUITABLE APPLICATIONS


- DURING LAND DEVELOPMENT AFTER PAVING OR DURING VERTICAL CONSTRUCTION TO ENSURE THE ADEQUACY AND FUNCTIONALITY OF ISLAND.
- USE IN TREE LANES OR IN LANDSCAPE.
- USE SURFACE ROUGHENING ON UPGRADIENT SLOPES IF DURING LAND DEVELOPMENT.

LIMITATIONS

- NOT FOR USE EXCEEDING 3H:1V SLOPES.
- NOT FOR USE FOR CONCENTRATED FLOW AREAS.
- PROLONGED STANDING WATER MAY AFFECT SUB-BASE OF PAVING AND COULD CAUSE SOIL TO SETTLE AND POTENTIALLY DAMAGE CONCRETE.

INSPECTION AND MAINTENANCE




- THE GESC MANAGER SHALL INSPECT AS NECESSARY TO ENSURE THE ADEQUACY AND FUNCTIONALITY OF THE CONTROL MEASURE.
- REMOVE ACCUMULATED SEDIMENT WHEN 1/2 CAPACITY. DO NOT ALLOW SEDIMENT TO OVERFLOW ONTO CURB OR SIDEWALK.
- IMPLEMENT ADDITIONAL CONTROL MEASURES SUCH AS DOWNGRADIENT SEDIMENT CONTROL, WHITTLES, CURB CHECKS, OR OTHER BARRIERS AS ON-SITE CONDITIONS REQUIRE.



- CURB SOCK INSTALLATION NOTES**
- ADDITIONAL CURB SOCKS MAY BE REQUIRED AS DIRECTED BY SEMSWA.
 - CURB SOCKS IN STREETS SHALL BE INSTALLED WITHIN 48-HOURS OF POURING CURBS. CURB SOCKS (AFTER PAVEMENT) SHALL BE INSTALLED WITHIN 48 HOURS AFTER PAVING IS PLACED.
 - CRUSHED ROCK SHALL BE FRACTURED FACE ON ALL SIDES.
 - WIRE MESH SHALL BE FABRICATED OF WIRE TWISTED INTO A MESH WITH A MAXIMUM OPENING OF 1.0 INCH (COMMONLY TERMED "CHICKEN WIRE"). ROLL WIDTH SHALL BE 48-INCHES.
 - WIRE MESH SHALL BE SECURED USING "HOG RINGS" OR WIRE TIES AT APPROXIMATELY 6-INCH CENTERS ALONG ALL JOINTS AND AT APPROXIMATELY 2-INCH CENTERS ON ENDS OF BERM.
 - REINFORCED ROCK BERM SHALL BE CONSTRUCTED IN ONE PIECE OR SHALL BE CONSTRUCTED USING JOINT DETAILS.
 - EXAMPLES OF ACCEPTABLE GEOSYNTHETIC MATERIAL: TENACITE MIRAFI MIRAGRID 2X1; STRATA GLOBAL SOLUTIONS "STRATAGRID SG 150"; SOLID FABRIC OPTIONAL.
 - THE TOP OF REINFORCED ROCK BERM SHALL BE 1/2"-1" BELOW TOP OF CURB.

CURB SOCK MAINTENANCE NOTES

- THE GESC MANAGER SHALL INSPECT AS NECESSARY TO ENSURE THE ADEQUACY AND FUNCTIONALITY OF THE CONTROL MEASURE.
- SEDIMENT ACCUMULATED UPSTREAM OF CURB SOCK SHALL BE REMOVED WHEN THERE IS EVIDENCE OF SIGNIFICANT SEDIMENT BUILDUP.
- CURB PROTECTION IS TO REMAIN IN PLACE UNTIL THE UPSTREAM DISTURBED AREA IS STABILIZED AND GRASS COVER IS APPROVED, UNLESS SEMSWA APPROVES EARLIER REMOVAL OF CURB PROTECTION IN STREETS.






CHECK DAM INSTALLATION NOTES

- SEE PLAN VIEW FOR:
 - LOCATIONS OF CHECK DAMS.
 - CHECK DAM TYPE (CHECK DAM OR REINFORCED CHECK DAM).
 - LENGTH, "L", CREST LENGTH, "CL", AND DEPTH, "D".
- CHECK DAMS INDICATED ON INITIAL GESC PLAN SHALL BE INSTALLED PRIOR TO ANY UPSTREAM LAND-DISTURBING ACTIVITIES.
- VL RIPRAP SHALL BE UTILIZED FOR CHECK DAMS.
- RIP RAP PAD SHALL BE TRENCHED INTO THE CHANNEL BANKS TO ADEQUATELY ANCHOR WITH CENTER OF THE DAM LOWER TO ALLOW FOR OVERTOPPING AT THE CREST.

CHECK DAM MAINTENANCE NOTES

- THE GESC MANAGER SHALL INSPECT AS NECESSARY TO ENSURE THE ADEQUACY AND FUNCTIONALITY OF THE CONTROL MEASURE.
- SEDIMENT ACCUMULATED UPSTREAM OF CHECK DAMS SHALL BE REMOVED WHEN THE SEDIMENT DEPTH UPSTREAM OF CHECK DAM IS WITHIN 1/2 OF THE HEIGHT OF THE CREST.
- CHECK DAMS ARE TO REMAIN IN PLACE UNTIL THE UPSTREAM DISTURBED AREA IS STABILIZED AND GRASS COVER IS APPROVED BY SEMSWA.
- WHEN CHECK DAMS ARE REMOVED, EXCAVATIONS SHALL BE FILLED WITH SUITABLE COMPACTED BACK FILL. ANY DISTURBED AREA SHALL BE SEEDED AND MULCHED AND COVERED WITH EROSION CONTROL BLANKET OR OTHERWISE STABILIZED IN A MANNER APPROVED BY SEMSWA.



DEWATERING INSTALLATION NOTES

- A CONSTRUCTION DISCHARGE (DEWATERING) PERMIT, IF REQUIRED, SHALL BE OBTAINED FROM THE COLORADO DEPARTMENT OF PUBLIC HEALTH AND ENVIRONMENT PRIOR TO ANY DEWATERING OPERATIONS. ALL DEWATERING SHALL BE IN ACCORDANCE WITH THE REQUIREMENTS OF THE DISCHARGE PERMIT AND SHALL BE COORDINATED WITH THE SEMSWA GESC INSPECTOR.
- THE GESC MANAGER SHALL PROVIDE, OPERATE, AND MAINTAIN DEWATERING SYSTEMS OF SUFFICIENT SIZE AND CAPACITY.
- DEWATERING OPERATIONS SHALL USE ONE OR MORE OF THE DEWATERING SUMP(S) SHOWN ABOVE OR OTHER MEANS APPROVED BY SEMSWA TO REDUCE THE PUMPING OF SEDIMENT, AND SHALL PROVIDE A TEMPORARY BASIN FOR SETTLING PUMPED DISCHARGES PRIOR TO RELEASE OFF SITE OR TO A RECEIVING WATER SEDIMENT BASIN PER DETAIL 14 MAY BE USED IN LIEU OF SUMP DISCHARGE SETTLING BASIN SHOWN ABOVE.
- DISCHARGE POINT SHALL BE A STABILIZED AREA.
- THE DISCHARGE END OF THE LINE SHALL BE STAKED IN PLACE TO PREVENT MOVEMENT OF THE LINE OFF THE STABILIZED DISCHARGE POINT.

DEWATERING MAINTENANCE NOTES

- THE GESC MANAGER SHALL INSPECT AS NECESSARY TO ENSURE THE ADEQUACY AND FUNCTIONALITY OF THE CONTROL MEASURE.
- TEMPORARY SETTLING BASINS SHALL BE REMOVED WHEN NO LONGER NEEDED FOR DEWATERING OPERATIONS. ANY DISTURBED AREA SHALL BE DRILL SEEDED AND CRIMP MULCHED OR OTHERWISE STABILIZED IN A MANNER APPROVED BY SEMSWA.

GENERAL NOTE:

USE OF A SEDIMENT FILTER BAG MAY BE SUBSTITUTED FOR USE OF THE RIPRAP PAD AND SUMP DISCHARGE SETTLING BASIN. FILTER BAG TO SET ON RELATIVELY FLAT STABLE GROUND.




UTILITY NOTIFICATION CENTER OF COLORADO
CALL BEFORE YOU DIG
811
Call 2 days prior to any digging, grading or excavating for the marking of underground member utilities

SOUTHEAST METRO STORMWATER AUTHORITY
7437 SOUTH FAIRPLAY STREET
CENTENNIAL COLORADO
80112-4486
(303) 858-8844 - INSPECTION DIVISION

GRADING EROSION AND SEDIMENT CONTROL
STANDARD NOTES AND DETAILS
REVISED OCTOBER, 2017

GESC
SHEET
1 OF 4



UTILITY NOTIFICATION CENTER
OF COLORADO
CALL BEFORE YOU DIG
811
Call 2 days prior to any digging, grading or
excavating for the marking of underground
member utilities

SOUTHEAST METRO STORMWATER AUTHORITY
7437 SOUTH FAIRPLAY STREET
CENTENNIAL COLORADO
80112-4486
(303) 858-8844 - INSPECTION DIVISION

**GRADING EROSION AND SEDIMENT CONTROL
STANDARD NOTES AND DETAILS
REVISED OCTOBER, 2017**


**GESC
SHEET
2 OF 4**

SEDIMENT BASIN INSTALLATION NOTES

- SEE PLAN VIEW FOR:
 - LOCATION OF SEDIMENT BASIN.
 - TYPE OF BASIN (STANDARD BASIN OR NON-STANDARD BASIN).
 - FOR STANDARD BASIN, CREST LENGTH, "CL", BOTTOM WIDTH, "W", AND HOLE DIAMETER, "HD".
 - FOR NON-STANDARD BASIN, SEE CONSTRUCTION DRAWINGS FOR DESIGN OF BASIN INCLUDING RISER HEIGHT, "H", NUMBER OF COLUMNS, "N", HOLE DIAMETER, "HD", AND PIPE DIAMETER "D".
- FOR STANDARD BASIN, BOTTOM DIMENSION MAY BE MODIFIED AS LONG AS BOTTOM AREA IS NOT REDUCED.
- SEDIMENT BASINS INDICATED ON INITIAL GESC PLAN SHALL BE INSTALLED PRIOR TO ANY OTHER LAND-DISTURBING ACTIVITY.
- EMBANKMENT MATERIAL SHALL CONSIST OF SOIL FREE OF DEBRIS, ORGANIC MATERIAL, AND ROCKS GREATER THAN 3 INCHES AND SHALL HAVE A MINIMUM OF 15 PERCENT BY WEIGHT PASSING THE NO. 200 SIEVE.
- EMBANKMENT MATERIAL SHALL BE COMPACTED TO AT LEAST 95 PERCENT OF MAXIMUM DENSITY WITHIN 2 PERCENTAGE POINTS OF OPTIMUM DENSITY IN ACCORDANCE WITH ASTM D698.
- PIPE SCH 40 OR GREATER SHALL BE USED.
- THE DETAILS SHOWN ON THIS SHEET PERTAIN TO STANDARD SEDIMENT BASIN(S) IDENTIFIED ON THE GESC PLAN VIEW DRAWINGS USED FOR DRAINAGE AREAS LESS THAN 15 ACRES. SEE CONSTRUCTION DRAWINGS FOR EMBANKMENT, STORAGE VOLUME, SPILLWAY, OUTLET, AND OUTLET PROTECTION DETAILS FOR ANY SEDIMENT BASIN(S) THAT HAVE BEEN INDIVIDUALLY DESIGNED FOR DRAINAGE AREAS LARGER THAN 15 ACRES.

SEDIMENT BASIN MAINTENANCE NOTES

- THE GESC MANAGER SHALL INSPECT AS NECESSARY TO ENSURE THE ADEQUACY AND FUNCTIONALITY OF THE CONTROL MEASURE.
- SEDIMENT SHALL BE REMOVED FROM THE POND WHEN DESIGNED STORAGE VOLUME IS NO MORE THAN ONE-THIRD FILLED WITH SEDIMENT.
- SEDIMENT BASINS ARE TO REMAIN IN PLACE UNTIL THE UPSTREAM DISTURBED AREA IS STABILIZED AND GRASS COVER IS APPROVED BY SEMWA.
- IF SEDIMENT BASINS ARE REMOVED, THE DISTURBED AREA SHALL BE SEEDDED AND MULCHED OR OTHERWISE STABILIZED IN A MANNER APPROVED BY SEMWA.
- TRASH AND DEBRIS SHALL BE REMOVED FROM THE SEDIMENT BASIN TO PREVENT CLOGGING AT THE OUTLET.




SEDIMENT CONTROL LOG INSTALLATION NOTES

- SEE PLAN VIEW FOR:
 - LOCATION AND LENGTH OF SEDIMENT CONTROL LOG.
- SEDIMENT CONTROL LOGS INDICATED ON INITIAL GESC PLAN SHALL BE INSTALLED PRIOR TO ANY LAND-DISTURBING ACTIVITIES.
- SEDIMENT CONTROL LOGS SHALL CONSIST OF STRAW, COMPOST, EXCELSIOR, OR COCONUT FIBER.
- NOT FOR USE IN CONCENTRATED FLOW AREAS.
- THE SEDIMENT CONTROL LOG SHALL BE TRENCHED IN APPROPRIATELY.
- 9" DIAMETER SEDIMENT CONTROL LOGS ARE THE MINIMUM BUT A LARGER DIAMETER MAY BE REQUIRED BY THE SEMWA INSPECTOR.

SEDIMENT CONTROL LOG MAINTENANCE NOTES

- THE GESC MANAGER SHALL INSPECT AS NECESSARY TO ENSURE THE ADEQUACY AND FUNCTIONALITY OF THE CONTROL MEASURE.
- SEDIMENT ACCUMULATED UPSTREAM OF SEDIMENT CONTROL LOGS SHALL BE REMOVED WHEN THE UPSTREAM SEDIMENT DEPTH IS WITHIN 1/2 THE HEIGHT OF THE CREST OF LOG.
- SEDIMENT CONTROL LOG SHALL BE REMOVED AT THE END OF CONSTRUCTION, IF ANY DISTURBED AREA EXISTS AFTER REMOVAL, IT SHALL BE STABILIZED IN A MANNER APPROVED BY THE SEMWA INSPECTOR.



SEDIMENT TRAP INSTALLATION NOTES

- SEE PLAN VIEW FOR:
 - LOCATION, LENGTH AND WIDTH OF SEDIMENT TRAP.
- SEDIMENT TRAPS INDICATED ON INITIAL GESC PLAN SHALL BE INSTALLED PRIOR TO ANY LAND-DISTURBING ACTIVITIES.
- SEDIMENT TRAP BERM SHALL BE CONSTRUCTED FROM MATERIAL FROM EXCAVATION. THE BERM SHALL BE COMPACTED TO 95% OF THE MAXIMUM DENSITY IN ACCORDANCE WITH ASTM D698.
- TRAP OUTLET SHALL BE CONSTRUCTED WITH D₆₀ = 12" RIPRAP WITH A MINIMUM OVERFLOW OF 6".
- THE TOP OF THE EARTHEN BERM SHALL ALLOW FOR OVERTOPPING.
- THE ENDS OF THE RIPRAP OUTLET STRUCTURE SHALL ALLOW FOR OVERTOPPING.
- OVERTOPPING MUST OCCUR ON A STABILIZED SURFACE TO INCLUDE WELL VEGETATED AREAS, RIP RAP, OR PAVEMENT.
- SEDIMENT TRAP SIZED TO PROVIDE STORAGE VOLUME EQUAL TO 1800 CUBIC FEET PER UPSTREAM ACRE.

SEDIMENT TRAP MAINTENANCE NOTES

- THE GESC MANAGER SHALL INSPECT AS NECESSARY TO ENSURE THE ADEQUACY AND FUNCTIONALITY OF THE CONTROL MEASURE.
- SEDIMENT ACCUMULATED UPSTREAM OF RIPRAP SHALL BE REMOVED WHEN THE UPSTREAM SEDIMENT DEPTH IS WITHIN 1/2 THE HEIGHT OF THE RIPRAP OUTLET STRUCTURE.
- SEDIMENT TRAPS SHALL REMAIN IN PLACE UNTIL THE UPSTREAM DISTURBED AREA IS STABILIZED AND GRASS COVERAGE IS APPROVED BY SEMWA.
- WHEN SEDIMENT TRAPS ARE REMOVED THE DISTURBED AREA SHALL BE DRILLED SEEDDED AND CRIMP MULCHED OR STABILIZED IN A MANNER APPROVED BY SEMWA.

SEEDING AND MULCHING INSTALLATION NOTES

- SEE PLAN VIEW FOR:
 - AREA OF SEEDING AND MULCHING.
 - TYPE OF SEED MIX.
- ALL BERMANS FURNISHED SHALL BE FREE FROM SUCH NOXIOUS SEEDS AS RUSSIAN OR CANADIAN THISTLE, COARSE FESCUE, EUROPEAN BIRCHWEED, JOHNSON GRASS, KNAF WEED AND LEAFY SPURGE.
- THE SEEDER SHALL FURNISH TO THE CONTRACTOR A SIGNED STATEMENT CERTIFYING THAT THE SEED FURNISHED IS FROM A LOT THAT HAS BEEN TESTED BY A RECOGNIZED LABORATORY. SEED WHICH HAS BECOME WET, MOLDY, OR OTHERWISE DAMAGED IN TRANSIT OR IN STORAGE WILL NOT BE ACCEPTABLE. SEED TICKETS SHALL BE PROVIDED TO SEMWA UPON REQUEST.
- DRILL SEEDING MIX SHALL CONFORM TO THE TABLE ON THE RIGHT: UNLESS OTHERWISE APPROVED BY SEMWA.
- IF THE SEED AVAILABLE ON THE MARKET DOES NOT MEET THE MINIMUM PURITY AND GERMINATION PERCENTAGES SPECIFIED, THE CONTRACTOR MUST COMPENSATE FOR A LESSER PERCENTAGE OF PURITY OR GERMINATION BY FURNISHING SUFFICIENT ADDITIONAL SEED TO EQUAL THE SPECIFIED PRODUCT. THE TAGS FROM THE SEED MOES MUST BE SUPPLIED TO CONTRACTOR AND FORWARDED TO THE SEMWA GESC INSPECTOR.
- THE FORMULA USED FOR DETERMINING THE QUANTITY OF PURE LIVE SEED (PLS) SHALL BE (POUNDS OF SEED) X (PURITY) X (GERMINATION) = POUNDS OF PURE LIVE SEED (PLS).
- PERMANENT SEED MIX SHALL BE USED UNLESS OTHERWISE APPROVED BY SEMWA.
- ALL AREAS TO BE SEEDDED AND MULCHED SHALL HAVE NATIVE TOPSOIL OR APPROVED SOIL AMENDMENTS SPREAD TO A DEPTH OF AT LEAST 6 INCHES (LOOSE DEPTH). ALL DISTURBED AREAS SHALL BE LOOSENOED TO A DEPTH OF 6 INCHES PRIOR TO SPREADING TOPSOIL.
- SOIL IS TO BE THOROUGHLY LOOSENOED (TILLED) TO A DEPTH OF AT LEAST 6 INCHES PRIOR TO SEEDING. THE TOP 6 INCHES OF THE SEED BED SHALL BE GENERALLY FREE OF ROCKS GREATER THAN 4 INCHES AND SOIL CLOSURES GREATER THAN 2 INCHES. SEEDING OVER ANY COMPACTED AREAS THAT HAVEN'T BEEN THOROUGHLY LOOSENOED SHALL BE REJECTED.
- SEED IS TO BE APPLIED USING A MECHANICAL DRILL TO A DEPTH OF 1/4 INCH. ROW SPACING SHALL BE NO MORE THAN 6 INCHES. MATERIAL USED FOR MULCH SHALL CONSIST OF LONG-STEMMED STRAW. AT LEAST 50 PERCENT OF THE MULCH, BY WEIGHT, SHALL BE 10 INCHES OR MORE IN LENGTH. MULCH SHALL BE APPLIED AND MECHANICALLY ANCHORED TO A DEPTH OF AT LEAST 2 INCHES. MULCH SHALL BE APPLIED AT A RATE OF 2000 LB. OF STRAW PER ACRE.
- IF THE PERMITTEE DEMONSTRATES TO SEMWA THAT IT IS NOT POSSIBLE TO DRILL SEED, SEED IS TO BE UNIFORMLY BROADCAST AT TWO TIMES THE DRILLED RATE, THEN LIGHTLY HARROWED TO PROVIDE A SEED DEPTH OF APPROXIMATELY 1 1/4 INCH, THEN ROLLED TO COMPACT, THEN MULCHED AS SPECIFIED ABOVE.
- WHEN SEEDING AND MULCHING IS USED TO STABILIZED DISTURBED AREAS, ALL DISTURBED AREAS WHICH ARE EITHER FINAL GRADE, OR WILL REMAIN INACTIVE FOR A PERIOD OF MORE THAN 30 DAYS SHALL BE REQUIRED TO BE STABILIZED WITHIN 14 DAYS OF THE COMPLETION OF THE GRADING ACTIVITIES. THIS MAY REQUIRE MULTIPLE MOBILIZATIONS FOR SEEDING AND MULCHING.
- MULCH SHALL BE APPLIED WITHIN 24-HOURS OF SEEDING.
- TACKIFIER SHALL BE UTILIZED TO HELP WITH STRAW DISPLACEMENT.

SEEDING AND MULCHING MAINTENANCE NOTES

- SEEDING AND MULCHED AREAS SHALL BE INSPECTED FOR REQUIRED COVERAGE MONTHLY UNTIL FINAL ACCEPTANCE IS ISSUED. REPAIRS AND RE-SEEDING AND MULCHING SHALL BE UNDERTAKEN AFTER THE FIRST GROWING SEASON TO MEET THE REQUIRED COVERAGE.
- REQUIRED COVERAGE FOR STANDARD, OPEN SPACE AND LOW GROWTH SEED MIXES SHALL BE DEFINED AS FOLLOWS:
 - 70% OF THE EXISTING/ PRE-CONSTRUCTION CONDITION.
 - FREE OF ERODED AREAS.
 - FREE FROM INFESTATION OF NOXIOUS WEEDS IN ACCORDANCE WITH THE GESC CRITERIA MANUAL.
- RILL AND GULLY EROSION SHALL BE FILLED WITH TOPSOIL PRIOR TO RESEEDING. THE RESEEDING METHOD SHALL BE APPROVED BY SEMWA.

TEMPORARY DRILL SEEDING MIX

SPECIES	VARIETY	NOTES	% IN MIX	POUNDS OF PLS PER ACRE
SMOOTH BROMGRASS	LINCOLN	PICS	30	3.9
INTERMEDIATE WHEATGRASS	DAHE	PICS	30	4.5
PURSCUE WHEATGRASS	LUNA	PICS	30	4.2
ANNUAL RYEGRASS	N/A	ACB	10	0.8
		TOTAL	100	13.4

NOTES: P=PERENNIAL
H=HYPERNOMAL
I=INTRODUCED
C=COOL SEASON
S=SOO FORMER
B=BLANCHGRASS

PERMANENT DRILL SEEDING – WETLAND SEED MIX¹

SPECIES	SCIENTIFIC NAME	SEASON	% IN MIX	SEEDS/LB.	LBS PLS ² /AC
SLOUGH GRASS	BECKMANNIA SYZYGACHNE	COOL	20	1,150,000	0.5
CANADIAN REED GRASS	CAHAMARGRISTIS CANADENSIS	COOL	20	2,270,000	0.2
TUFTED HARR GRASS	DESCHAMPSIA CESPERTOSA	COOL	10	2,500,000	0.1
COMMON SPIKE RUSH	ELEOCHARIS PALUSTRIS	COOL	15	620,000	0.6
BALTIC RUSH	JUNCUS BALTICUS	COOL	15	10,900,000	0.4
KNOTTED RUSH	JUNCUS NOODUS	COOL	10	12,300,000	0.1
TORREY'S RUSH	JUNCUS TORREYI	COOL	10	12,300,000	0.1
	TOTAL		100		2 LBS PLS ² /AC

¹ TO BE INSTALLED AT APPROXIMATELY 0" TO 6" ABOVE WATER LINE.

² PLS = PURE LIVE SEED PER POUND BASED 60 SEEDS PER SQUARE FOOT. IF BROADCAST SEEDING, DOUBLE THE RATE APPLIED.

PERMANENT DRILL SEEDING¹ – TRANSITION SEED MIX – WITHOUT FORBS

SPECIES	SCIENTIFIC NAME	SEASON	% IN MIX	SEEDS/LB.	LBS PLS ² /AC
CANADA WILDRYE	ELYMUS CANADENSIS	COOL	15	115,000	3.4
STREAMBANK WHEATGRASS	ELYMUS LANCEOLATUS SPP. PSAMMOPHILUS	COOL	15	156,000	2.5
SLENDER WHEAT GRASS	ELYMUS TRACHYCALULUS	WARM	10	159,000	1.6
BALTIC RUSH	JUNCUS BALTICUS	COOL	15	10,900,000	0.1
SWITCHGRASS	PANICUM VIRGATUM	WARM	15	389,000	1.0
WESTERN WHEATGRASS	PASCOPYRUM SMITHI	COOL	15	110,000	3.6
SAND DROPSSEED	SPOROBOLUS AIROIDES	WARM	15	1,758,000	0.2
	TOTAL		100		12.4 LBS PLS ² /AC

¹ TO BE INSTALLED AT APPROXIMATELY 6" TO 24" ABOVE WATER LINE.

² PLS = PURE LIVE SEED PER POUND BASED 60 SEEDS PER SQUARE FOOT. IF BROADCAST SEEDING, DOUBLE THE RATE APPLIED.

³ IF DESIRED, SHRUBS FROM THE WILLOW SHRUBLAND PLANT COMPOSITION SCHEDULE CAN BE INSTALLED IN THIS ZONE.

PERMANENT DRILL SEEDING¹ – TRANSITION SEED MIX – WITH FORBS

SPECIES	SCIENTIFIC NAME	SEASON	% IN MIX	SEEDS/LB.	LBS PLS ² /AC
NATIVE GRASSES					
CANADA WILDRYE	ELYMUS CANADENSIS	COOL	15	115,000	3.4
STREAMBANK WHEATGRASS	ELYMUS LANCEOLATUS SPP. PSAMMOPHILUS	COOL	15	156,000	2.5
SLENDER WHEAT GRASS	ELYMUS TRACHYCALULUS	WARM	10	159,000	1.6
BALTIC RUSH	JUNCUS BALTICUS	COOL	15	10,900,000	0.1
SWITCHGRASS	PANICUM VIRGATUM	WARM	15	389,000	1.0
WESTERN WHEATGRASS	PASCOPYRUM SMITHI	COOL	15	110,000	3.6
SAND DROPSSEED	SPOROBOLUS AIROIDES	WARM	15	1,758,000	0.2

PERMANENT DRILL SEEDING¹ – TRANSITION SEED MIX – WITH FORBS

SPECIES	SCIENTIFIC NAME	SEASON	% IN MIX	SEEDS/LB.	LBS PLS ² /AC
NATIVE WILDFLOWERS					
INDIAN BLANKET FLOWER	GALLIARDIA ARISTATA	SUMMER-FALL	1	132,000	0.2
ROCKY MOUNTAIN IRIS	IRIS MISSOURIENSIS	SPRING-SUMMER	2	368,000	0.1
EVENING PRIMROSE	OENOTHERA ELATA	SUMMER	2	1,300,000	0.1
GOLDEN BANNER	THERMOPSIS MONTANA	SPRING	2	15,000	3.5
MEXICAN HAT	RATIBIDA COLUMNIFERA	SUMMER-FALL	1	1,230,000	0.1
SAND DROPSSEED	SPOROBOLUS AIROIDES	WARM	15	1,758,000	0.2
	TOTAL		100		14.4 LBS PLS ² /AC

¹ TO BE INSTALLED AT APPROXIMATELY 6" TO 24" ABOVE WATER LINE.

² PLS = PURE LIVE SEED PER POUND BASED 60 SEEDS PER SQUARE FOOT. IF BROADCAST SEEDING, DOUBLE THE RATE APPLIED.

³ IF DESIRED, SHRUBS FROM THE WILLOW SHRUBLAND PLANT COMPOSITION SCHEDULE CAN BE INSTALLED IN THIS ZONE.

PERMANENT DRILL SEEDING – UPLAND SEED¹ MIX – WITHOUT FORBS

SPECIES	SCIENTIFIC NAME	SEASON	% IN MIX	SEEDS/LB.	LBS PLS ² /AC
BIG BLUESTEM	ANDROPOGON GERARDI	WARM	10	130,000	2.0
SULFUR FLOWER	EROGONIUM UMBELLATUM	FALL	2	209,000	0.3
PRAIRIE ASTER	MACHAERANTHERA TRACHYSTACHYA	SUMMER	1	408,000	0.1
PURPLE PRAIRIE CLOVER	DALEA PURPUREA	SUMMER	1	210,000	0.1
WESTERN YARROW	ACHILLEA MILEFOLIUM VAR. OCCIDENTALIS	SUMMER-FALL	2	2,770,000	0.1
PLAINS COREOPSIS	COREOPSIS TINCTORIA	SUMMER-FALL	1	1,400,000	0.1
INDIAN BLANKET FLOWER	GALLIARDIA ARISTATA	SUMMER-FALL	1	132,000	0.2
PURPLE CONEFLOWER	LECHNACEA PURPUREA	SUMMER	1	117,000	0.2
	TOTAL		100		15.5 LBS PLS ² /AC

¹ TO BE INSTALLED AT APPROXIMATELY 24" ABOVE WATER LINE.

² PLS = PURE LIVE SEED PER POUND BASED 60 SEEDS PER SQUARE FOOT. IF BROADCAST SEEDING, DOUBLE THE RATE APPLIED.

³ IF DESIRED, TREES AND SHRUBS FROM THE COTTONWOOD SHRUB WOODLAND COMPOSITION SCHEDULE CAN BE INSTALLED IN THIS ZONE.

UPLAND SEED MIX – WITH FORBS¹


SPECIES	SCIENTIFIC NAME	SEASON	% IN MIX	SEEDS/LB.	LBS PLS ² /AC
NATIVE GRASSES					
BIG BLUESTEM	ANDROPOGON GERARDI	WARM	8	130,000	1.6
SIDEOTS GRAMA	BOULELOUA CURTIPENDULA	WARM	8	191,000	1.1
BLUE GRAMA	BOULELOUA GRACILIS	WARM	8	825,000	0.3
CANADA WILDRYE	ELYMUS CANADENSIS	COOL	8	115,000	1.6
THICKSPICE WHEATGRASS	ELYMUS LANCEOLATUS SPP. LANCEOLATUS	COOL	5	154,000	0.8
STREAMBANK WHEATGRASS	ELYMUS LANCEOLATUS SPP. PSAMMOPHILUS	COOL	5	156,000	0.8
SLENDER WHEAT GRASS	ELYMUS TRACHYCALULUS	WARM	10	159,000	1.6
NEEDLE AND THREAD	HESPEROSTIPHA COMATA	COOL	8	115,000	1.8
WESTERN WHEATGRASS	PASCOPYRUM SMITHI	COOL	10	110,000	2.4
INDIAN GRASS	SORGHASTRUM NUTANS	WARM	10	170,000	1.5
SAND DROPSSEED	SPOROBOLUS CRYPTANDRUS	WARM	10	5,298,000	0.1
NATIVE WILDFLOWERS					
BLACK-EYED SUSAN	RUDIBEEDIA HIRT	SUMMER-FALL	1	1,710,000	0.1
SULFUR FLOWER	EROGONIUM UMBELLATUM	FALL	2	209,000	0.3
PRAIRIE ASTER	MACHAERANTHERA TRACHYSTACHYA	SUMMER	1	408,000	0.1
PURPLE PRAIRIE CLOVER	DALEA PURPUREA	SUMMER	1	210,000	0.1
WESTERN YARROW	ACHILLEA MILEFOLIUM VAR. OCCIDENTALIS	SUMMER-FALL	2	2,770,000	0.1
PLAINS COREOPSIS	COREOPSIS TINCTORIA	SUMMER-FALL	1	1,400,000	0.1
INDIAN BLANKET FLOWER	GALLIARDIA ARISTATA	SUMMER-FALL	1	132,000	0.2
PURPLE CONEFLOWER	LECHNACEA PURPUREA	SUMMER	1	117,000	0.2
	TOTAL		100		15 LBS PLS ² /AC

¹ TO BE INSTALLED AT APPROXIMATELY 24" ABOVE WATER LINE.

² PLS = PURE LIVE SEED PER POUND BASED 60 SEEDS PER SQUARE FOOT. IF BROADCAST SEEDING, DOUBLE THE RATE APPLIED.

³ IF DESIRED, TREES AND SHRUBS FROM THE COTTONWOOD SHRUB WOODLAND COMPOSITION SCHEDULE CAN BE INSTALLED IN THIS ZONE.

COMMON OR TRADE NAME	SCIENTIFIC NAME	LBS PLS/AC
OPTION 1: OATS	AVENA SATIVA	60 TO 90
OPTION 2: QUICKGARD	TRITICUM AESTIVUM X SCALE CEREALE	10 TO 40
OPTION 3: REGREEN	TRITICUM AESTIVUM X ELYTRIGIA ELONGATA	10 TO 40




SILT FENCE INSTALLATION NOTES

- SEE PLAN VIEW FOR:
 - LOCATION AND LENGTH OF FENCE.
- ANCHOR TRENCH SHALL BE EXCAVATED WITH TRENCHER, OR WITH SILT FENCE INSTALLATION MACHINE; NO ROAD GRADERS, BACKHOES, ETC. SHALL BE USED. TRENCH SHALL BE COMPACTED BY HAND, WITH "JUMPING JACK", OR BY WHEEL ROLLING. COMPACTION SHALL BE SUCH THAT SILT FENCE RESISTS BEING PULLED OUT OF ANCHOR TRENCH BY HAND.
- SILT FENCE GEOTEXTILE SHALL MEET THE FOLLOWING REQUIREMENTS:
 - 6-TO 12-GALLONS PER MINUTE PER SQUARE FOOT FLOW CAPACITY.
 - 90 LB. TENSILE STRENGTH PER ASTM D4622.
 - UV DESIGN AT 500 HRS MIN. 70% STRENGTH RETAINED PER ASTM D 4355.
- SILT FENCE INDICATED ON INITIAL GESC PLAN SHALL BE INSTALLED PRIOR TO ANY LAND-DISTURBING ACTIVITIES.

SILT FENCE MAINTENANCE NOTES

- THE GESC MANAGER SHALL INSPECT AS NECESSARY TO ENSURE THE ADEQUACY AND FUNCTIONALITY OF THE CONTROL MEASURE.
- SEDIMENT ACCUMULATED UPSTREAM OF SILT FENCE SHALL BE REMOVED WHEN THE UPSTREAM SEDIMENT REACHES 25%.
- SILT FENCE SHALL BE REMOVED WHEN THE UPSTREAM DISTURBED AREA IS STABILIZED AND GRASS COVER IS APPROVED BY SEMWA. IF ANY DISTURBED AREA EXISTS AFTER REMOVAL, IT SHALL BE SEEDDED AND MULCHED OR OTHERWISE STABILIZED IN A MANNER APPROVED BY SEMWA.




SLOPE INTERCEPT DITCH INSTALLATION NOTES

- MATERIALS CUT OUT OF DITCH TO FORM A COMPACTED BERM ADJACENT TO AND ON THE CONSTRUCTION AREA SIDE OF DITCH.
- SLOPE INTERCEPT DITCH SHALL HAVE A MINIMUM DEPTH OF 10".
- COMPACTED BERM SHALL HAVE A MINIMUM HEIGHT OF 10".
- SLOPE INTERCEPT DITCH SHALL BE CUT IN ON THE CONTOUR.
- SLOPE INTERCEPT DITCH CAN BE USED IN PLACE OF SILT FENCE (SF) AND SEDIMENT CONTROL LOGS (SCL).
- SEE PLAN VIEW FOR LOCATION.

SLOPE INTERCEPT DITCH MAINTENANCE NOTES

- THE GESC MANAGER SHALL INSPECT AS NECESSARY TO ENSURE THE ADEQUACY AND FUNCTIONALITY OF THE CONTROL MEASURE.
- SEDIMENT ACCUMULATED IN DITCH SHALL BE REMOVED WHEN DITCH BECOMES 1/2 FULL. REMOVED SEDIMENT SHALL BE PLACED ON AND COMPACTED WITH THE ADJACENT BERM.
- BERM MATERIAL TO FILL DITCH UPON COMPLETION OF CONSTRUCTION. ALL DISTURBED AREAS TO BE SEEDDED AND MULCHED PER DETAIL 17.



STABILIZED STAGING AREA INSTALLATION NOTES

- SEE PLAN VIEW FOR GENERAL LOCATION OF STAGING AREA. CONTRACTOR MAY MODIFY LOCATION AND SIZE OF STABILIZED STAGING AREA WITH SEMWA APPROVAL.
- STABILIZED STAGING AREA SHALL BE LARGE ENOUGH TO FULLY CONTAIN PARKING, STORAGE, AND UNLOADING AND LOADING OPERATIONS.
- IF REQUIRED BY SEMWA, SITE ACCESS ROADS SHALL BE STABILIZED IN THE SAME MANNER AS THE STAGING AREA.
- STAGING AREA SHALL BE STABILIZED PRIOR TO ANY OTHER OPERATIONS ON THE SITE.
- THE STABILIZED STAGING AREA SHALL CONSIST OF A MINIMUM OF 3" OF GRANULAR MATERIAL (GRAVEL).

STABILIZED STAGING AREA MAINTENANCE NOTES











- THE GESC MANAGER SHALL INSPECT AS NECESSARY TO ENSURE THE ADEQUACY AND FUNCTIONALITY OF THE CONTROL MEASURE.
- GESC MANAGER SHALL PROVIDE ADDITIONAL THICKNESS OF GRANULAR MATERIAL IF ANY RUTTING OCCURS OR UNDERLYING SUBGRADE BECOMES EXPOSED.
- STABILIZED STAGING AREA SHALL BE ENLARGED IF NECESSARY TO CONTAIN PARKING, STORAGE, AND UNLOADING AND LOADING OPERATIONS.
- ANY ACCUMULATED DIRT OR MUD SHALL BE REMOVED FROM THE SURFACE OF THE STABILIZED STAGING AREA.
- THE STABILIZED STAGING AREA SHALL BE REMOVED AT THE END OF CONSTRUCTION. THE GRANULAR MATERIAL SHALL BE REMOVED OR, IF APPROVED BY SEMWA, USED ON SITE, AND THE AREA TOPSOILED, DRILL SEEDDED AND CRIMP MULCHED OR OTHERWISE STABILIZED.

UTILITY NOTIFICATION CENTER
OF COLORADO
CALL BEFORE YOU DIG

811

Call 2 days prior to any digging, grading or excavating for the marking of underground member utilities

SOUTHEAST METRO STORMWATER AUTHORITY

 <p>SURFACE ROUGHENING INSTALLATION NOTES</p> <ol style="list-style-type: none"> 1. SURFACE ROUGHENING SHALL BE PROVIDED ON ALL FINISHED GRADES (SLOPES AND "FLAT" AREAS) WITHIN 2 DAYS OF COMPLETION OF FINISHED GRADE (FOR AREAS NOT RECEIVING TOPSOIL) OR WITHIN 2 DAYS OF TOPSOIL PLACEMENT. 2. AREAS WHERE BUILDING FOUNDATIONS, PAVEMENT, OR SOD IS TO BE PLACED WITHIN 7-DAYS OF FINISHED GRADING DO NOT NEED TO BE SURFACE ROUGHENED. 3. DISTURBED SURFACES SHALL BE ROUGHENED USING RIPPING OR TILLING EQUIPMENT ON THE CONTOUR OR TRACKING UP AND DOWN A SLOPE USING EQUIPMENT TREADS. <p>SURFACE ROUGHENING MAINTENANCE NOTES</p> <ol style="list-style-type: none"> 1. THE GESC MANAGER SHALL INSPECT AS NECESSARY TO ENSURE THE ADEQUACY AND FUNCTIONALITY OF THE CONTROL MEASURE. 2. VEHICLES AND EQUIPMENT SHALL GENERALLY BE CONFINED TO ACCESS DRIVES AND SHALL NOT BE DRIVEN OVER AREAS THAT HAVE BEEN SURFACE ROUGHENED. 3. IN NON-TURF GRASS FINISHED AREAS, SEEDING AND MULCHING SHALL TAKE PLACE DIRECTLY OVER SURFACE ROUGHENED AREAS WITHOUT FIRST SMOOTHING OUT THE SURFACE. 4. IN AREAS NOT SEEDED AND MULCHED AFTER SURFACE ROUGHENING, SURFACES SHALL BE RE-ROUGHENED AS NECESSARY TO MAINTAIN GROOVE DEPTH AND SMOOTH OVER ANY RILL EROSION. <p>SR SURFACE ROUGHENING 22</p>	 <p>SLOPE DRAIN - DETAIL SCALE: NTS</p>  <p>PLASTIC LINED DRAIN - SECTION SCALE: NTS</p>  <p>TERMINATION OF PLASTIC LINED SLOPE DRAIN - DETAIL SCALE: NTS</p> <p>SLOPE DRAIN - SECTION SCALE: NTS</p> <p>TERMINATION OF RIPRAP LINED SLOPE DRAIN - DETAIL SCALE: NTS</p> <p>SLOPE DRAIN INSTALLATION NOTES</p> <ol style="list-style-type: none"> 1. SEE PLAN VIEW FOR: <ul style="list-style-type: none"> • LOCATION AND LENGTH OF SLOPE DRAIN. • PIPE DIAMETER, "D", AND RIPRAP SIZE, "Dw". 2. SLOPE DRAIN DIMENSIONS SHALL BE CONSIDERED MINIMUM DIMENSIONS; CONTRACTOR MAY ELECT TO INSTALL LARGER FACILITIES. ANY DAMAGE TO SLOPE OR SLOPE DRAIN DURING RUNOFF EVENTS SHALL BE THE CONTRACTOR'S RESPONSIBILITY. 3. SLOPE DRAINS INDICATED ON INITIAL GESC PLAN SHALL BE INSTALLED PRIOR TO ANY UPSTREAM LAND-DISTURBING ACTIVITIES. 4. FOR TEMPORARY SLOPE DRAINS, PIPE MAY BE INSTALLED ON TOP OF SLOPE; HOWEVER, 12" MIN. COVER AT TOP OF SLOPE SHALL BE PROVIDED. 5. AN ENERGY DISSIPATOR SHALL BE PLACED AT THE OUTFALL OF THE SLOPE DRAIN. <p>SLOPE DRAIN MAINTENANCE NOTES</p> <ol style="list-style-type: none"> 1. THE GESC MANAGER SHALL INSPECT AS NECESSARY TO ENSURE THE ADEQUACY AND FUNCTIONALITY OF THE CONTROL MEASURE. 2. TEMPORARY SLOPE DRAINS ARE TO REMAIN IN PLACE UNTIL NO LONGER NEEDED, BUT SHALL BE REMOVED PRIOR TO THE END OF CONSTRUCTION, WHEN SLOPE DRAINS ARE REMOVED, THE DISTURBED AREA SHALL BE DRILL SEEDED AND CRIMP MULCHED OR OTHERWISE STABILIZED IN A MANNER APPROVED BY SEMDMA. <p>TSD TEMPORARY SLOPE DRAIN 23</p>	 <p>FORD CROSSING - DETAIL SCALE: NTS</p>  <p>CULVERT CROSSING - DETAIL SCALE: NTS</p> <p>FORD CROSSING - SECTION SCALE: NTS</p> <p>CULVERT CROSSING - SECTION SCALE: NTS</p> <p>TEMPORARY STREAM CROSSING INSTALLATION NOTES</p> <ol style="list-style-type: none"> 1. SEE PLAN VIEW FOR: <ul style="list-style-type: none"> • LOCATIONS OF TEMPORARY STREAM CROSSING. • LENGTH, "L", CREST LENGTH, "LC", CROSSING HEIGHT, "H", DEPTH, "D", CULVERT DIAMETER, "CD", AND NUMBER, TYPE AND CLASS OF CULVERTS. 2. TEMPORARY STREAM CROSSING DIMENSIONS, D50, AND NUMBER OF CULVERTS INDICATED (FOR CULVERT CROSSING) SHALL BE CONSIDERED MINIMUM DIMENSIONS; ENGINEER MAY ELECT TO INSTALL LARGER FACILITIES. ANY DAMAGE TO STREAM CROSSING OR EXISTING STREAM CHANNEL DURING BASEFLOW OR FLOOD EVENTS SHALL BE THE CONTRACTOR'S RESPONSIBILITY. 3. SEE SHEET 1 FOR RIPRAP AND 1-1/2" CRUSHED ROCK GRADATIONS. 4. FOR A TEMPORARY STREAM CROSSING THAT WILL CARRY LOADS, THE TEMPORARY STREAM CROSSING MUST BE DESIGNED BY THE DESIGN ENGINEER. <p>TEMPORARY STREAM CROSSING MAINTENANCE NOTES</p> <ol style="list-style-type: none"> 1. THE GESC MANAGER SHALL INSPECT AS NECESSARY TO ENSURE THE ADEQUACY AND FUNCTIONALITY OF THE CONTROL MEASURE. 2. SEDIMENT ACCUMULATED UPSTREAM OF STREAM CROSSINGS SHALL BE REMOVED WHEN THE SEDIMENT DEPTH UPSTREAM OF CROSSING IS WITHIN 50% OF THE CREST (FORD CROSSING) OR GREATER THAN AN AVERAGE DEPTH OF 50% (CULVERT CROSSING). 3. STREAM CROSSINGS ARE TO REMAIN IN PLACE UNTIL NO LONGER NEEDED, BUT SHALL BE REMOVED PRIOR TO THE END OF CONSTRUCTION. 4. WHEN STREAM CROSSINGS ARE REMOVED, THE DISTURBED AREA SHALL BE DRILL SEEDED AND CRIMP MULCHED AND COVERED WITH EROSION CONTROL BLANKET OR OTHERWISE STABILIZED IN A MANNER APPROVED BY THE SEMDMA. <p>TSC TEMPORARY STREAM CROSSING 24</p>	 <p>VEHICLE TRACKING CONTROL - DETAIL SCALE: NTS</p>  <p>VEHICLE TRACKING CONTROL - SECTION SCALE: NTS</p> <p>VEHICLE TRACKING CONTROL INSTALLATION NOTES</p> <ol style="list-style-type: none"> 1. VEHICLE TRACKING CONTROL PADS SHALL BE INSTALLED AT EVERY EXIT POINT OF THE SITE. 2. VEHICLE TRACKING CONTROL PADS SHALL CONSIST OF HARD, DENSE, DURABLE STONE, ANGULAR IN SHAPE AND RESISTANT TO WEATHERING. ROUNDED STONE OR BOULDERS WILL NOT BE ACCEPTABLE. THE STONES SHALL NOT BE SMALLER THAN 3" IN SIZE. THE STONE SHALL HAVE A SPECIFIC GRAVITY OF AT LEAST 2.6. CONTROL OF GRADATION WILL BE BY VISUAL INSPECTIONS. 3. ANY CRACKED OR DAMAGED CURB AND GUTTER AND SIDEWALK SHALL BE REPLACED BY PERMITTEE. <p>VEHICLE TRACKING CONTROL MAINTENANCE NOTES</p> <ol style="list-style-type: none"> 1. THE GESC MANAGER SHALL INSPECT AS NECESSARY TO ENSURE THE ADEQUACY AND FUNCTIONALITY OF THE CONTROL MEASURE. 2. VEHICLE TRACKING CONTROL SHALL BE REMOVED AT THE END OF CONSTRUCTION, THE ROCK MATERIAL REMOVED OR, IF APPROVED BY SEMDMA, USED ON SITE, AND THE AREA TOPSOILED, DRILL SEEDED AND CRIMP MULCHED OR OTHERWISE STABILIZED. <p>VTC VEHICLE TRACKING CONTROL 25</p>	 <p>VEHICLE TRACKING CONTROL WITH WHEEL WASH - DETAIL SCALE: NTS</p>  <p>VEHICLE TRACKING CONTROL WITH WHEEL WASH - SECTION SCALE: NTS</p> <p>VEHICLE TRACKING CONTROL WITH WHEEL WASH INSTALLATION NOTES</p> <ol style="list-style-type: none"> 1. SEMDMA RESERVES THE RIGHT TO REQUIRE VEHICLE TRACKING CONTROL WITH WHEEL WASH FACILITIES AT SITES WHERE TRACKING ONTO PAVED AREAS BECOMES A SIGNIFICANT PROBLEM. 2. IF VEHICLE TRACKING CONTROL WITH WHEEL WASH FACILITIES ARE REQUIRED, ALL WHEELS ON EVERY VEHICLE LEAVING THE SITE SHALL BE CLEANED OF MUD USING A PRESSURE-WASHER. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING A WATER SOURCE. 3. VEHICLE TRACKING CONTROL PADS SHALL CONSIST OF HARD, DENSE, DURABLE STONE, ANGULAR IN SHAPE AND RESISTANT TO WEATHERING. ROUNDED STONE OR BOULDERS WILL NOT BE ACCEPTABLE. THE STONES SHALL NOT BE SMALLER THAN 3" IN SIZE. THE STONE SHALL HAVE A SPECIFIC GRAVITY OF AT LEAST 2.6. CONTROL OF GRADATION WILL BE BY VISUAL INSPECTIONS. 4. ANY CRACKED OR DAMAGED CURB AND GUTTER AND SIDEWALK SHALL BE REPLACED BY CONTRACTOR. <p>VEHICLE TRACKING CONTROL WITH WHEEL WASH MAINTENANCE NOTES</p> <ol style="list-style-type: none"> 1. THE GESC MANAGER SHALL INSPECT AS NECESSARY TO ENSURE THE ADEQUACY AND FUNCTIONALITY OF THE CONTROL MEASURE. 2. ACCUMULATED SEDIMENT IN THE WASHWATER/SEDIMENT TRAP SHALL BE REMOVED WHEN THE SEDIMENT DEPTH REACHES AN AVERAGE OF 12-INCHES. 3. VEHICLE TRACKING CONTROL WITH WHEEL WASH FACILITY SHALL BE REMOVED AT THE END OF CONSTRUCTION, THE RIPRAP MATERIAL REMOVED OR, IF APPROVED BY THE COUNTY, USED ON SITE, AND THE AREA TOPSOILED, DRILL SEEDED AND CRIMP MULCHED OR OTHERWISE STABILIZED. <p>WW VTC WITH WHEEL WASH 26</p>
--	--	---	--	--

DETAIL

SHEET

LEGEND

<u>NO.</u>	<u>NO.</u>			
1	(1)		(CBC)	CUT BACK CURB
2	(1)		(CD)	CHECK DAM
3	(1)		(CWA)	CONCRETE WASHOUT AREA
4	(1)		(CF)	CONSTRUCTION FENCE
5	(1)		(CM)	CONSTRUCTION MARKERS
6	(1)		(CS)	CURB SOCK
7	(1)		(DW)	DEWATERING
8	(2)		(DD)	DIVERSION DITCH
9	(2)		(ECB)	EROSION CONTROL BLANKET
10	(2)		(GMS)	GROUT MIXING STATION
11	(2)		(IP)	INLET PROTECTION
12	(2)		(RCD)	REINFORCED CHECK DAM
13	(2)		(RRB)	REINFORCED ROCK BERM
14	(2)		(RRC)	RRB FOR CULVERT PROTECTION
15	(2)		(SB)	SEDIMENT BASIN
16	(3)		(SCL)	SEDIMENT CONTROL LOG
17	(3)		(ST)	SEDIMENT TRAP
18	(3)		(SM)	SEEDING AND MULCHING
19	(3)		(SF)	SILT FENCE
20	(3)		(SID)	SLOPE INTERCEPT DITCH
21	(3)		(SSA)	STABILIZED STAGING AREA
22	(4)		(SR)	SURFACE ROUGHENING
23	(4)		(TSD)	TEMPORARY SLOPE DRAIN
24	(4)		(TSC)	TEMPORARY STREAM CROSSING
25	(4)		(VTC)	VEHICLE TRACKING CONTROL
26	(4)		(WW)	VTC WITH WHEEL WASH



(LOC) ROCK AND RIPRAP GRADATIONS LIMITS OF CONSTRUCTION

(*EG) MAY MEET MAJOR MODIFICATION REQUIREMENTS

Appendix I - Definitions

Abatement: A form of enforcement where SEMSWA may step in and take necessary action to mitigate non-compliance issues. The entity must incur the costs of SEMSWA's actions.

Authorized Agent: Individual or agency responsible for maintaining compliance with the GESC permit requirements.

Burden of Proof: The obligation resting on a party to provide sufficient evidence for their position.

Check Dam (CD): Small rock dam designed to withstand overtopping, that is placed in a small stream or drainage way. The purpose of the check dam is to trap sediment-laden water in the backwater zone upstream of the check and to reduce flow velocities in a channel.

Collateral: All standard GESC Permittees and some Low Impact Permittees are required to post collateral in the form of Irrevocable Letter of Credit from a Colorado Bank or Colorado Branch, or Cash Escrow in the form of a check. If the Collateral is in the form of a Letter of Credit, then the expiration date must be for a minimum of two years. The amount of collateral is based on the cost estimate of installing and maintaining the grading, erosions, and sediment controls required on a site.

Compensatory Action: Failure to comply with GESC requirements may result in temporary actions to mitigate the violation(s).

Concrete/Grout Washout Area (CWA, GWA): Shallow excavation with a small perimeter berm to isolate concrete truck washout operations.

Construction Activities: Refers to ground surface disturbing and associated activities (land disturbance), which include, but are not limited to, clearing, grading, excavation, demolition, installation of new or improved haul roads and access roads, staging areas, stockpiling of fill materials, and borrow areas. Construction does not include routine maintenance to maintain the original line and grade, hydraulic capacity, or original purpose of the facility. Activities to conduct repairs that are not part of regular maintenance or for replacement are construction activities and are not routine maintenance. Construction activity is from initial ground breaking to final stabilization regardless of ownership of the construction activities.

Construction Fence (CF)/ Construction Markers (CM): Consists of orange plastic fencing, or other approved material, attached to support posts and used to control access to the construction site and delineate limits of construction.

Control Measure: Refers in the GESC Manual to a measure implemented by a contractor to control construction site erosion, sediment and waste. *Previously referred to as a Best Management Practice (BMP).

Control Regulation 72: The Cherry Creek Reservoir Control Regulation (5 CCR 1002-72).

Dewatering (DW): Consists of a gravel filter provided on the suction end of a pump to reduce the pumping of sediment and a rip rap pad at the discharge end of the pump to provide erosion protection. Dewatering includes settling the discharge water in a small basin or sediment pond before releasing to receiving waters.

Dewatering Permit: CDPS Permit issued by the Water Quality Control Division for the discharge of construction dewatering source water to waters of the state. Construction dewatering source water means groundwater, surface water, and stormwater that have mixed with the groundwater and/ or surface water (i.e. commingled stormwater runoff) that has come into contact with Construction Activities.

Diversion Ditch (DD): Small earth channel used to divert and convey runoff to a sediment basin, check dam, or drainage way.

Engineering Cost Estimate (ECE): Applicants are required to provide an estimate associated with implementing the GESC Permit documents. The ECE provides unit cost information that is used to generate the cost estimate. The ECE is used to quantify the collateral required for a project.

Erosion Control Blanket (ECB): Fibrous blanket of straw, excelsior, or coconut material trenched in and staked down over prepared, seeded soil. The matting reduces both wind and water erosion.

Grading, Erosion, and Sediment Control (GESC) Drawings: Illustrative portion of the GESC Plan that shows the location and extent of all grading, erosion, and sediment control BMPs as well as other associated information required by the GESC Manual.

Grading, Erosion, and Sediment Control (GESC) Inspector: SEMSWA representative who visits construction sites to check for compliance with the GESC Permit.

Grading, Erosion, and Sediment Control (GESC) Manager: On-site representative who serves as the Permittee(s) contact person with SEMSWA and who is responsible for ongoing compliance with the GESC Permit.

Grading, Erosion, and Sediment Control (GESC) Permit: Permit obtained from SEMSWA prior to commencement of land disturbing activities as described in the SEMSWA GESC Manual.

Grading, Erosion, and Sediment Control (GESC) Plan: Plan submitted to SEMSWA for review and acceptance including GESC Drawings and the GESC Drawing and Report Checklist.

Grading, Erosion, and Sediment Control (GESC) Report: Report required to be submitted with the GESC Plan that details all aspects of the GESC Plan such as soils, areas, and volumes, etc.

Grout Mixing Stations (GMS): Contained area to isolate grout and/or mixing operations. A GMS shall be provided when masonry work is performed.

Hold Harmless Letter: Must be submitted if applicant wishes to obtain a GESC permit before the Construction Drawings are approved. The project must have received favorable recommendation from the Planning Commission or City Council. A letter acknowledging that the applicant is proceeding at their own risk and that there may be revisions that the applicant is required to implement after construction begins.

Illicit Discharge: Any prohibited direct or indirect non-stormwater discharge into the MS4.

Inlet Protection (IP): Reinforced rock berm placed in front of (but not blocking) a curb-opening inlet around an area inlet to reduce sediment in runoff entering the inlet.

Insert Slope Intercept Ditch (SID): Small earth channel with accompanying earthen berm cut in on the contour used to check stormwater surface flows from leaving a construction site and to prevent run-on of stormwater surface flows from undisturbed areas contiguous with the construction site.

Land Disturbing Activity: Any activity that results in a change in the existing land surface (both vegetative and non-vegetative). Land disturbing activities include, but are not limited to clearing, grading, excavation, demolition, installation of new or improved haul roads and access roads, staging areas, stockpiling of fill materials, and borrow areas. Compaction that is associated with stabilization of structures and road construction shall also be considered a land disturbing activity.

Larger Common Plan of Development or Sale: A contiguous area where multiple separate and distinct construction activities may be taking place at different times on different schedules, but remain related. The Division has determined that “contiguous” means construction activities located in close proximity to each other (within ¼ mile).

Limits of Construction: Area shown in the GESC Plan that delineates areas in which construction activities can take place including staging, storage, and stockpiling.

Major Modifications: Modifications to the GESC plan involving re-engineering, or changes to the site hydrology, which may include changes to grading, drainage, design intent, beyond limits of a Control Measure, or eliminating a Control Measure. Control Measures that may meet Major Modification requirements are indicated with a “box” on the Legend in Appendix G.

Minor Modifications: Modifications to the GESC plan made throughout the project to address changes in site conditions that do not meet the Major Modifications definition and are generally a like for like, or more suitable Control Measure substitution.

Municipal Separate Storm Sewer System (MS4): State, city, town or other public entity-owned conveyance or system of conveyances (including roads with drainage systems, municipal streets, catch basins, curbs, gutters, ditches, man-made channels, or storm drains) designed to collect or convey stormwater.

Notice of Violation (NOV): A written notice provided by a SEMSWA GESC Inspector if a site is found to be in non-compliance with the GESC requirements. Violations must be remedied within 48 hours, or a Stop Work Order may be issued.

Permittee(s): Owner and Contractor that obtain a GESC Permit.

Reinforced Rock Berm (RRB): Linear mass of gravel enclosed in wire mesh to form a porous filter, able to withstand overtopping. The berm is heavy and stable and promotes sediment deposition on its upstream side as well as reducing flow velocities.

Sediment Basin (SB): An impoundment that captures sediment-laden runoff and releases it slowly, providing prolonged settling times to capture coarse and fine-grain sediment.

Sediment Control Log (SCL): Cylindrical bundle of excelsior, straw, or coconut designed to form a semi-porous filter, able to withstand overtopping, and promote sediment deposition on the upstream side and reducing flow velocities.

Sediment Trap (ST): Riprap berm with a small upstream basin that acts to trap coarse sediment particles.

Seeding (SE) and Mulching (MU): Consists of drill seeding disturbed areas with permanent grasses and mechanical crimping of straw mulch to provide immediate protection against raindrop and wind erosion and, as the grass cover becomes established, to provide long-term stabilization of exposed soils.

Silt Fence (SF): Temporary sediment barrier constructed of woven fabric stretched across supporting posts. The bottom edge of the fabric is placed in an anchor trench that is backfilled with compacted soil.

Stabilized Staging Area (SSA): Refers to stripping topsoil and spreading a layer of granular material in the area to be used for a trailer, parking, storage, unloading, and loading. A stabilized staging area reduces the likelihood that the vehicles most frequently entering a site are going to come in contact with mud.

Stop Work Order: A written notice provided by a SEMSWA GESC Inspector that revokes a GESC Permit as a result of a priority violation; Contractors receiving a Stop Work Order shall cease construction operations until the problem is addressed and a signed Stop Work Order Release Form is obtained.

Stormwater: Runoff generated from a precipitation event.

Stormwater Construction Permit: CDPS permit issued by the Water Quality Control Division to discharge stormwater associated with construction activities into waters of the state of Colorado.

Street Sweeping (SS): Consists of cleaning mud and other debris which is tracked onto impervious surface at a construction site. Street sweeping shall be used for incidental tracking and is not intended to be used as the sole BMP.

Public Improvements Agreement (PIA): Obligates the developer/owner to install the public facilities per the approved plans and fulfill any additional requirements specific to the site.

Surface Roughening (SR): Consists of creating a series of grooves or furrow on the contour in all disturbed, graded areas to trap rainfall and reduce the formation of rill and gully erosion.

Temporary Slope Drain (TSD): A small culvert or plastic lined channel to convey runoff down a slope or channel bank to reduce the occurrence of a rill and gully erosion.

Temporary Stream Crossing (TSC): A rock layer placed temporarily in a stream to allow construction equipment to cross. A stream crossing may include culverts or provide a low-water crossing, or ford.

Variance: A formal request made to SEMSWA by the Permittee to modify or alter existing engineering standards for a specific project.

Vehicle Tracking Control (VTC): Pad of rock at all exit points for a site that is intended to help strip mud from tires prior to vehicles leaving the construction site.

Waters of the State (of Colorado): Any and all surface waters and subsurface waters which are contained in or flow in or through this state, but does not include waters in sewage systems, waters in treatment works of disposal systems, waters in potable water distribution systems, and all water withdrawn for use until use and treatment have been completed. This definition can include water courses that are usually dry.